



## LHC Injectors Upgrade

# A new RF system for the PSB.

Wide working group involved including :

S.Albright, M.E.Angoletta, L.Arnaudon, M.Brugger, N.Chritin, A.Findlay, M.Haase, J.Hansen,  
M.Jaussi, A.Jones, J-M.Lacroix, D.Landre, J.Molendijk, M.Paoluzzi, D.Quartullo, B.Riffaud,  
C.Rossi, J.Sanchez Quesada, E.Shaposhnikova, .....

.....and many more.

LIU-PSB Working Group Meeting, 10th December 2015



- 1. Brief historical recall***
- 2. Proven performances***
- 3. System characteristics***
- 4. Cavities arrangement.***
- 5. Available space and layout in the ring.***
- 6. Issue with pick up.***
- 7. Layout in equipment rooms.***
- 8. Required parts and installations.***
- 9. Installation planning.***



# Brief historical recall

- *PSB RF system consolidation requires heavy interventions in existing RF systems :*
  - *intensity and energy increase → Linac 4.*
  - *consolidation of ageing equipment.*
- *Deep and costly interventions required on the C02 and C04 RF systems:*
  - *Finemet system studies launched to face new requirements and changes.*
- *Studies converged into a new approach which:*
  - *maximize the advantages of the wideband response of Finemet*
  - *use of solid-state amplifiers.*
- *A wide range of issues had to be addressed:*
  - *RF power production*
  - *Radiation hardness of solid-state devices*
  - *Dedicated low-level electronics for active cancellation of beam-induced voltages*
  - *Dedicated low-level electronics allowing multi-harmonic operation.*
  - *Beam stability issues*
- *New system performance finally also allow controlled blow-up:*
  - *abandon C16 upgrade.*

***The project study phase is now completed, results reported at the project review and full deployment plan endorsed by the management.***



# Proven performances

- *Beam tests proved the system ability to produce intense beams equivalent to what achieved with standard operation.*
- *System capable of operation at h1, h2 and h10.*
- *All system components are largely within thermal and current limits even at high duty-cycles.*
- *Effects of radiation on the amplifiers in the ring can be mitigated and re-adjustments needed every 10 years.*
- *The LL digital electronics compensate beam loading and maintain beam stability.*
- *Extrapolations indicate that operation will be possible at 2GeV and beam intensities as high as  $2 \cdot 10^{13}$  ppp.*



# System characteristics.

- *Modular system based on wideband, solid-state driven identical cells.*
- *High performance digital Low Level electronics:*
  - *Multi-harmonic operation (8, 12 or more beam revolution frequency harmonics)*
  - *Voltage allocation at the most appropriate frequency*
  - *Active cancellation of beam induced voltage.*
  - *Active gap impedance reduction*
- *Ample margins and reserves.*
  - *RF power amplifier designed to ensure operation with 2 broken RF Mosfets out of 16.*
  - *System designed to ensure operation with 6 broken cells per ring.*
- *PLC interlocks individually tracing the characteristics of the RF Mosfets, RF amplifiers, radiation effects, etc.*
- *PLC / Low Level electronics communication ensures best performance with available number of cells.*





# System characteristics.

Parameter	Value
Operation Frequency	1 MHz to 18 MHz
Operation mode	Single frequency or multi-harmonic
Single cell voltage Freq < 4 MHz Freq > 4 MHz	700 V <sub>pk</sub> Linearly derate to 250 V <sub>pk</sub>
Total nominal voltage Freq < 4 MHz Freq > 4 MHz	24 kV <sub>pk</sub> Linearly derating to 4 kV <sub>pk</sub>
Cell length	130 mm
Number of cells in a cavity	6
Number of cavities per ring	6



# Cavities arrangement (preliminary).


- *Two 6-gaps units can be installed in each section and ring.*
- *Amplifier installed on one side only. Other side available for future improvements.*
- *Cavities and power amplifiers cooled by demineralized water.*
- *Negligible contribution to air heating.*





# Available space in the machine.

Four sections presently attributed to RF systems: 5L1, 7L1, 10L1 and 13L1









# Proposed layout in the ring.

*Use of three sections for new RF systems: 5L1, 7L1 and 13L1. Section 10L1 in stand-by.*






# Proposed layout in the ring.





**13L1**







# Proposed layout in the ring.

7L1





# Proposed layout in the ring.



**5L1**



# Issue with BPP5L1 pick-up.

*Section 5L1 presently filled with :*

- *The C16 RF system*
- *The pick-up BPP5L1*

*Both to be removed to allow the new installation.*

*Existing pick-up installed in sections:*

- *1L5, 8L1, 11L2 : not used*
- *5L1, 14L4 : 1 in use and 1 spare*

*Proposed future pick-up arrangement :*

- *1L5 : not used may be removed*
- *8L1, 11L2 : 1 in use and 1 spare*
- *5L1 : removed*
- *14L4 : not used may be removed*



*Proposed strategy agreed by*

- *RF : A. Blas and A. Findlay*
- *BI : L. Soby*
- *OP : B. Mikulec*

*During 2015-2016 YETS*

*Head amplifiers installed in 8L1 and tested during 2016.*


*During 2016-2017 EYETS*

*Head amplifiers will be installed in 11L2 and tested during 2017.*

*Removals, changes etc. to be discussed with TE/VSC*




# Rack Layout: FINEMET control for one Section



- *Racks for control electronic and interlock: section 5L1, 7L1 and 13L1*
- *Each cavity 1 control rack*
- *For one section (4 cavities) 4 control racks plus one interlock rack*
- *Three systems 15 control racks*




# Rack Layout: Power Supplies for one Section



- *Racks for power supplies: section 5L1, 7L1 and 13L1*
- *Each cavity 2 racks with power supplies one section 8 racks*
- *Three systems 24 racks with power supplies*



# Booster 361/1



M. Haase  
December 10<sup>th</sup> 2015








# BRF 1 LAYOUT LS2

**POWER SUPPLIES  
13L1**




**CONTROL RACKS  
13L1**

**CONTROL RACKS  
7L1**






# BRF2 LAYOUT LS2: FINEMET SECTION 5L1





# BAT Layout LS2 Access Period 7L1

Rack structure in LS2  
Rack installation in LS2



G. Georgiev






# Required parts and installations.

- **The modular system has the advantage of being mostly composed of standardized units:**
  - **The 6-gaps cavity** **24 units + 2 spare**
  - **The RF amplifier** **144 units + 20 spares**
  - **40V 200A power supply** **144 units + 20 spares**
  - **30V 50A power supply** **24 units + 3 spares**
  - **Ancillary electronics and RF drivers** **24 units + 3 spares**
  - **PLC interlocks** **24 units + 1 spares**
- **Additional components/contributions will be:**
  - **Cooling water distribution** - S. Moccia informed (EN-CV) :  $\approx 48\text{m}^3/\text{hr}$  per section
  - **Cabling** - G. Minchev informed (EN-EL) : **Remove  $\approx 2000$  / install  $\approx 1200$  cables**
  - **Power distribution & cabling** - J. Devine informed (EN-EL)
  - **Timing and intranet**
  - **Rack integration BRF1 / BRF2 /BAT**
- **Dedicated test place for parts acceptance, test and maintenance.**



# Installation planning.

All system elements will be assembled, tested in the test place and ready for installation before beginning of LS2.



6 months to remove equipment

8 months for installation

8 Months commissioning/testing

