

HOM considerations for Energy Recovery Linacs and other high-current, CW SRF accelerators

Georg Hoffstaetter (Cornell) for the SRF and CBETA team

- (1) Cavity design and construction for high BBU current
- (2) Beam-pipe HOM absorber design and construction
- (3) HOM testing with and without beam
- (4) Beam limits from HOM heating
- (5) BBU limits for multi-turn ERLs with realistic HOM

High Order Modes in Superconducting Cavities
HOMSC16, 22 – 23 August, 2016




Cornell Laboratory for
Accelerator-based Sciences and
Education (CLASSE)






- Cornell DC gun
- 100mA, 6MeV SRF injector (ICM)
- 600kW beam dump
- 100mA, 6-cavity SRF CW Linac (MLC)

Existing components at **Cornell**







ePHENIX




eSTAR



BeAST




courtesy Thomas Roser





- $1.7 \times 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$ for $\sqrt{s} = 127 \text{ GeV}$ (15.9 GeV $e\uparrow$ on 255 GeV $p\uparrow$)
- $\times 10$ luminosity with modest improvements (coating of RHIC vacuum chamber)
- $\times 100$ luminosity with shorter bunch spacing (ultimate capability)



- eRHIC uses two FFAG beamlines to do multiple recirculations. (FFAG-I: 1.7-5.0 GeV, FFAG-II: 6.7-18.3 GeV, 20 GeV)
- All sections of a FFAG beamline is formed using a same FODO cell. Required bending in different sections is arranged by proper selection of the offsets between cell magnets (or, alternatively, with dipole field correctors).
- Permanent magnets can be used for the FFAG beamline magnets (no need for power supplies/cables and cooling).



@S.Brooks, D.Trbojevic





Each of two eRHIC FFAGs contain 1066 FFAG cells

Some of the most important risk items for eRHIC:

- 1) FFAG loops with a factor of 4 in momentum aperture.
 - a) Precision, reproducibility, alignment during magnet and girder production.
 - b) Stability of magnetic fields in a radiation environment.
 - c) Matching and correction of multiple simultaneous orbits.
 - d) Matching and correction of multiple simultaneous optics.
 - e) Path length control for all orbits.

- 2) Multi-turn ERL operation with a large number of turns.
 - a) HOM damping.
 - b) BBU limits.
 - c) LLRF control and microphonics.
 - d) ERL startup from low-power beam.





Background for CDR

Wrote PDDR for hard X-ray ERL
at Cornell in 2012.

Start of CBETA July 2014 White
paper December 2014

CDR scheduled for magnet
prototypes.

Planned for completion of optics
and layout for CDR.

Scheduled this Review to
include advise on CDR.


Plan to include committee
advise by the end of July.

DRAFT CBETA Conceptual Design Report

Cornell-Brookhaven ERL Test Accelerator

Editors: G. Hoffstaetter and D. Trbojevic

Contributors: J. Barley, I. Bazarov, A. Bartnik, I. Ben-Zvi, J. S. Berg, S. Brooks, D. Douglas, J. Dobbins, B. Dunham, R. Eichhorn, R. Gallagher, C. Gulliford, G. Hoffstaetter, Y. Li, M. Liepe, W. Lou, G. Mahler, C. Mayes, F. Méot, M. Minty, R. Patterson, S. Peggs, V. Ptitsyn, T. Roser, D. Sabol, E. Smith, J. Tuzzolo, D. Trbojevic, N. Tsoupas, H. Witte



June 7, 2016



Track Record:

- a) ERL injector with world-record current (10 times more than the next)
- b) ERL injector with world-record emittance (5 times less than the next)
- c) SRF cavity shape for high current (30 times more than the next)
- d) SRF R&D for ERL Light Sources with world-record low energy loss
- e) High Brightness Beam Physics (first full hard x-ray ERL design)

Facilities and Capabilities:

- About 120 accelerator-related employees with decades of experience in accelerator building and operation at the worlds forefront.
- Facilities and experience for building full SRF accelerators and DC guns.
- Space for a 100mA, > 36MeV per turn ERL.



LOE contained approximately 7,000 square feet of Lab and Shop space





70% of the existing technical-use space was removed for the initial phase






The initial installation was completed for the MLC and ERL beamline






The second phase will accommodate the new loop-layout






The second phase is almost complete





- six packages of 7-cell cavity/Coupler/tuner
- a SC magnets/BPMs package (magnet not installed)
- five regular HOMs/two taper HOMs






- MLC assembly was completed
- Cooled down fall 2015, field, Q, and microphonics tested.
- Further cold studies will start August 2016




- Central focus: Maximize threshold current through ERL
- Optimization over ~ 100 degrees of freedom
 - Center cell geometry
 - End cell geometry
 - Beam line HOM absorbers
- Simulate ERL performance with realistically shaped cavities



Goal: Maximize $I_{th} > 100$ mA
(under constraints)

Center cells

- Geometries are (nominally) identical
- Responsible for general properties of HOM spectrum
 - Controls frequencies of HOM passbands and dispersion relations
 - Determines cell-to-cell coupling and how sensitive HOM spectrum is to variation in cell shape




Goal: Maximize $I_{th} > 100$ mA
(under constraints)

Center cells

- Geometries are (nominally) identical
- Responsible for general properties of HOM spectrum
 - Controls frequencies of HOM passbands and dispersion relations
 - Determines cell-to-cell coupling and how sensitive HOM spectrum is to variation in cell shape

End cells

- Asymmetric design helps prevent trapped modes
- Responsible for coupling HOMs to HOM absorber
 - Directly controls quality factors of HOMs



Goal: Maximize $I_{th} > 100$ mA
(under constraints)

Center cells


- Geometries are (nominally) identical
- Responsible for general properties of HOM spectrum
 - Controls frequencies of HOM passbands and dispersion relations
 - Determines cell-to-cell coupling and how sensitive HOM spectrum is to variation in cell shape

End cells

- Asymmetric design helps prevent trapped modes
- Responsible for coupling HOMs to HOM absorber
 - Directly controls quality factors of HOMs

Beam Pipe

- Should be short to improve linac fill factor but long enough to avoid dissipating too much power from the fundamental mode



Goal: Maximize $I_{th} > 100$ mA
(under constraints)

Center cells

- Geometries are (nominally) identical
- Responsible for general properties of HOM spectrum
 - Controls frequencies of HOM passbands and dispersion relations
 - Determines cell-to-cell coupling and how sensitive HOM spectrum is to variation in cell shape

End cells

- Asymmetric design helps prevent trapped modes
- Responsible for coupling HOMs to HOM absorber
 - Directly controls quality factors of HOMs

Beam Pipe


- Should be short to improve linac fill factor but long enough to avoid dissipating too much power from the fundamental mode

HOM load


- Absorber material properties determine specific mode losses.



Baseline Center Cells




Enhanced cell-to-cell coupling





○ HOM properties with no fabrication variation

× HOM properties with 1/16 mm variation


Band	1.8 GHz	1.9 GHz	2.5 GHz	2.7 GHz	3.1 GHz	3.4 GHz
Baseline Design	192	95	31	277	55	10
New Design	188	73	107	227	47	20




Absorbing Material:
Doped SiC (SC-35
from Coorstek



Cooling Passage
Configuration of 80K
Cooling Jacket



The HOMSC workshop series started in 2010 with a call to discuss development of this HOM absorber.




Horizontal Test Cryostat:


16MV/m, 1.8K: $Q_0 = 2.E10$
(reached with coupler)

$Q_0 = 3.5E10$ without coupler

$Q_0 = 6E10$ with coupler and HOM
absorbers (held the world record)


- Much better Q_0 than the ERL spec.
- Increased state of the art expectations for other projects, e.g. LCLS-II.
- Became essential for high- Q cavity research, incl. for N-doped cavities.






Beamline HOM absorbers
strongly damp dipole
HOMs to under $Q \sim 10^4$

HTC-2: No HOM Absorbers
HTC-3: With HOM Absorbers






Current, bunch length	ΔT (beam pipe behind Abs.) coated/uncoated	ΔT (80K gas temp) coated/uncoated	ΔT (80K absorber temp) coated/uncoated	ΔT (5K flange next to cavity) coated	ΔT , beam pipe to cavity coated/uncoated
25 mA, 3.0 ps	0.075/0.075	1.14/0.82	1.02/0.975	0.007	0.076/-0.005
40 mA, 3.4 ps	0.2475/0.335	2.95/2.16	2.72/2.53	0.021	0.179/0.009
40 mA, 2.7 ps	0.2975/0.425	3.00/2.22	2.772/2.63	0.027	0.203/0.014


- No charge-up of the HOM absorber observed.
- HOM heating was less than expected, limits to 400mA total ERL current.
- **This establishes the current limit of 40mA for the 4-turn CBETA ERL**





■ Initial cool ■ 1st thermal cycle w/ fast cool ■ 2nd thermal cycle w/ slow cool



- 5 of 6 cavities had achieved design gradient of 16.2MV/m at 1.8K in MLC.
- Cavity#4 is limited by quench so far, no detectable radiation during test.
- **Enough Voltage for 76MeV per ERL turn (where 36MeV are needed)**



- 4 of 6 cavities had achieved design Q_0 of 2.0×10^{10} at 1.8K.
- Q_0 of Cavity#6 had severe FE at 16MV/m.
- **Enough cooling for 73MV per ERL turn (where 36MeV are needed)**



Dipole HOMs on MLC were strongly damped below $Q \sim 10^4$.
Consistent with HTC and simulation results.


HTC results were:

- HOM heating: currents are limited to $< 40\text{mA}$ in CBETA
- BBU no HOM limits BBU to below 100mA in one turn




Count

CBETA 1-pass
Cavity shape error: 125 μm



100% of simulations have $I_{th} > 100\text{mA}$



CBETA 4-pass

Cavity shape error: 125 μm


x/y coupling is simulated to increase the threshold significantly

100% of simulations have $I_{th} > 100\text{mA}$

86% of simulations have $I_{th} > 40\text{mA}$

- Cornell DC gun
- 100mA, 6MeV SRF injector (ICM)
- 600kW beam dump
- 100mA, 6-cavity SRF CW Linac (MLC)

Existing components at Cornell




Cornell is building a 4-turn Energy Recovery Linac (ERL) with a beam current limited by HOMs through

- (a) HOM heating
- (b) The Beam-Breakup (BBU) instability

Cornell has already built the Injector Cryomodule (ICM) and the Main Linac Cryomodule (MLC) with beam-pipe HOM absorbers.

- The ICM has accelerated 75mA CW without HOM-heating problems.
- The cavity arrangement of the MLC with HOM absorbers has been tested with beam.
- HOM-absorber heating limits to 320mA in the MLC, or 40mA for a 4-turn ERL beam.
- HOM measurements with and without beam indicate the a 1-turn ERL with 100mA should be possible.
- BBU calculations: 100mA one-turn ERL is possible, 4-turn ERL may be possible

To operate accelerators CW linacs with larger currents, HOM absorption at room temperature become advisable. Designs for this should be developed.





Questions Discussion ?