



Wendelstein 7-X: first experience with the cryogenic system

Presented by: Chandra Prakash Dhard

Chandra Prakash Dhard, Michael Nagel, Sylvio Raatz, Holger Bau, Uwe Meyer, Konrad Riße, Thomas Rummel and W7-X team

Max-Planck-Institut fuer Plasmaphysik
Wendelsteinstrasse 1, 17491 Greifswald, Germany

1. Introduction

- Wendelstein 7-X (W7-X) stellarator
- Cryogenic system

2. Operation of cryogenic system

- First cool-down, different modes of operation, warm-up
- Personnel: Shifts, on call duty

3. Problems, concerns, further improvements

- Operational, equipments, controls, external supply systems
- Helium gas management
- Maintenance: preventive, scheduled

4. Summary and future operations


1. Introduction

W7-X Stellerator overview







Machine height: 4.5 m
Machine diameter: 16 m
Machine mass: 725 t
Cold mass: 425 t


Major radius: 5.5 m
Minor radius: 0.53 m
Plasma volume: 30 m³
Non-planar coils: 50
Planar coils: 20
Number of ports: 254
Induction on axis: < 3 T
Stored energy: 600 MJ
Heating power: 10 MW
Duration: 30 min




1. Torus assembly sequence



1. Torus assembled




2. Helium refrigerator layout



Refrigerator supplied by Linde Kryotechnik AG

2. Refrigerator: schematics




Standard mode (3.9 K, 2.5 Tesla)

Guarantee value and (measured average value during refrigerator acceptance test)

<u>Appl.</u>	<u>Heat load</u> W	<u>Mass flow</u> g/s	<u>ΔP</u> Bar	
Casing (3.87K)	1800 (1835)	300 (307)	0.1 (0.2)	
Coils (3.84K)	800 (808.6)	200 (216)	0.7 (0.8)	
	450 (508.5)	250 (255)	0.6 (0.53)	
				T_{in} K
Shield	14000 (14553)		<70K (61K)	
Leads		15 (15.43)	~4.5K (~4.5K)	
LHe used (Dewar)		-22.5 (-18.65)		
LN2+ LHe used		-31.5 (-27.4) -15 (-14.35)		

2. Cold compressors / pumps



Forced flow, subcooled helium

Phase separators: PS1 (4.5K), PS2 (3.8K), PS3 (3.3K)

Peak power mode: Both cold compressors & 4 pumps in operation

Standard mode: 1 cold compressor & 2 pumps in operation



2. Cold compressor parameters

Parameters	Units	Cold compressor (CC1) (3.9K operation)		Cold compressor (CC2) (3.4K operation)	
		SM	PPM	SM (Not operating)	PPM
Mass flow	g/s	102.8	113.3	--	126.6
Suction pressure	mbar a	640	760	1250	350
Suction temperature	K	12.8	10.8	6	5.25
Discharge pressure	bar a	1.25	1.25	1.25	1.25
Discharge temperature	K	18.4	14.2	--	10.2
Efficiency Isentropic	%	≥ 70	≥ 70	--	≥ 70
Heat inleak with intercept cooling	W	≤ 50	≤ 50	≤ 50	≤ 50



 První brněnská strojírna
Velká Bíteš, a. s.



Supplied by Linde Kryotechnik in close cooperation with PBS



2. Cold pumps parameters



Parameters	Units	Pumps for casings & structure (CS)		Pump for coils		Pump for CVP	
		SM	PPM (2 pumps)	SM (Not operating)	PPM	SM	PPM
Mass flow	g/s	306	816	--	275	255	255
Suction pressure	bar	3	3	3	3	3	3
Suction temperature	K	5.09	4.3	5.09	4.3	4.5	4.14
Discharge pressure	bar	≥ 3.15	3.46	--	5.38	3.66	3.66
Discharge temperature	K	5.2	4.38	--	4.74	4.61	4.26
Efficiency Isentropic	%	≥ 55	≥ 55	≥ 55	≥ 55	≥ 55	≥ 55



Supplied by Linde Kryotechnik
in close cooperation with PBS



2. Various components / parameters



Cold box



Cold pump




No.	Device
7 kW	Refrigerator power at 4.5 K
2	Screw compressors 1.6 MW electrical power
1 2	Oil removal system Dryers
3	Pressure levels 1.1; 3-4; 11-17 bar
7	Turbines in cold box
1	Phase separator
2	Sub coolers with cold compressors
4	Cold circulators
1	LHe - dewar
5	Different consumers

2. Preperation of cryogenic system

Cryogenic system: refrigerator, supply lines to cryostat, piping inside the cryostat, current leads, quench gas exhaust system

- Verification that assembly and tests had been done successfully
- Flushing procedure:
 - filling to 3 bars, rapid expansion, gas was filtered
 - at least three times
 - inside cryostat pressure increased from 3 to 12 bars
- Pumping and filling of the single cooling circuits (three times):
 - evacuated to 30 mbar
 - filled to 1 bar with helium
- Cleaning using the dryer and cold adsorber of refrigerator
 - first cleaning of single circuits, than all circuits together
 - impurity less than 10 vpm for nitrogen
 - 4 weeks cleaning time
- Inside the cryostat:
 - helium leak rate better than $3 \cdot 10^{-5}$ mbar *l/s (warm condition)
 - - vacuum $2 \cdot 10^{-4}$ mbar before cool down

2. W7-X first cool-down



- cold mass 456 tons
- $\max(\Delta T) = 40 \text{ K}$
- cool down rate 1 K/h
- cryostat pressure
10⁻⁴ mbar (warm)
10⁻⁷ mbar (cold)
- helium leak rate at 4 K
 $\approx 5 \cdot 10^{-5} \text{ mbar} \cdot \text{l/s}$

- Parallel cool down of cryostat and refrigerator
- Visual checks, no ice formation or water condensation on cryostat or components
- No vibrations or fluctuations
- Check of flow distribution in circuits
- Check of displacement sensors at coils, at GFK-supports at magnet structure and at CL
→ Displacements within predicted range!
- Smooth cool down in 4 weeks

2. Heat load & flow conditions

Mode	SM (3.9 K)			SSM (<10 K)
	Coil housing and structure	Conductor cooling	Shield cooling	Coil conductor, housing and structure
Feed temperature [K]	3.9	3.9	50	5.2
Flow rate [g/s]	300	200	110	160
Heat Load [W]	426	256	5600	566
Design value for heat load [W]	1800	800*	9000	1800
Pressure drop [mbar]	140	360	1180	140-290


* design value for refrigerator performance

SSM = short stand by mode
SM = standard mode


- ✓ Specified mass flow rates achieved
- ✓ Pressure drop within limits
- ✓ Average thermal loads on shield 4 W/m²
- ✓ Average thermal loads on cold structure 0.55 W/m²
- ✓ Conductor outlet temperatures between 4.0 to 4.7 K

2. Helium cooling during current load steps


- Non-planar coils: 12.8 kA, planar coils: 5.0 kA
- Cooling with helium flow (3.7 bar, 3.9 K)



2. Coil temperatures during magnets operation




Helium outlet temperature of the coil conductor cooling



Helium outlet temperature of coil housing cooling

- Current ramp 15 A/s from 0 to 12.8 kA in the NPC
 - ➔ Maximum 200 mK temperature increase due to eddy currents
- Stable current operation with 12.8 kA
 - ➔ in the average $\Delta T = 50$ mK for conductor cooling
 - ➔ $\Delta T = 10$ mK for coil housing cooling
 - ➔ low ohmic heating, good quality of joints

2. First plasma operations



3.2.2016, 15:21:25.822 (local time)



- Plasma campaign 10.12.2015 – 10.03.2016
- 1st Helium plasma: 10.12.2015
- 1st Hydrogen plasma: 03.02.2016
- Plasma parameters achieved:
 - ✓ Pulse time upto 6s
 - ✓ ECRH energy upto 4MW
 - ✓ Temp_electron upto 9 keV
 - ✓ Temp_ion upto 2 keV
 - ✓ Density $\sim 2 \dots 3 \times 10^{19}/\text{m}^3$

3. W7-X warm-up



Temp diff. ($T_{\max} - T_{\min}$) ≤ 40 K
Took about 6 Weeks

Temp. on hold during Easter vacations


2. Operation personnel / duties

- 3 shift operation: Cool-down & warm-up
- 2 shift operation: Standby modes (SSM, LSM), standard mode
 - On call duty for the night shift (1 colleague from Cryo)
 - On call duty for the night shift (W7-X main operation team & other systems)
 - Refrigerator sends the alarm by itself in case of problems
- 2 colleagues / shift: 1 electrical/controls + 1 mechanical
- The responsible officers (refrigerator operation), available in normal working hours and on call duty (under rotation)
- Cryo group has 17 colleagues, 12 from these are under regular shift duty, others substitute in case of need and remain available for on call duty

3. Problems, concerns, learnings ...

- Operational: training while operating
- Controls: Optimize the logic program (& online reload), input table values, controller parameters, old computers → being updated
- Instrumentation:
 - Temperature sensor malfunctioning (often) leading to operational problems → online change if possible, removing from logic, keep enough spares, within W7-X cryostat not possible to access → rely on redundant ones
- Valves:
 - Seat leakage → plug seals changed
 - Oscillations (pressure/level) → building intercepts on the stem
 - End position switches: leading to trips (component/refrigerator) → logic rethinking
 - Abrupt opening, blocking at a level → controller changed
- Cold machinery:
 - Cold compressors: limited operating range
 - Cold pumps: Spindel bearings
- Cooling water system: auto switchover (redundant), motor change
- External supply systems: Cooling tower (freezing in winter, suppl. temp. limit in summer), electricity
- Lessons: prepare for online changes/replacement, keep enough spares

3. Number of failures during OP1.1



3. Helium gas management

Helium gas before start of operation:	13 600 Nm ³
Helium gas purchased during operation:	6 500 Nm ³
Helium gas available at the end of operation:	16 000 Nm ³
<hr/>	
Helium gas loss during the operation:	4 100 Nm ³
	~ 20% (of 20100 Nm ³)
	(All volums at STP)

Reasons for loss:

- Used during the initial purging of whole volume in W7-X and refrigerator
- Refrigerator trip in standard mode with W7-X connected: Safety valves opened, leakage at isolation valves
- During initial cleaning of whole system, several regeneration of Dryer and cold adsorber beds.


3. Further improvements: Helium gas tank

- Existing: 4 tanks, Carbon steel, with quench gas damper
- 1 tank as dedicated quench tank (once empty), $p < 1.5$ bara
- 10 kL LHe Dewar contains He for about 2 full tanks
- During peak power mode, Dewar could be empty in couple of hours
- No He recovery system available
- Planned to buy 1 more tank



- 4 pure Helium gas tanks
- each 250 m³
- working pressure 19 barg

3. Further improvements: Controls



3. Maintenance: preventive, regular

Preventive:

- Physical inspection by each shift: refrigerator and W7-X cryo system
- Oil leakage checks through compressor & oil pump bearings
- Operating hours (before oil drainage) for each coalescers

Regular:

- After certain operating hours or durations as prescribed by the manufacturer:
For rotating equipments i.e. compressors, motors, oil pumps, cooling water pumps/motors, vacuum pumps etc.
- Cold machine bearing check/change
- Isolation vacuum checks of transfer lines, Dewar
- Check of valves

4. Summary and future operations

Summary:

- Cryogenic system operated continuously (Feb 2015 – Apr 2016)
(except few breaks due to trips etc. 😊)
- Measured heat loads well within the design values
- Designed flow, pressure and temperatures achieved
- In house training of operation team
- Adjustment of controls: logic, parameters
- Presently in progress: Maintenance and problem sorting

Future operations:

Mid 2017: Cool-down for W7-X operation phase 1.2

