



ALFA

From LS1 to 2016


P.Fassnacht on behalf of ATLAS/ALFA

- Detector readiness
- Status of physics analyses (short)
- Plans for 2016

The ALFA detector





- 2 x 2 stations
~ 240 m from ATLAS IP
- 8 fiber detectors with
2 x 10 layers of 0.5 mm
quadratic fibers
- Movable in vertical
direction
- Resolution ~ 35 μm





Long list of LS1 upgrades ...

- All 4 station moved from tunnel to surface, complete disassembling
 - Replacement of detector ALFA2 → ALFA10
 - Alternate pre-vacuum pumping with remote controlled spare pump
 - Reduced dead time of trigger electronics to handle up to ~ 700 bunches
 - Upgrade of clock movement system: PXI, FESA etc.
 - Upgrade of DCS and TDAQ along with ATLAS stream
 - Vital: heat protection to avoid damage of detectors
 - New laser survey in tunnel
 - Special trigger board to stay within ATLAS latency budget
-
- Move both far stations to new positions to enlarge distance 4m → 8m, → improve t -resolution by factor 2
 - New code for reconstruction software



From tunnel to surface and back




15/3/2016

Forward Physics Workshop

Heating in Run1





Temperatures of ALFA detectors during a LHC fill



- Max increase ~ 20 degrees observed
- Danger: destroy structure of fiber detector


4 Measures against heating

RP Filler, ferrites, air cooling, heat distribution




Heating in Run2

Temperatures of ALFA detectors during a LHC fill 2015




➔ Small increase by ~ 3 degrees, save for Run2

Data taking in Run2: beta* 90m



Monday 8:00


15/3/2016



Sunday 12:00

Elastic scattering

- Refill LHC with 3 bunches $\sim 8E10$ plus up to 10 pilot bunches $\sim 1E10$
- Move the Roman Pots again to $5.5 \sigma_{\text{nominal}}$
- Follow data recording by farm processing for various groups of trigger items
- Now w/o IBL in readout to allow higher trigger and storage rates




- After about 4.5 hours beam was dumped by operator !!!
- Collected: 40 million physics, 11 million elastic, 450 million calibration triggers
- Data w/o crossing angle for standard elastics analysis
- Qualification by loss map tests for Roman Pots at 10σ successful, originally 12σ

K.Korcył

Diffractive scattering

- Due to ALFA dead time min bunch spacing 100 nsec, allows max 700 bunches
- Unusual filling scheme, never before tested ...
- Strategy for intensity ramp: 50 \rightarrow 250 \rightarrow 700 bunches
- Move all Roman Pots to $10 \sigma_{\text{nominal}}$ (5-7 mm)
- Example: Online plots for **single diffractive events** combining ALFA & MBTS



Integrating over all 7 fills:

- LHC delivered: 735 nb-1
- ATLAS+ALFA in position recorded: 652 nb-1
- ATLAS+ALFA optimal: ~ 600 nb-1 ($\sim 82\%$ efficiency)


K.Korcył

List of YETS 2015 upgrades ...


- Vacuum pumps & fans
- Replacement of noisy LVDT
- Modification of Radmons for higher doses
- Upgrade of movement system. Interlock validation started
- Changes in DCS and TDAQ along with ATLAS
- Measures against the UFO issue
- Long-pending installation of new magnet cables

UFO issue and measures (1)

Beam dump in an ALICE/LHCb vdM run by a BLM signal close to station A7L1





Measure#1: multiple movement repetitions in TS2



No clear effect
UFO rate scales with beam intensity
All signals below dump threshold

UFO issue and measures (2)

Measure#2: increase dump threshold from machine side, more coherent with TOTEM
Increase by factor ~ 25 should rule out UFO amplitudes above the threshold over Run2




Beta* 90m, Oct 10-19, 2015
BLM signals versus RP mvt

→ No indication
of correlation seen.

Magnet cables for Q4


Cables installed - to satisfy optics requirements very asymmetric powering of Q4 needed for the 2 beams. Not possible with the past powering schema – Like for TOTEM new cables installed during YETS



Cables: 24h Short Circuit Test

Optics:

- Starting point : 1000 m optics of 2012.
- No more Beam1 / Beam2 ratio constraint on Q4.
- Phase advances: 90deg in vertical (ok) and away 180deg in horizontal (not yet fully there...).
- Preliminary file available.



Steps to highest beta*

Powering tests of Q4.R5 on the 2015.02.14 results (TOTEM)







Figure 3 – current ratio between the 2 apertures in IR5

De-coupling of beam1 and beam2 allows to design optics with less constraints

Status of physics analyses

Elastic scattering:

- Total/elastic cross section at 7TeV (beta* 90m) published
- Analysis 8TeV / 90m in final stage. Internal reviewing started.
- Analysis 8TeV / 1km first iteration done, checking consistency with 90m results
- Data 13 TeV/ 90m first inspection done, on hold until 8 TeV results published



Diffractive processes:

- 7 + 8 TeV – exclusive pions: close to being finalized
- 13 TeV – inclusive and exclusive analysis started
- ALFA+LHCf – combined data, mostly $pp + \pi^0$

Standard elastics program

Measurement of luminosity and total cross section by elastic scattering at very low t

In dependence on t -range two options:

1. Only nuclear scattering and luminosity from ATLAS $\rightarrow \sigma_{\text{tot}}$


$$\frac{d\sigma}{dt} = \frac{1 + \rho^2}{16\pi(\hbar c)^2} \sigma_{\text{tot}}^2 \exp(-Bt)$$

2. Coulomb + nuclear scattering:
 \rightarrow Luminosity and σ_{tot}

$$\frac{dN}{dt} = L\pi |f_C + f_N|^2 \approx L\pi \left| -\frac{2\alpha}{|t|} + \frac{\sigma_{\text{tot}}}{4\pi} (i + \rho) e^{-b|t|/2} \right|^2$$


Key parameter: small t_{min} requires small emittance ϵ_N , close distance N_σ and large β^*

$$t_{\text{min}} = m_p p \frac{\epsilon_N N_\sigma^2}{\beta^*}$$



On the way to highest beta*

H.Burkhardt: first attempt for beta* 2-3 km




Problematic phase advance
in horizontal plane


$\rightarrow M12x \sim \sin \mu_x \sim 0$

B1	β_x	φ_x	M12x	β_y	φ_y	M12y
237m	357m	180.035	-0.58m	43.95m	98.53	328
245m	285m	181.52	-22.4m	45.41	109.2	318

Hit maps & resolution from fast simulation



At small t , t -resolution mainly limited by poor lever arm, in particular in x ($M12_x$)



H. Stenzel

t_min, how much into CNI?

Mechanical limitation to RP positions:

AC switch


Approx. 800-900 μm per gap.

$$t_{\min} = p^2 \cdot y_d^2 / (\beta_y \cdot \beta^*)$$

$$y_d = 800 \mu\text{m} \text{ (half gap + wall + } d_{d_w}\text{)}$$
$$\beta_y(240\text{m}) = 45\text{m}, \beta^* = 2500\text{m}$$
$$p = 6.5\text{TeV}/c$$


$$\Rightarrow t_{\min} = 2.4 \cdot 10^{-4} \text{ GeV}^2$$

“Only” freedom: maximise $\beta_y \cdot \beta^*$!



Acceptance versus detector positions

- For data in CNI region with acceptance > 10% detectors at 1mm to beam
- Taking into account $\sim 0.4\text{mm}$ dead space due to window+gap RPs at 0.6mm



Acceptance (10%) and t-resolution limits range for physics analysis to at best $t > 2.10^{-4} \text{ GeV}^2$

Schedule for 2016

- Two slots to implement and measure optics: end of May, July
- A period of 3-4 days for data taking late September , together with TOTEM.
Needs final confirmation

Apr				May				June					
Wk	14	15	16	17	18	19	20	21	22	23	24	25	26
Mo	4	11	18	25	2	9	Whit 16	23	30	6	13	20	27
Tu							VdM		beta* 2.5 km dev.				
We										TS1			
Th	Recommissioning with beam				Ascension								
Fr					May Day comp				MD 1				
Sa					Intensity ramp-up Scrubbing as required								
Su				1st May									

July				Aug				Sep					
Wk	27	28	29	30	31	32	33	34	35	36	37	38	39
Mo	4	11	18	25	1	8	15	22	29	5	12	19	26
Tu												beta* = 2.5 km data taking	
We				MD 2					TS2	MD 3			
Th							MD			Jeune G			
Fr													
Sa				beta* 2.5 km dev.									
Su													



Ready for $\beta^=2.5\text{km}$*

Thank you for your attention