

# DCS and TDAQ for AFP

Elżbieta Banaś, Krzysztof Korcyl  
on behalf of the ATLAS Forward Proton  
DCS and TDAQ Groups



The Henryk Niewodniczański  
Institute of Nuclear Physics Polish Academy of Sciences  
Cracow, Poland


**LHC Forward Physics Working Group**

CERN, 15-16 March 2016


# Outline

- DCS
  - status after installation in the tunnel
  - plans
- L1 Trigger
  - full system project
  - status after installation in the tunnel
  - plans
- DAQ
  - full system project
  - status after installation in the tunnel, status in SR1
  - plans


# DCS: overview of installed AFP Hardware Structure



USA15




330 m



# Low Voltage Supply

## 1st stage: USA 15


- Wiener PL512, Ethernet controlled , OPC DA server in VM2008 Framework software + technical panels **READY** 😊
- LVPP 4 (*IBL like*) – split each voltage line to 4 lines, with precise current measurement ELMB, OPC UA server Framework software + technical panels **READY** 😊



## 2nd stage: tunnel

Voltage Regulators Crate VREG (*IBL like*)

- 2 LV boards for supply FE-I4 chips in Near and Far Stations
- 1  $V_{VDC}$  board for optoboard
- 1 controller board
- Radiation hard voltage regulators, control – ELMB with non standard firmware, OPC UA server IBL software – technical panels **READY** 😊



# High Voltage Supply, Optoboard power supply

## ISEG HV System:

- Crate: ECH 238\_1200W-UPS
- EHS F405n 16 channels module  
CAN-controlled,  
OPC UA server (new design)

Framework software + technical panels **READY** 😊

**Iseg Module Operation**

Module Name: ATLAFLCS:Iseg/can0/crate02/ma00 Node ID: 0

Model: All (16 Channels) Device ID: 0 Device Class: 26


	ch	VMeas	IMeas	Vset	Iset	
near station	00	0.00 V	-0.000 A	1.00 V	0.0001 A	Set
	01	0.01 V	-0.000 A	1.00 V	0.0001 A	Set
	02	0.00 V	-0.000 A	1.00 V	0.0001 A	Set
	03	0.00 V	-0.000 A	5.00 V	0.0001 A	Set
far station	04	0.00 V	-0.000 A	1.00 V	0.0001 A	Set
	05	0.01 V	-0.000 A	1.00 V	0.0001 A	Set
	06	0.01 V	-0.000 A	1.00 V	0.0001 A	Set
	07	-0.00 V	-0.000 A	1.00 V	0.0001 A	Set

Commands for all channels: Switch Channels ON / OFF [On] [Off] RampSpeed: 1.00 %Vn

## SCOL – power supply for optoboard (IBL-like)

- 3 different supply voltages:
  - $V_{VDC}$  – main supply (1st stage)
  - $V_{pin}$  – depletion voltage for the PIN receiver diode
  - $V_{iset}$  – operation point of the VCSELs
- Optoboard Reset Signal

Framework software + technical panels **READY** 😊



**AFP INF SCOL MC BlockA**

Optoboard ARM\_C AFP\_Right

Low Power - VPin	High Power - Channel A	Low Power - VPin
VMeas: 4.997 V	VMeas: 6.853 V	VMeas: 6.853 V
IMeas: 1.728 mA	IMeas: 367.832 mA	IMeas: 367.832 mA
Analog Out: 2049 cnt	Analog Out: 5610 cnt	Analog Out: 5610 cnt
Power: TRUE	Power: TRUE	Power: TRUE
VSet: 5.000 V	VSet: 7.000 V	VSet: 7.000 V
VSet: 5.000 Set	Interlock: 2.608 V	VSet: 7.000 Set
[ON] [OFF]	[ON] [OFF]	[ON] [OFF]


Low Power - RST

VMeas: 0.801 V	UMSS4Rp: 2.502
IMeas: 1.351 mA	UMSS4Rm: 0.004
Analog Out: 1310 cnt	IMSRShp: 0.000
Power: TRUE	IMSRShm: 0.000
VSet: 0.800 V	IMSRSm: 0.000
VSet: 0.800 Set	IMSRSLp: 0.000
[ON] [OFF]	IMSRSLm: 0.000
Interlock: 2.608	Set Permanent: FALSE
RESET: FALSE	Set [Unset]
[Reset]	Interloc: RESE

ELMB Name: AFP\_SCOL\_ARMC ID: 1 Serial Number: J594 State: Operational 5

# Interlock Matrix Crate and temperature monitoring

*All power supplies are interlockable*



Temperature sensors - 45 for one Arm:

detector, heat exchanger, pot wall, stepper motor, Air Cooler, Local Trigger Board, optoboard, VREG -> connected to Interlock Matrix Crate

- Crucial sensors - Hardware interlock action


Defined and tested **READY**



- Monitoring

ELMB, CanOpen UA OPC server

Framework software + technical panels **READY**



# Secondary Vacuum and Cooling

Covered by Roman Pot Instrumentation and Control system - Xavier Pons (PH-DT)

Monitoring and control via PLC Siemens S7 1200, USA15, native S7 WinCCOA Driver

Vacuum Very similar to ALFA system

PLC program – operating



DCS software – technical panels **READY**



Cooling

○ PLC program – operating




○ Integration with DCS – ongoing




Connection and PLC control/monitoring scheme

From M. Trzebinski



15-16/03/2016



DCS and TDAQ for AFP

# Movement and Positioning control

- Document draft distributed (1 comment received):  
“Specification and Validation of the Motion Control System of the ATLAS Forward Proton Roman Pots”





Figure 2. The IN, OUT, and HOME switches and their ideal ranges settings. In addition the electrical STOP needle switch (and photo insert) is shown and its relation to the positions of the other switches.



Covered by Roman Pot Instrumentation and Control system - Xavier Pons (PH-DT)  
Last hardware commissioning tests done


Integration with DCS – to be started soon



# Front-end chips FE-I4 / HPTDC Health Parameters

Goal:

internal FE chips parameters (temperature, supply voltage, current, ...) are collected by DAQ and transferred to DCS



OPC UA server embedded in RCE will acquire health parameters via dedicated API's:


- OPC UA server framework installed on RCE, ready for development
- Access to test station for API development is setup
- Calibration constants will be provided by detector experts

Status - ongoing 

# DCS Status and plans

- DCS production project is setup in Point1 environment } 😊
  - Archiving
- Communication protocols, hardware access **READY** } 😊
  - OPC UA servers in SLC6: HV and CanOpen
  - OPC DA server in VM 2008: LV Wiener PL512
  - S7 Native Driver for PLC S7 1200 control
- Hardware Interlock – implemented **READY** 😊
- Technical panels for detector powering – **READY** 😊
- Technical panels for vacuum – **READY** 😊 for Cooling - ongoing ⚙️
- Integration with Movement an Positioning System – to be done 🚫
- FSM – started, ongoing ⚙️
- Automatic emergency actions- software interlock – started, ongoing ⚙️
- Notification system – started, ongoing ⚙️
- Integration with ATLAS Central DCS - to be done 🚫
- Documentation....

# AFP LVL1 trigger



Current ATLAS L1 latency: **84** BCXs

Protons from P1 to 217 m: **29** BCXs

Fast air-core cable (300m): **43** BCXs

ATLAS CTP work: **6** BCXs


Trigger logic: **6** BCXs

NIM signals with  
encoded information  
from timing detectors


AFP\_CTPIN

ATLAS  
Central Trigger Processor

# AFP2+0 LVL1 trigger






The LTB board forwards services (LV, HV) for the FE modules and houses HitBus chip



3 out of 4 FE-I4 HitOR outputs are connected to HitBus chip (DBM) to make logic function (AND/OR, single module) . The HitBus output is then converted into NIM level and sent to CTP.

**ATLAS**  
**Central Trigger Processor**



# AFP2+0 LVL1 trigger




# AFP LVL1 trigger status and development

- AFP LTB boards commissioned and installed in the tunnel
- trigger signals from the LTBs arrive at CTP in decent form (after 250 m of air-core cables)
  - NIM logic in CTP crate discriminates signals to make 23 ns pulses
  - copies for standalone runs arrive at AFP rack and can be used as triggers
    - as single stations or in coincidence
- AFP LVL1 trigger ready for commissioning

# AFP DAQ




# AFP2+0 DAQ





# Status of standalone AFP TDAQ



**@ SR1**

Controls LTP+TTC in VME crate 

Controls RCE to configure and run FE-I4 

Monitoring data quality via sampler @ DCM 

Firmware at HSIO controlled from RCE 

- interfaces with TTC

- L1A, BCR, ECR

- requests FE data, formats fragments then forwards to ROS 

- copies of events sent to RCE for monitoring 

- test data files written via ROS with full ATLAS formatting

**@ USA15**

- fast trigger cables reach CTP rack; signals discriminated, copies sent to AFP rack
- CTP signal cable between CTP and AFP racks arrived, but needed to be tested
- TTC system from SR1 moved to USA15 for commissioning detectors in the tunnel
- OKS configuration for standalone partition ready for data from detectors - waiting for ROS PC
- standalone programs calibGui and cosmicGui will be used in commissioning until partition starts controlling RCE