



## PEPI and Service Bay Cooling Requirements

Jason Andrews, Brian Hamilton, Hassan Jawahery, **Tom O'Bannon**, Will Parker, and Jack Wimberley

> University of Maryland May 17, 2016





## Near Electronics Cooling

- Baseline is chilled water-based coolant
- Two thermal load categories
  - 8 PEPI Chassis
  - 4 Service Bays
- Risk Mitigations
  - Continuous dry gas flow to prevent condensation
  - Robust pressure tests of heat exchangers and pipes to lower risk of leaks
  - Is Active Leak Detection Needed?



### **Power Rollup Summary**



SubAssy	Thermal loads (Watts)
SBC-UL	2908.6
SBC-UR	2908.6
SBC-LL	2908.6
SBC-LR	2908.6
SBC Totals	11634.3
cable SBC-UL	499.6
cable SBC-UR	499.6
cable SBC-LR	499.6
cable SBC-LL	499.6
Total Cable: SBC>PEPI	1998.2
Station 0, UL PEPI	499.3
Station 1, UL PEPI	551.0
Station 0, UR PEPI	499.3
Station 1, UR PEPI	551.0
Station 0, LR PEPI	499.3
Station 1, LR PEPI	551.0
Station 0, LL PEPI	499.3
Station 1, LL PEPI	551.0
Total x8 PEPI Chassis	4201.0
UTaX	978.2
UTaU	978.2
UTbX	1088.6
UTbV	1088.6
UT Planes	4133.5
TOTALS Input Power for all	
4 SBCs (Watts):	21967.0
MARATON Output Power	
(Watts)	26672.8

~ 2900 Watts thermal load *per* SBC essentially reduces the net PEPI Chassis thermal load

~ 500 Watts thermal load per cable tray is spread over the 10 meter runs \*

~ 500 – 550 Watts thermal load per PEPI Chassis (much easier to cool compared to ~ 2000 Watt PEPI if linear regulators were on-board)

\* This is an estimated upper bound

- Longest cable now estimated at 7 meters maximum
- Selected copper wire sizes tending to be larger than identified minimums
- However, worse case currents for SALT ASICs not yet finalized

# System Control and Interlocks



- System power and cooling controls must obviously be coordinated
- Two tiers of interlocks planned
  - CERN detector safety system
    - Harsh, uncontrolled pull-the-plug approach
  - SMCU
    - Power sequence controls
    - Checks key temperatures and coolant flows to implement a very *basic* local interlock
    - Controlled shutdown, when possible
- Items not yet defined
  - Key sensors
    - CO2 flow sensors
    - Coolant flow sensors
    - Humidity sensors
    - Leak sensors?
  - Operating conop for standard On/Off sequences
    - Turn on the PEPI chassis first?
      - After dry gas flows for tbd duration
      - Then water cooling started
      - Then PEPI boards powered
    - How is CO2 system started and stopped?
      - Are any special power sequences required to minimize thermal transients and ramp rates?
    - Power detector planes on/off by horizontal power groups or single full vertical staves?






### Summary

- Predicted thermal loads for PEPI and service bays have been tabulated
- SALT ASIC maximum current requirements not yet finalized
- Several open items exist
  - Identify some of the specific sensors
  - Coordinated cooling and power system requirements





#### BACKUP







### **UT Electronics Block Diagram**

