


Discussion on UT assembling, testing and installation

May 17, 2016

Burkhard Schmidt

UT installation, based on TT layout

- The yellow parts will be re-used for UT (other items only as they seem useful)
- The sequence would be as follows:
 1. Put the infrastructure on the C-side (racks, chain, services etc.) in place
 2. Install the C-side detector box
 3. Install the A-side detector box
 4. Install/connect the infrastructure on the A-side
 5. The beam-pipe and the interface to the UT-box should be mounted only at the end
- A small crane is available in this detector area



New assembly hall at Point 8



C

- New LHCb Assembly Hall & Storage - roughly 485 m² – crane 30 t
 - The UT group we request about 80m² of assembly space in this hall.
 - About half of it should be equipped with a clean room.
 - In addition, space of about 20m² needs to be foreseen for a cooling plant, needed to carry out the required detector tests at room temperature (<20°C)

UT Maintenance

- Some considerations:
 - Maintenance will be done in the cavern; it is NOT foreseen to bring the detector halves to the surface.
 - The detector will be carefully moved to the ‘maintenance position’.
 - All interventions, be it on the staves, the flex cables and other connections, or the PEPI electronics, will be carried out in this location.
 - The appropriate measure will have to be agreed upon.
 - This might include a sort of tent for work on staves with ‘semi-clean room’ conditions etc.



UT Assembly & Testing Plan

- Tentative stave assembly procedure:
 - Fully-populated staves shipped to CERN
 - Box half with frame and cooling manifold assembled and ready, has removable cover panels on open sides and dry air flush
 - Add single stave at a time, connect pigtail, connect cooling, mount to frame, power up, cool down, and read out in order to qualify stave for operation
 - Test stave (see below)
 - Add second stave, using same procedure, test
 - Repeat for all staves in four half-planes, working from beampipe region outward, populating planes U,V,X,X in order
 - **Ideally, test everything possible before lowering half-UT into pit**
- Proposed DAQ assembly:
 - DCBs will be housed in crates above the detector box.
 - They should be considered as part of the detector halves assembled on the surface
- Installation of LV and HV distribution:
 - LV and HV modules will be in the racks on the side of the detector or further away on the 'balcony' and installed independent on the detector halves
 - Some LV and HV will be needed on the surface for testing
 - Use some modules first there before installation in the cavern

Backup

UT cooling needs during assembly & testing

- The staves will be installed 1 by 1
 - About 53-75 W per stave, depending on position in the detector
 - after each stave assembly, a cooling cycle will be performed for tests
 - 16+16 staves in 'a' layers and 18+18 staves in 'b' layers;
 - 68 staves in total; 34 staves per detector box
- Each box has 4 manifolds (for the inlet)
 - 2 manifolds per LUCASZ loop; about 850 W per manifold
 - The whole detector half/box need to be tested at the end



Performance parameters for a CO₂ plant on the surface for assembling and commissioning

Parameters	unit	CMS	LHCb
Cooling loop max flow	g/s	14	10
Total plant flow	g/s	max. 20	20
Min evaporating T	°C	-25	-25
Max evaporating T	°C	+15	+15
Number of cooling loops	#	2	2
Max Δp across cooling loop	bar	<20	<20
Cooling loop max power	W	810	850
Plant max power	W	1500	1500
Transfer line length	m	18	15

- Joint development with CMS