



Man/Women-Power Considerations for Construction

Sheldon Stone, Syracuse University



RISKS

Schedule Risk

- ❑ Critical situation is already upon us due to delays
 - ❑ Data flex - >~6 months behind schedule
 - ❑ Hybrid - Need a preliminary design drawing immediately, especially giving Salt position to start Stave construction
 - ❑ Salt - hopefully on track now, can expect working chip by end of July, but needs to be tested & refined

Materials risk

- ❑ Silicon sensors
 - ❑ Design prototype was done using a sole source, Hamamatsu. (Could not be avoided as Micron did not give a realistic price for prototypes)
- ❑ Other parts
 - ❑ Procurement of cables also a potential problem even if prototypes work
 - ❑ Other parts need to be ordered expeditiously (Ti tubes, CBF...)
 - ❑ Electronic components

Electronic risk

- ❑ Salt takes more than estimated power (6mW/channel)- Pepi cannot supply enough power
- ❑ Noise level is too high as determined in slice test
- ❑ Mitigation strategy causes time delay & more cost, needs redesign of either Pepi, Salt, or both

Electronics box risk

- Can box be assembled and fit all the components?
- Will grounding scheme work, or will noise be too much? Should be able to test this as we install staves.

Testing risks

- ❑ Incur more schedule delays because testing systems are not yet ready
- ❑ Is the Salt testing system ready? If not when will it be ready? (**this is on the critical path**). I am talking here not only of tests on the next chip version, but also the production version
- ❑ This is still under our control, lets not let the testing systems setups slip (cables, hybrids, electronics, fully populated staves).

Shipping risk

- ❑ Obvious hazards in trans-Atlantic transport
 - ❑ Mitigation: early construction and testing of transport device. (Design is already done)

Financial risk

- ❑ Running over budget on any component is a problem here
- ❑ As there is no contingency any item over run needs to be replaced by cost saving elsewhere
- ❑ This problem is made worse by the accumulated project delays

Manpower risks

- ❑ Is there adequate manpower to get everything done in the remaining time? This is for each group to answer.
- ❑ Mitigate by starting stave construction now

Construction tasks

- ❑ Work at all institutions: Chip testing, electronics testing, at CERN: detector box, testing finished modules after shipment, mounting in box....
- ❑ Electronics production (Maryland)
- ❑ Machining (Cincinnati)
- ❑ Data flex & hybrid production (Milano)

Available person power

WBS#	Subsystem	Contact Person	Physicists	Software pros	CERN	AGH	Cinn	Maryland	Milan	Syr	Zurich	Sum
	Upstream Tracker	Marina Artuso										
1	Sensor and hybrids	M. Rudoff, M. Citterio	7									
1.01	Sensor		4							4		4
1.02	Front-end hybrid		3						3			3
2	SALT ASIC	M. Idzik, K.Swientek	6									
2.01	Asic production	M.Idzik	6			4						4
2.02	Testing	O. Steinkamp									2	
3	Electronics	T. O'Bannon J. Wang	7									
3.01	Flex cables		3				1		1	1		3
3.02	PEPI electronics		4					4				4
4	DAQ/Electronics infrastructure	C. Beteta	6	2								
4.01	Tell40/sol40 boards/crates	C. Beteta, J. Wang	4	2						1	1	2
4.02	HV/LV/cabling	C. Beteta	2								2	2
5	Mechanics and Cooling	R. Mountain, S. Coelli	11									
5.01	Cooling plants	S. Coelli	2		1				1			2
5.02	Staves and hybridization	R. Mountain	9							9		9
6	Integration with LHCb	B.Schmidt, N. Neri	1									
6.01	Frame and detector box		1		3							3
7	Integration and testing	S. Blusk, T. Skwarnicki	4									
7.01	Module and stave wirebonding		2							2		2
7.02	Test infrastructure		2							2		2
8	Project management	M. Artuso										
8.1	sensor and hybrids	M. Artuso, M. Citterio										
8.2	salt asic	M. Idzik										
8.3	Electronics	T.O'Bannon, J. Wang										
8.4	Mechanics and cooling	R. Mountain, N. Neri										
8.5	Electronics Infrastructure	C. Beteta										
8.6	Integration in LHCb	B.Schmidt, O. Steinkamp										
8.7	Integration and testing	S. Blusk and T. Skwarnicki										
	TOTAL		42	2	3	4	1	4	5	19	5	

STAVE CONSTRUCTION

Syracuse tasks

- ❑ Construct bare staves (metrology)
- ❑ Test & glue on dataflex cables (metrology)
- ❑ Test hybrids
- ❑ Construct modules & test them (metrology)

Syracuse tasks II

- ❑ Glue modules to staves
(metrology)
- ❑ Wire bond modules
- ❑ Test modules & full staves
electrically
- ❑ Package and ship to CERN

Manpower situation

- ❑ Generally we need to use the people we have
- ❑ Syracuse
 - ❑ 5 faculty @ ½: 2.5 fte contingency only
 - ❑ 5 grad students: 2.5 fte
 - ❑ 2 Res. Prof. & 2 postdocs: 2 fte (other UT tasks, procurements, oversight....)
 - ❑ 10 undergraduates @ 20%: 2 fte,
 - ❑ 1/2 tech: 1/2 fte
 - ❑ Total time: $7 * 40 = 280$ hr/week, yearly total 13,000 hours (46 weeks)
 - ❑ Contingency = 100 hr/week, 4,600 hours

Construction Time Estimates

Item	Manpower time
bare staves	1360 hours
Test and glue data flex (320) (metrology)	960hours
Test hybrids (use test bonds)	1000 hours
Unpack Si inspect and test	2000 hours
Construct modules & Test	1400 hours
Glue modules to staves	600 hours

Construction Time Estimates II

Item	Manpower time
Wire bond modules to flex	2300 hours
Measure Si positions	320 hours
Cool down stave and test	320 hours
Test full stave electrically	160 hours
Vibration free stave transport system	1000 hours
Package for shipment to CERN	200 hours
TOTAL	11600 hours

Bare stave tasks

- Bend tubes – 2 hr
- Braise tubes & test – 1 hr (testing)
- Cut Carbon fiber faces – 30 min
- Mount 1st side facings to vacuum jig & mount on granite table – 20 min
- Glue end blocks to facing – 1 hr
- Glue on foams – 4.5 hr
- Cut trough for cooling tube (shop)

Bare stave tasks II

- Epoxy in tube - 1 hr
- Glue carbon foam over tube and opposite side facing - 1 hr
- Trim facings - 30 min
- Glue in ultem inserts -1 hr
- Metrology & other tests including cool down -2 hr
- Move to storage - 10 min
- Ancillary (little things) – 1 hr
- Total: 14 hours
- Times 80 staves= 10 hr

Summary

- ❑ Sufficient manpower to do the project at Syracuse
- ❑ Spatial needs within the clean room are an issue
- ❑ Propose starting bare stave construction **now** in order to use available manpower and finishing this task before others. Otherwise we have unused manpower