

# WP4 Activities

J. Nash – SLHC-PP SG

# Task 4.1

---

## Description of work

### Task 4.1 Coordination and organisation of CMS2

Overall coordination task for managing the upgrade of the experiment for SLHC; identification of participating institutes and their contribution, including activities related to seeking and integrating new partners; definition of the organisational project structure needed to manage the consortium of institutes participating in the construction and modification work; negotiation with institutes and funding agencies to establish collaboration agreements, cost books and reporting methods; exchange and dissemination of scientific and technical information (CERN, Imperial)

<b>Deliverables task 4.1</b>	<b>Description</b>	<b>Nature</b>	<b>Delivery date</b>
4.1.1	Project Structures for construction of systems and sub-systems	O, R	M12
4.1.2	Cost book and MoU for the upgrade and installation phase	R	M36

<b>Milestone</b>	<b>Description</b>	<b>Nature</b>	<b>Expected date</b>
4.1	Upgrade Project Scope defined	R	M18




# Task 4.1.1 – Management Structure

---

- ▶ Project management structure defined
- ▶ Management team put in place
- ▶ Team and mandate approved by CMS
  - ▶ Now a “project” (ala Tracker/ECAL...)
- ▶ Regular meetings of management team
- ▶ Monthly meetings of overall upgrade team
  - ▶ Regular meetings of many subgroups within sub-detector upgrade projects
- ▶ Two Workshops held, more planned

# Upgrade project organization

## CMS Upgrade Project




15 May 2008

# Milestone 4.1 – Upgrade Scope

---

- ▶ Workshop in May 2008 at CERN to define the scope of upgrades
  - ▶ What needs to be done in Phase I, Phase 2
- ▶ Follow up workshop held November 2008 in FNAL (150 participants) to track progress, and prepare work plan for the following six months
  - ▶ Goal prepare TP for phase I upgrades
- ▶ Workshop to be held in May 2009 to present, approve plans for phase I upgrades, and also progress towards a “Strawman” for phase 2 upgrades.

# Agreed Scenario for Peak luminosity (CMS/ATLAS/Machine/LHCC)



**New injectors + IR upgrade phase 2**

To be revised  
First phase imminently  
Second phase more known after start of LHC data taking

Early operation

**Linac4 + IR upgrade phase I**


Upgrades required to keep CMS operating at maximum potential throughout

**Collimation phase 2**




Agreed at the May 2008 Upgrades Workshop  
<http://indico.cern.ch/conferenceDisplay.py?confId=28746>

# Upgrade Scope



# Documents

Work Plan agreed at the May Workshop





# November Workshop at FNAL

---

- ▶ Meeting held 19-21 November 2008 at FNAL
  - ▶ <http://indico.cern.ch/conferenceDisplay.py?confId=41832>
  - ▶ Checkpoint to assess progress towards 2009 milestones
  - ▶ Goals for the meeting
    - ▶ follow progress, concentrate on phase I, some look at critical Phase 2 areas
    - ▶ establish the workplan for the coming 6 months
      - Key output for this workshop: a program of work which helps us arrive at a planning for the Phase I upgrades.
- ▶ Excellent levels of attendance and quality of discussion indicate what a success this meeting was
  - ▶ Around 150 participants many from outside the US
  - ▶ Workshop atmosphere
    - ▶ Good to think outside of the box – CMS has been successful by being ambitious
- ▶ Real progress has been made in identifying key areas to focus effort on in the coming months
  - ▶ Also a chance to look at “cross-disciplinary” areas

# BPIX Options

for 2013 replacement/upgrade

Slide from  
21. May 2008

as 2008


<u>Option</u>	<u>Layer/Radii</u>	<u>Modules</u>	<u>Cooling</u>	<u>Pixel ROC</u>	<u>Readout</u>	<u>Power</u>
0	4, 7, 11cm	768	C <sub>6</sub> F <sub>14</sub>	PS46 as now	analog 40MHz	as now
1	4, 7, 11cm	768	C <sub>6</sub> F <sub>14</sub>	2x buffers	analog 40MHz	as now
2	4, 7, 11cm	768	CO <sub>2</sub>	2x buffers	analog 40MHz	as now
3	4, 7, 11cm	768	CO <sub>2</sub>	2x buffers	analog 40MHz μ-tw-pairs	as now
4	4, 7, 11cm	768	CO <sub>2</sub>	2xbuffer, ADC 160MHz serial	digital 320MHz μ-tw-pairs	as now
5	4, 7, 11, 16cm	1428	CO <sub>2</sub>	2xbuffer, ADC 160MHz serial	digital 640 MHz μ-tw-pairs	DC-DC new PS




## After many discussions, considerations & iterations

- **4 layer pixel system 4, 7, 11, 16 cm** → 1216 full modules
- **CO2 cooling based**
- **Ultra Light Mechanics**
- **BPIX modules with long 1.2m long microtwisted pair cables**
- **Shift material budget from PCB & plugs out of tracking eta - region**
- **ROC buffers for  $1.5 \times 10^{34}$  and serial binary readout @160 MHz**
- **Serialized binary optical readout at 320 MHz to old, modified px-FED**
- **Recycle & use current AOH lasers → 320MHz binary transmission**
- **Same FEC's , identical TTC & ROC programming**
- **Keep LV-power supply & push more current through cables**

# BPIX Upgrade Phase 1 (2013), 4 Modules long




- Two identical half shells
- 1 type of fullmodule only
- Layer 1: R 39mm; 16 faces
- Layer 2: R 68mm; 28 faces
- Layer 3: R 109mm; 44 faces
- Layer 4: R 160mm; 64 faces
- Clearance to beampipe 4mm



# BPIX/FPIX Envelope Definition for 4 Layer Pixel System


All barrel layers 4 module long → small eta hole of  $\Delta\eta \sim 0.08$  at  $\eta=1.288$



Various iterations forth and back by R.H. / Silvan Steuli / Kirk Arndt

→ no further changes since 2.12.2008 !

# Current Pixel System with Supply Tubes / Cylinders




## BPIX Cabling & flexible cooling pipes



# Shift PCB/Plug Material out of tracking Volume

- Modules with long pigtailed (1.2m) CCA wires 16x(2x125μ)






## New weight of replacement/upgrade BPIX detector (2013)

	<u>Present BPIX</u>	<u>New 2013 BPIX</u>	<u>Comments</u>
Empty mechanics	1103 g	550 g 1.5mm/1.4mm pipes	possible, with ~ 94g for
384 Module	872 g	522 g 75 $\mu$ ROC no HV-cap	1.36g/mod no SiN strips
384 Signal cable	167g	7 g	2 x ( 2x125 $\mu$ CCA)
384 Power (6x250 $\mu$ CCA)	82g	68 g	5x250 $\mu$ CCA
384 Power plug	16g	0 g	none
32 Print	499 g	32 g	radial power cable to ST
Cooling (C <sub>6</sub> F <sub>14</sub> )	810 g	83 g	CO <sub>2</sub> in 1.45mm diam. pipe
Silicon tube incl. fluid	372g	5 g	CO <sub>2</sub> pipes to supply tube

----- Total ----- ~~3921g~~ **1267 g** **factor 3.1 down** -----

# Moving to Phase II

## Tracker - Draft Upgrade Structure





Material Budget, Power Consumption, cooling key issues for a new tracker  
Tracker upgrade team has been actively studying these areas

# System Test with DC-DC Converters



- Results summarized by Lutz in October meeting

<http://indico.cern.ch/getFile.py/access?contribId=0&resId=0&materialId=slides&confId=41790>



⇒ Noise of Enpirion converters can be controlled by combination of shielding and filtering (LDO).

- Studies with commercial buck converters documented in Jans thesis CMS TS-2009/003 "System Test Measurements with a DC-DC Conversion Powering Scheme for the CMS Tracker at SLHC"

# C02 Cooling for phase II

---




## Summary

- Almost essential to re-use the current cooling pipes on YB0, can this be done?
- Met with CERN safety commission to discuss issues
- Looks possible, agreed plan of validation with CERN safety

- With this system design, max coolant temp at 15 degrees C and safety valve at 57 bar, the currently installed copper tubes can be approved by CERN safety
- We will build one equivalent circuit for destructive testing by CERN safety
- We will pressure test the installed copper tubes with gas at  $1.25 \times 57 = 71$  bar





# Example: Layout for the Tracking Trigger Project



- A conceptual layout for a tracking detector was proposed
  - Trigger groups to understand what could be achieved with stubs
  - Tracker produces stubs to feed the Trigger
- Layout concept for stacked rods proposed
  - study groups to look at the practical aspects – What questions do we need to answer to understand if this can be built?


# Examples with two "Pt" layers at lower radii

Layout Task Force  
D. Abaneo



Number of hit modules


etaProfileTotal	
Entries	2000
Mean	1.387
Mean y	5.391
RMS	0.8098
RMS y	2.099



2. Naz - CMS Upgrades

Number of hit modules

etaProfileTotal	
Entries	2000
Mean	1.388
Mean y	5.19
RMS	0.8095
RMS y	2.006



SLHC-PP WP4 Feb 2006

# Trigger

- ▶ Technologies for Phase I upgrades
  - ▶ Micro TCA implementations
  - ▶ The hope is to develop a common infrastructure for use in trigger upgrades
    - ▶ Reduce the large number of standards currently in use in the trigger system
    - ▶ Increase reliability/flexibility
- ▶ Tracking Trigger discussions
  - ▶ Possible candidate architectures
  - ▶ Simulations
  - ▶ Key R/D for phase II
    - ▶ Need to establish which ideas most likely to be successful and dedicate sufficient resources to determine viability
      - Can it be implemented
      - How well does it work
      - Power/Material implications



Figure 1: micro TCA crate with single high backplane

# Calorimeters

## ▶ HCAL

- ▶ Progress on using Silicon PMs as a new Photo Detector
- ▶ New off detector electronics
- ▶ Upgrade strategies

## ▶ ECAL



- ▶ Data on radiation damage to crystals and VPTs in the EE
  - ▶ Establish what will be the performance at SLHC
- ▶ Simulations of SLHC and EE
  - ▶ How well will the EE perform given any performance degradation
- ▶ ECAL/HCAL joint electronics issues

▶ e.g. Trigger electronics

2  
4

J. Nash - CMS Upgrades

SLHC-PP V





# WP 4.2 Deliverables

---

<b>Deliverables task 4.2</b>	<b>Description</b>	<b>Nature</b>	<b>Delivery date</b>
4.2.1	Personnel and working practices of the Technical Coordination unit in place	O, R	M12
4.2.2	Key structural requirements (information repository, tools, coordination framework, safety and quality systems, integration office) and scheduling and reporting mechanisms in place	O, R	M18
4.2.3	Pilot design and schedule for the upgrade project published.	R	M36


## Task 4.2.1 – Upgrade TC Unit established

---

- ▶ Upgrade TC named (W. Zeuner)
- ▶ Working within the current technical coordination unit.
- ▶ Have started work on defining the working methodology
- ▶ Planning for Muon system phase I upgrade (ME 4/2 Construction and installation) progressed well at the FNAL workshop
- ▶ Meetings between Executive Board, and Project Managers to discuss procedures for reviews, TC needs for upgrades, engineering support issues

# Muons

- ▶ Planning for Phase I upgrades
  - ▶ CSC production
  - ▶ RPC production
- ▶ Planning for installation
- ▶ Concepts for using the Muon system in a tracking trigger



# ME4/2 Upgrade Schedule

- ▶  $t_0$  -- CD2 approval, money flows, begin work on Bldg 904
- ▶  $t_0+3$  months -- orders sent out for all parts
- ▶  $t_0+6$  months -- production tooling shipped to CERN and assembled in Bldg 904
- ▶  $t_0+9$  months -- chamber parts delivered, shipped to CERN
- ▶  $t_0+12$  months -- production begins at Bldg 904 at 2 CSCs/month
- ▶  $t_0+15$  months -- production ramps to 4 CSCs/month
- ▶  $t_0+18$  months -- FAST site begins assembly & testing at CERN (Bldg 904?), spare CFEB boards installed on ME4/2s
- ▶  $t_0+24$  months -- 42 CSCs finished and tested -- ready for installation of 1st endcap, recover 200 CFEB boards from ME1/1s
- ▶  $t_0+33$  months -- all 76 CSCs finished
- ▶  $t_0+36$  months -- final 36 chambers ready for installation on 2nd endcap

# Future meetings

---

- ▶ **Upgrade Days**
  - ▶ Meetings scheduled once per month
    - ▶ Keep momentum
    - ▶ Track progress
  - ▶ Topics which cross detector groups, or go into depth on a particular topic
    - ▶ Examples : Sensor R/D, HCAL/ECAL common readout electronics, tracking trigger issues
- ▶ **Upgrade Workshop 13-15 May 2009 CERN**



# Spend Profile

	<b>CERN</b>	<b>DESY</b>	<b>ETHZ</b>	<b>Imperial</b>
Total Project	48	18	15	9
Spend to date	12.2	1.9	2.8	2.8

# Reports

---

- ▶ We have to produce reports this month for the two deliverables we have achieved.
- ▶ Fairly lightweight
  - ▶ See <http://info-slhc-pp.web.cern.ch/info-SLHC-PP/MILESTONES.htm#Milestones>
  - ▶ J. Nash for 4.1.1
  - ▶ W. Zeuner for 4.2.1
- ▶ In 6 Months time we have a milestone to report on
  - ▶ Project scope defined
  - ▶ should be a direct outcome of our May workshop.

# Conclusions

---

- ▶ **Good progress on tasks/Milestones**
  - ▶ Upgrades teams established
  - ▶ Upgrade Scope understood
    - ▶ Details being studied/prepared
- ▶ **Phase I/Phase 2 split actually allows us to deliver a fairly complete upgrade plan during the course of this FP7 project**