



[www.cern.ch](http://www.cern.ch)

# LHC accelerator status and prospects

Frédéric Bordry

## LHC Days in Split

19 - 24 September 2016

Diocletian's Palace / Palazzo Milesi

Split, Croatia




# LHC (Large Hadron Collider)

## 14 TeV proton-proton accelerator-collider built in the LEP tunnel

Lead-Lead (Lead-proton) collisions


- 1983 : First studies for the LHC project
- 1988 : First magnet model (feasibility)
- 1994 : Approval of the LHC by the CERN Council
- 1996-1999: Series production industrialisation
- 1998 : Declaration of Public Utility & Start of civil engineering
- 1998-2000: Placement of the main production contracts
- 2004 : Start of the LHC installation
- 2005-2007: Magnets Installation in the tunnel
- 2006-2008: Hardware commissioning
- 2008-2009: Beam commissioning and repair
- 2010-2035: Physics exploitation



# LHC 2010-2012: a rich harvest of collisions

## CMS Integrated Luminosity, pp

Data included from 2010-03-30 11:21 to 2012-12-16 20:49 UTC



$\Sigma \sim 30 \text{ fb}^{-1}$



- 2010: **0.04 fb<sup>-1</sup>**  
7 TeV CoM  
Commissioning
- 2011: **6.1 fb<sup>-1</sup>**  
7 TeV CoM  
... exploring limits
- 2012: **23.3 fb<sup>-1</sup>**  
8 TeV CoM  
... production

7 TeV and 8 TeV in 2012  
Up to 1380 bunches  
With  $1.5 \cdot 10^{11}$  protons

# Run 1 (2010 – 2012)

- Foundations well proven at 8 TeV
  - Magnets, vacuum, cryogenics, RF, powering, instrumentation, collimation, beam dumps etc.
- Huge amount of experience gained
  - Operations, optics, collimation...
- Healthy respect for machine protection

Technology: beautiful,  
when well done!



# 2013 - 2015

April '13 to Sep. '14



3<sup>rd</sup> June  
First Stable Beams




Number of Bunches per Train  
**2244**

Number of Bunches per Train  
**2244**

13-14

Aug 14-Apr

2015




Dipole training campaign




10<sup>th</sup> April  
Beam at 6.5 TeV

Struggle



IONS



Pb-Pb at  $v_{sNN} = 5.02$  TeV





# 2015 LHC Luminosity at 13 TeV

## ATLAS

## CMS

Peak



$5 \times 10^{33} \text{ cm}^{-1} \text{ s}^{-1}$   
 Design  $10^{34} \text{ cm}^{-1} \text{ s}^{-1}$



Integrated

**Achieved  $\sim 4.3 \text{ fb}^{-1}$**




**Last week of  
 operation  $> 1 \text{ fb}^{-1}$**



# LHC schedule 2016

2016:  
a production  
year

Integrated luminosity goal:  
2016 :  $\sim 25 \text{ fb}^{-1}$  at 13 TeV c.m




# First circulating beams in LHC in 2016 on Easter Friday 25<sup>th</sup> March 2016





# LHC Start-up 2016



Friday 25 <sup>th</sup> March	First circulating beam
Saturday 26 <sup>th</sup> March	First ramp to 6.5 TeV
Sunday 27 <sup>th</sup> March	Squeeze to 0.4 m and optics measurements
Thursday 31 <sup>st</sup> March	Optics correction at 6.5 TeV (flat-top+squeeze)
Wednesday 6 <sup>th</sup> April	Nominal bunch to flat-top
Friday 8 <sup>th</sup> April	Nominal bunches into collisions
Tuesday 12 <sup>th</sup> April	Quiet beams
Sunday 17 <sup>th</sup> April	Aperture measurement (collision)
Thursday 21 <sup>st</sup> April	72 bunch injection to 444 bunches/beam
Friday 22 <sup>nd</sup> April	First Stable Beams – 3 bunches/beam



# LHC April – May 2016

Mon 25 <sup>th</sup> April	Start scrubbing
Tues 26 <sup>th</sup> April	1668+1884 bunches
Weds 27 <sup>th</sup> April	Stable Beams 12 bunches.
Thu 28 <sup>th</sup> April	Beam back (PS on rotating machine)
Fri 29 <sup>th</sup> April	Stable Beams 49 bunches
Thu 5 <sup>th</sup> May	Beam back
Fri 20 <sup>th</sup> May	Stable Beams 1177 bunches
Sat 21 <sup>st</sup> May	Fill 4947 lost after 35.5 hours
Thu 26 <sup>th</sup> May	POPS back in action



**Vacuum leak on SPS dump**




**POPS – capacitor bank**



**Weasel Transformer Pt8**


**Rotating machine down**



- **Lost around 2 weeks to technical faults**
- **Limitation number of injected bunches to avoid stressing SPS beam dump**



# P8 Transformer 66 kV/18 kV






Tests divers

## Eviter les dégâts de fouines

Contre les fouines avides de ronger, toute une panoplie de méthodes, plus ou moins efficaces, sont mises en oeuvre. Aucun moyen ne garantit une protection totale. Néanmoins, diverses recommandations vous montrent comment éloigner les fouines par des procédés simples.

**Les assurances sont mises à contribution**  
Certes, le nombre de cas annoncés diminue, mais pour les assurances, les frais demeurent, c'est-à-dire que le coût moyen par cas est toujours plus élevé. Chaque année, les compagnies d'assurances suisses doivent déboursier des dizaines de millions de francs à cause de dégâts



# LHC : new schedule

Scrubbing



	Apr			May					June				
Wk	14	15	16	17	18	19	20	21	22	23	24	25	26
Mo	4	11	18	25	2	9	Whit 16	23	30	6	13	20	27
Tu							VdM			TS1			
We		Injector TS (8 hours)											
Th					Ascension						beta* 2.5 km dev.		
Fr	Recommissioning with beam				May Day comp			VdM					
Sa													
Su				1st May									

- MD1 period postponed (5 days)
- TS1 shortened to 2.5 days – considerable amount done during extended stops for technical issues


	July			Aug				Sep					
Wk	27	28	29	30	31	32	33	34	35	36	37	38	39
Mo	4	11	18	25	1	8	15	22	29	5	12	19	26
Tu								MD 2				beta* = 2.5 km data taking	
We											TS2		
Th				MD 1						Jeune G			
Fr								beta* 2.5 km dev.					
Sa													
Su				beta* 2.5 km dev.						MD 3			



# 2016 Overall machine efficiency





## 2015 efficiency



**Performance of data production**  
(no commissioning, MD, ...)

# Peak and Integrated luminosity overview



( 2016-09-11 11:06 including fill 5288; scripts by C. Barschel )

Design luminosity  
 $> 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$



# LHC Limitations

## SPS beam-dump

Nb of bunches per injection limited to 96

Total number of bunches: 2200

## LHC Injection kickers

Outgassing from ceramic

Bunch population limited to around  $1.1 \times 10^{11}$




## Electron cloud

Still significant heat-load within cryogenic limits

Dynamics – well handled by cryogenics feed-forward – no impact on operations in the present conditions


## UFOs

Frequency has happily conditioned down







# UFOs – 2015 and beginning 2016




Arc UFOs : rates similar to end of 2015  
- did not lose conditioning over the YETS stop




# UFOs - 2016



## Longitudinal locations (whole 2016)



# Recall: Dipole Training Campaign after LS1 (2015)



**Each Sector Trained to 6.55 TeV (11080 A) (100 A above the operational field)**

**172 training quenches  
~600 secondary quenches  
Only 1 quadrupole quench**

**Cryogenics recovery time: 8 – 10 hours**

Sector	# Training quench	Flattop quenches
S12	7	0
S23	17	0
S34	15	1
S45	51	0
S56	18	3
S67	22	1
S78	19	3
S81	29	0
Total	171	8


**Large variation in number of training quenches per sector**

Circuit	Status	#M Firm 1	#M Firm 2	#M Firm 3	#MQ Firm 1	#MQ Firm 2	#MQ Firm 3	#MQ total	#CQ total
RB.A12	11080 A reached	50	95	9	2	1	4	7	7
RB.A23	11080 A reached	56	58	40	0	2	15	17	17
RB.A34	11080 A reached	44	81	29	1	7	8	16	16
RB.A45	11080 A reached	48	44	62	-	3	48	51	49
RB.A56	11080 A reached	28	42	84	0	0	18	18	17
RB.A67	11080 A reached	57	36	61	0	1	21	22	21
RB.A78	11080 A reached	53	40	61	2	10	7	19	19
RB.A81	11080 A reached	64	24	66	0	3	26	29	26



# LHC: new schedule approved on 31<sup>st</sup> August

Initial LHC SCHEDULE



New Schedule



**LHC Proton Run 2016 is reduced by one week: one week investment for energy increase**


**The restart date in 2017 is unchanged**

- Technical Stop
- Machine development
- Recommissioning with beam
- Special physics runs
- Scrubbing



Training of 2 sectors towards 7 TeV (max 2 weeks)

# LHC EYETS approved on 31<sup>st</sup> August 2016



# LHC: Incoming 2016



	July				Aug				Sep				
Wk	27	28	29	30	31	32	33	34	35	36	37	38	39
Mo	4	11	18	25	1	8	15	22	29	5	12	19	26
Tu								MD 2				beta* = 2.5 km data taking	
We											TS2		
Th				MD 1						Jeune G			
Fr								beta* 2.5 km dev.					
Sa										MD 3			
Su				beta* 2.5 km dev.									

	Oct			Nov				Dec		End of LHC run [06:00]			
Wk	40	41	42	43	44	45	46	47	48	49	50	51	52
Mo	3	10	17	24	31	7	14	21	28	5	12	19	26
Tu	MD 4					Ions setup				Extended year end technical stop			
We					TS3								
Th							Ion run (p-Pb)					Lab closed	
Fr				MD 5									
Sa													
Su									Pb MD			Xmas	New Year

- **Beta\* 2.5 km physics (4 days and long preparation)**
- **29 days of proton physics left**
- **Proton-lead run at  $\sqrt{s_{NN}}$  of 5 and 8 TeV**
- **2 weeks dipole training before Christmas**

# Run 2

Ion runs in 2016 (p-Pb) and 2018 (Pb-Pb)



Shutdown/Technical stop  
 Protons physics  
 Commissioning  
 Ions



↑  
 Push 2 sectors towards 7 TeV  
 Extended Year End Technical Stop – 20 weeks  
 General maintenance: LHC and injectors  
 and CMS pixel upgrade;

- **Peak luminosity to  $\sim 1.7 \cdot 10^{34}$  (limited by inner triplets)**
- **$\sim 40\text{-}45 \text{ fb}^{-1}/\text{year}$  in 2017 and 2018 (goals will be fixed at Chamonix 2017)**
- **Prepare for HL-LHC and post-LS2 LIU era**
- **Prepare for 7 TeV operation**

# Conclusion: 2016 goals

Peak luminosity >  $1.2 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$

Over 25 fb<sup>-1</sup> in both ATLAS and CMS 😊



Progress represents a phenomenal ongoing effort by all the teams involved



# SATISFACTION

**Peak luminosity  $> 1.2 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$**

**Integrated luminosity  $\sim 30 \text{ fb}^{-1}$**

# SATISFACTION

Peak luminosity  $> 1.2 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$

Integrated luminosity  $\sim 30 \text{ fb}^{-1}$

# I CAN'T GET NO SATISFACTION

KEEP  
CALM  
AND  
KEEP  
GOING

To reduce the crossing angle (test after TS2)

To keep the emittance growth through the cycle

To increase the number of bunches (2748, 288 per train) and bunch intensity

Reduction of  $\beta^*$  (ATS optics could be an option)

Optimisation of the integrated luminosity (availability)

Prepare towards 14 TeV operation

...

*Europe's top priority should be the **exploitation of the full potential of the LHC**, including the high-luminosity upgrade of the machine and detectors with a view to collecting **ten times more data than in the initial design, by around 2030**. This upgrade programme will also provide further exciting opportunities for the study of flavour physics and the quark-gluon plasma.*

## HL-LHC from a study to a PROJECT

**$300 \text{ fb}^{-1} \rightarrow 3000 \text{ fb}^{-1}$**

including LHC injectors upgrade **LIU**  
(Linac 4, Booster 2GeV, PS and SPS upgrade)

# Goal of High Luminosity LHC (HL-LHC):

The main objective of HiLumi LHC Design Study is to determine a hardware configuration and a set of beam parameters that will allow the LHC to reach the following targets:

Prepare machine for operation **beyond 2025 and up to 2035-37**

Devise beam parameters and operation scenarios for:

#enabling a total integrated luminosity of **3000 fb<sup>-1</sup>**

#implying an integrated luminosity of **250-300 fb<sup>-1</sup> per year,**

#design for  $\mu \sim 140$  ( **$\sim 200$** ) ( $\rightarrow$  peak luminosity of **5 (7)  $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$** )

#design equipment for 'ultimate' performance of  **$7.5 \cdot 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$**   
and **4000 fb<sup>-1</sup>**

**$\Rightarrow$  Ten times the luminosity reach of first 10 years of LHC operation**




# LHC Upgrade Goals: Performance optimization

Luminosity recipe :

$$L = \frac{n_b \times N_1 \times N_2 \times g \times f_{rev}}{4p \times b^* \times e_n} \times F(f, b^*, e, S_s)$$


- 1) maximize bunch intensities → Injector complex
- 2) minimize the beam emittance LIU ↔ IBS
- 3) minimize beam size (constant beam power); → triplet aperture
- 4) maximize number of bunches (beam power); → 25ns
- 5) compensate for 'F'; → Crab Cavities
- 6) Improve machine 'Efficiency' → minimize number of unscheduled beam aborts

# Luminosity Levelling, a key to success




- High peak luminosity
- Minimize pile-up in experiments and provide “constant” luminosity

- Obtain about 3 - 4  $\text{fb}^{-1}/\text{day}$  (40% stable beams)
- About 250 to 300  $\text{fb}^{-1}/\text{year}$




# The HL-LHC Project



- **New IR-quads  $Nb_3Sn$  (inner triplets)**
- **New 11 T  $Nb_3Sn$  (short) dipoles**
- Collimation upgrade
- Cryogenics upgrade
- Crab Cavities
- Cold powering
- Machine protection
- ...

**Major intervention on more than 1.2 km of the LHC**

# Project Landmarks



CERN Novembre 2015



# Squeezing the beams: High Field SC Magnets

## Quads for the inner triplet

**Decision 2012 for low- $\beta$  quads**



**Aperture  $\varnothing$  150 mm – 140 T/m**

**( $B_{\text{peak}} \approx 12.3$  T)**

operational field, designed for 13.5 T



**=> Nb<sub>3</sub>Sn technology**

**(LHC: 8 T, 70 mm )**



	$\beta_{\text{triplet}}$	Sigma triplet	$\beta^*$	Sigma*
Nominal	~4.5 km	1.5 mm	55 cm	17 $\mu\text{m}$
HL-LHC	~20 km	2.6 mm	15 cm	7 $\mu\text{m}$

# First short model magnet MQXFS1 (1.5 m) Inner triplet Quad final cross section ( $\varnothing = 150$ mm)




**CERN - US LARP collaboration**  
**Design and  $\text{Nb}_3\text{Sn}$  coils by CERN and LARP together (50%-50%)**

**Full collider characteristics.**  
**Final length will be 3 to 5 times more**



# First short model magnet MQXFS1 (1.5 m) Result of the first energization @ FNAL



**Next: thermal cycle and memory test (and more...)**



# HL-LHC Upgrade Ingredients: Crab Cavities

## Crab Cavities: Geometrical Reduction Factor

- Reduces the effect of geometrical reduction factor
- Independent for each IP

$$F = \frac{1}{\sqrt{1 + Q^2}}; \quad Q \propto \frac{q_c S_z}{2S_x}$$


- Noise from cavities to beam?!?
- Challenging space constraints




Compact cavities aiming at small footprint & 400 MHz, ~5 MV/cavity

# Excellent first results: e.g. RF dipole > 5 MV

¼ w and 4-rods also tested (1.5 MV)



LARP





Initial goal was 3.5 MV  
however  $\Delta V > 5-6$  MV would ease integration



# In-kind contributions and collaborations for design, prototypes, production and tests

Discussions are ongoing with other countries, e.g Canada,...




Q1-Q3 : R&D, Design, Prototypes and in-kind **USA**  
D1 : R&D, Design, Prototypes and in-kind **JP**  
MCBX : Design and Prototype **ES**  
HO Correctors: Design and Prototypes **IT**  
Q4 : Design and Prototype **FR**

CC : R&D, Design and in-kind **USA**

CC : R&D and Design **UK**

# LHC / HL-LHC Plan



## HL-LHC Plan



# Conclusions

LHC is operational at 13 TeV c.m. and with 25ns beams

**2016 : production mode at 13 TeV ;  $> 30 \text{ fb}^{-1}$**


- 25 ns operation
- $\beta^* = 40 \text{ cm}$  in ATLAS and CMS ; 3m in LHCb ; 10m in ALICE
- Going towards combining ramp & squeeze
- Rapid intensity ramp up in spite several technical problems

*Nominal design luminosity  $1 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$  reached and exceeded ( $1.2 \cdot 10^{34}$ )*

- **Optimisation of the integrated luminosity** (availability  $\sim 65 \%$ )


**RUN 2 goal :  $> 100 \text{ fb}^{-1}$  and to reach  $300 \text{ fb}^{-1}$  at the end of RUN 3**

**LHC Injector Upgrade (LIU => LS2) and High Luminosity LHC (HL-LHC =>LS3) well defined and now in construction phase**





# Hvala na pažnji



[www.cern.ch](http://www.cern.ch)

