


HL-LHC

Lucio Rossi Project Leader

1st International Workshop of the Supeconducting Magnet Test Stands CERN – Globe of innovation, 13 June 2016

LHC



LHC the largest scientific instrument

LHC dipoles: the collider backbone

The dipole line in the LHC ring

- 27 km, p-p at 7+7 TeV 3.5+3.5 start, 4+4 in 2012 6.5+6.5 TeV in 2015
- 1232 x 15 m Twin Dipoles
- Operational field 8.3 T @11.85 kA (9 T design)
- HEII cooling, 1.9 K with 3 km circuits (130 tonnes He inventory).
- Field homogeneity bending stree






More than dipoles...

The pletora of SC magnets...

- 392 Main Quads Two-In-One rated for a peak field of 7 T.
- About 100 other Two-in-One MQs
- 32 MQX (low- β) single bore for luminosity (design L=1·10³⁴ cm⁻²s⁻¹), 70 mm apertures, about 8 T peak field, high quality
- A «zoo» of 7600 «small» Sc magnets (correctors and higher order magnets
- Total: 9 MJ stored energy (at nominal)









SC radiofrequency, Cryogenics,

LHC: much more than magnets...

400 MHz Standing wave RF

4 single cell cavities in cryomodule, 2 beam

fully cold tested

5.5 MV/m nominal (8 MV/m available)

Nominal 2MV, up to 3 MV at 8 MV/m


Cryo: 8 x 18 kW@4.5K

Collimators: 146











Why upgrading the LHC?



The project started in 2010 as EC-FP7 Design Study

High Luminosity LHC

From FP7 **HiLumi LHC** Design Study application



The main objective of HiLumi LHC Design Study is to determine a hardware configuration and a set of beam parameters that will allow the LHC to reach the following targets:


A peak luminosity of $L_{peak} = 5 \times 10^{34} \text{ cm}^{-2} \text{s}^{-1}$ with levelling, allowing:

An integrated luminosity of 250 fb⁻¹ per year, enabling the goal of $L_{int} = 3000 \text{ fb}^{-1}$ twelve years after the upgrade.

This luminosity is more than ten times the luminosity reach of the first 10 years of the LHC lifetime.



The bolt advance in luminosity





FP7-HiLumi classified as «success story» by EC





The HiLumi LHC Design Study (a sub-system of HL-LHC) is cofunded by the European Commission within the Framework Programme 7 Capacities Specific Programme, Grant Agreement 284404




Cryo@P4





Beam diagnostics BGV





Electrical transmission lines based on a high-temperature superconductor to carry current to the magnets from the new service tunnels near ATLAS and CMS.



15 to 20 new collimators and 60 replacement collimators to reinforce machine protection.

BENDING MAGNETS

4 pairs of shorter and more powerful dipole bending magnets to free up space for the new collimators.




HL-LHC project breakdown structure


WP1 WP9 Cryogenics Project Management WP2 **WP10** Accelerator Physics & Performance **Energy Deposition & R2E** WP3 **WP11** 11 T Dipole IR Magnets WP4 **WP12** Crab Cavities & RF Vacuum & Beam Screen WP5 **WP13** Collimation Beam Instrumentation WP6A **WP14 Beam Transfer & Kickers** Cold Powering **WP15** WP6B Integration & (De-)Installation Warm Powering WP7 **WP16** Machine Protection IT String & Commissioning WP8 **WP17** Infrastructure, Logistics & Civil Engineering Collider-Experiment Interface



High Luminosity LHC Project



Deep changes in the Inner Triplet region (around ATLAS & CMS experiments)



International collaborations: an opportunity and a challenge, also for testing!



International collaboration regards also tests

- SM18 @ CERN
 - HiLumi has triggered the SM18 upgrade and pays about half of it.
 - HiLumi IT string is in the plan since 2015 (see talk)
- US/LARP-AUP : FNAL and BNL
- INFN-LASA (Milano)
- UPPSALA univ.
- CEA ?
- More?



14

HiLumi counts on cryogenic full power tests: no harware will be installed without test

- First test in the chain is the strand/conductor! Try also to be synergic to these test!
- A Magnet not testet is not worth anything, yet!
- Testing, for HiLumi like for LHC, is integral part of the design-construction-qualification cycle:
 - Validation of design & basic choice
 - Verification of performance and of conformity to specs
 - Most crititical acceptance, releasing payment and tranfer of properties (from Industry or Collaboration)
 - → time and schedule are IMPORTANT!!!
 - Anticipate HWC and operation issues (stand-alon test and especially IT string)





Thanks to Marta for orgnaizing this meeting and all of you for the great support to HiLumi