RD51 Common Test Beam: Status

RD51 collaboration week
Kolymbari, June 2009
Yorgos Tsipolitis
NTUA

Outline

- RD51 Test beam requirements
- Schedule
- Experimental zone
- Setup sketch and mechanics
- Gas system & cables
- Magnet

Dedicated semi-permanent test beam

From the approved proposal:

"The collaboration would like to ask for the following resources and infrastructure at CERN:

[...] Access to irradiation and test beam facilities (including the possibility to keep "semi-permanent" setup). The collaboration foresees typically 2 annual test beam campaigns each of a few weeks duration."

Semi-permanent setup means the RD51 members can always find:

- Dedicated cables and gas pipes permanently lying in the zone
- Stable dedicated gas mixing racks in the gas zone
- Dedicated space, electronics racks, computers in the control room
- Devices such as trigger scintillator and tracking telescope, as well as support mechanics. They will be stored out of the beam line but in the experimental area or very close to it

2009 Specific test beam requirements

Requirements 2009:

- Dimension: around 60x60 cm² planar devices; weight: few kg devices
- CF₄ and flammable gas mixtures
- High resolution (better than 70µm) external tracker
- Low or high rate beam, typically MIPS (pions preferred)
- Mechanical Support allowing X-Y position and rotation
- High Magnetic field, sometimes together with low energy beam

Groups involved in summer time slot:

- CERN GDD Large Area GEM detector (large support)
- Frascati KLOE-2 GEM prototypes (magnet, flammable gases)

Groups involved in autumn time slot:

- CERN GDD Large Area GEM detector
- Paul Colas' Saclay group MicroMegas TPC (magnet, low energy beam)
- Stephane Aune's Saclay group MicroMegas (magnet?, flammable gases?)
- Bonn TPC (high energy beam, magnet?)


2009 test beam

PS Operation


Period 2 2009 Jun 4 to Jul 9

dule issue date: 14-April-2009		Version 3.0			(colour code: purple (dark) = scheduling meeting , light green (light) = weeken:					
7	Thu Fri Sat Sun N 4 5 6 7 Jun Jun Jun Jun V	8 9 10 11 1		on Tue Wed Thu 15 16 17 18 k24 Jun Jun Jun	19 20 2	un Mon Tue Wed 1 21 22 23 24 un Wk25 Jun Jun	25 26 27 28	Mon Tue Wed 7 29 30 1 Vk28 Jun Jul	Thu Fri Sat Sun Mon Tui 2 3 4 5 6 7 Jul Jul Jul Wk27 Jul	
achine BIG MD										
T2 -H2	NA61-TR	8h D Lazic			A DIMAL		WCALO	8h P Luukk	CMS-SiUpgr	
T2 -H4	NA63	Mazziotta	TRD 8h	Mazziotta S	SITRD	M Alfonsi	RI	D51	С MS ф Ç	
Period 6 2009 Oct 22 to Nov 23										
dule issue date. 14-April-2009 Version 3.0 (colour code. purple (dark) – scheduling meeting , ligh										
Thu Fri Sat Sun Mon Tue Wed Th									5	
achine Buchup										
T	8h			BIG	MD			NA61	<u>8</u> h	
T2 -H2 Sh Z Fodor						phys				
T2 -H4	8h M Alfonsi		RD5	1 Sh Sing	ovski	CMS-ECA	AL 8h Y Itow		_	


SPS/H4 line at Prevessin North Area







The RD51 installation @ SPS/H4




- Electronics rack is in a region with a 5-10mT fringe field
- Cables length can arrive up to more than 8 m

Yorgos Tsipolitis RD51-WG7

Setup "A" outside the magnet

Placed upstream Goliath, composed by a table with precisely-positioned tracking elements and an external support for the case of very large *Detectors Under Test* (DUTs)




Setup "A" table



- height ~ 70 cm
- Surface 85x120 cm² with a grid of holes
- Suitable for small (20x20 cm²), light (5 kg) tracking elements and DUTs
- In case of flammable gas, retention buckets can be added on the table (closing the fixation holes)
- Moved out of beam on the side when not used, without dismounting the tracker

Large detector support




Tracker & DAQ

- A new micromegas tracker, 3 x-y detectors, are ready and will be at CERN next Monday (Demokritos & NTU Athens groups)
- The DAQ system is already at CERN and working
- There is a problem with the block transfer that limits the R/O but will be fixed.

Setup "B" inside the magnet

WG7




Similar table mounted over rails

Rails will extend out of the magnet for about 1m, with two legs for support

Table will be moved out of the beam when not used. Rails will stay, if possible

More than 8m lenght for cable, to arrive from rack to the farthest part of the magnet, properly using cable trays



rail wheel


12

Setup "B" inside the magnet



Gas Pipes

- Stainless steel from gas zone to a patch panel in the experimental area
- 5 lines, each with 6mm diam. pipes for inlet and 10mm diam. pipes as exhaust



RD51-WG7

14

Cables list (barrack -> area)

Lines installed from the experimental area to the barracks

- Fiber line x2
- Ethernet lines x3 + 2 small switches at both sides
- SHV lines x4
- 16 LEMO coaxial cables

Still missing:

- Other fiber lines for October
- More coaxial cables

Cables inside the experimental area must be provided by the users!!!


Specification and field map from NA57

Power: about 2MW Maximum field: 1.4T

Gap volume: around 8 m³

Max. water pressure: 10 bar

 Looking at the map realized during NA57 experiment, the field seems to drop fast when approaching the border.



Field map realized during NA57 experiment, file decoded by Frascati group

RD51-WG7