



Vacuum System for DDBA and Lessons Learned for Diamond-II

Matthew Cox Diamond Light Source, UK

matthew.cox@diamond.ac.uk www.diamond.ac.uk




Overview

- Requirements
- Vacuum pumping design
- Vessel manufacture
- Build and processing



Why DDBA?

Need for additional insertion devices \rightarrow Double Double Bend Achromat (DDBA) concept: Replace one or two "DBA" cells with a new "DDBA" cell creating a new mid-cell straight section for an Insertion Device, thus converting a BM beamline into an ID beamline.



 Exploration of technology needed for a possible major upgrade, Diamond-II with smaller emittance. One contender for Diamond-II has a DTBA lattice which would have many vacuum system similarities with DDBA

diamond Vacuum requirements

- Replace entire vacuum system for one cell (17.35m)
- Beam physics compatible: Impedance, Beam stay clear, RF heating, DC/AC magnets, SR heat loads ...
- CO equivalent p ≤ 10⁻⁹ mbar with stored beam (Z² weighted sum of partial pressures)
- No pressure bursts or particles to trip beam

 Installation + beam conditioning in a working machine with ≤ 8 weeks downtime

😔 diamond 🔰 Vacuum pumping design


- Vacuum vessels typically 18 x 27 mm ellipse internal
- No NEG coating. Discrete ion pump and Non-Evaporable Getter (NEG) pumps fitted in where space ... not in optimum places for vacuum.
- Mixture of distributed <u>and</u> lumped photon absorbers

NEG coating	No NEG coating
Better ultimate vacuum Only active gases pumped (in the absence of SR) so may required auxiliary pumping anyway.	Worse ultimate vacuum between pumps – should be good enough though All gases can be pumped
Quicker beam conditioning (few A.h)	Slower beam conditioning (100s A.h)
Always need to bake / reactivate after venting (probably)	Don't always need to rebake after venting
Significant R & D and setup time and effort needed for variety of vessel geometries	Much less R & D, time and effort needed
Sensitive to saturation, surface poisoning, flaking etc	No coating to flake off or get poisoned Larger pumping capacity.
Probably more expensive overall (at commercial coating prices). Economics may be different for a whole machine	Probably cheaper overall despite additional discrete pumps, controls, wiring etc

New DDBA Arc Layout

Photon beam extraction at crotch 1 and 3 only Built up on 2 girders

Existing RF gate valve



ALERT Workshop, Trieste, Sept 2016

diamond

😔 diamond 🔹 Vacuum pumping design


Was it a good choice?

Indications are positive so far:

Simulations say it will work

Static pressure and cleanliness (RGA scans) before installation are good


Yet to be installed and tested with beam – PSD and beam conditioning, Heating (RF and SR), Impedance, Mechanical stability and alignment, Pressure spikes, beam losses and beam trips etc



ALERT Workshop, Trieste, Sept 2016

diamond Vacuum vessel design

- Vessel materials copper alloy (OFS, OFHC) and stainless steel (316L, 316LN)
- Cross section typically 18 x 27 ellipse internal. Much smaller cross section and more delicate than Diamond-I vessels
- Fabrication by TIG welding, vacuum brazing, e-beam welding
- Incorporate distributed and lumped water cooled absorbers with bumps to shadow flange joints
- Low gap flange joints (Helicoflex[®] sealed) in e-beam path. Standard CF flanges otherwise.




Typical Diamond-I and DDBA vessel cross sections



27x18 ellipse section in OFScopper with e-beam welded cooling channel



Vacuum vessels



ALERT Workshop, Trieste, Sept 2016


Dipole 1,3,4 vessels


Copper

diamond


Antechamber to allow SR - BM (+ ID for dipole 1 and 3) to exit to downstream crotch No water cooling needed











Manufacturing method to reduce distortion: Machine 2 halves E-beam weld together Vacuum braze adapter into flange Cu-Cu TIG weld vessel to flange adapter. Late stage pro

Cu-Cu TIG weld vessel to flange adapter. Late stage problems with weld cracking led to change to vacuum braze with stainless steel intermediate piece. Needed to re-run thermal FEA. Trial welds had not been not fully representative.




Weld cracking

> Additional stainless steel intermediate piece









ALERT Workshop, Trieste, Sept 2016



Dipole 2 vessel and straight vessels











Orbital weld

Copper / stainless steel elliptical tube - curved E-beam welded external water cooling channel NEG cartridge pump ports Internal cooled bumps to shield flange joints from SR

NEG pump interface



SR shadowing bump





ALERT Workshop, Trieste, Sept 2016




BPMs

Improved design compared with previous BPM buttons at DIAMOND to reduce RF heating





6mm button – new ESRF type





Outer gap between shroud and vessel

> Inner gap around button

button and vessel


BPM station fitted with bakeable Kapton insulated cables


Manufacture and welding-in relatively unproblematic – yet to be tested with beam



RF bellows

Similar to Diamond-I but scaled down to smaller cross section Manufacture relatively unproblematic






Flexible RF contact assembly on test



BPM with double RF bellows



BPM with single RF bellows



RF Compatible Helicoflex[®] Flanges: Lab Tests



Test setup

Requirements


Low RF impedance (zero gap) Lateral alignment <100µm Reliable seal Tolerant to thermal cycling

A number of options explored

Helicoflex[®] Standard seal selected

Helicoflex[®] seals widely used in other industries, e.g. nuclear, fusion and are generally regarded as reliable

Positive lab tests in all different sizes needed - gaps, steps, leak rate, thermal cycling



DN63CF





Helicoflex DN63

diamond RF Compatible Helicoflex[®] Flanges: In Practice

In practice not quite so straightforward

- Sealing problems at vessel supplier
 - Surface finish seems critical milled / turned / polished
 - Different size seals behave differently
 - Not fully understood
 - Seems reliable with correct surface finish
- More sensitive to particles than standard CF type seals
- Leak testing was slow and difficult add leak testing grooves!
- Expensive, long delivery, single source supplier (more recently second source)

On the plus side

- Removable dowel pins for lateral alignment work well
- Only one leak at Diamond which was due to inadequate clean assembly conditions
- Further R & D needed to understand the sealing behaviour before it could be selected for a major project



DN40 Helicoflex[®] sealed flange on dipole vessel showing groove for removable alignment dowel pin, spot welded temperature sensor and survey monument blocks



Imprint of machine groove pattern on DN40 Helicoflex[®] seal (5 mm graph squares)

😓 diamond

Vessels contract

Milestone	Target	Actual/Current	Delay (months)
Vessels contract placed	Aug 2014	Aug 2014	0	
Vessels final design review	Dec 2014	Jan 2015	1	
Vessels first complete set delivered	Jul 2015	Feb 2016	7	Puild time
Installation	Aug/Sep 2016	Oct/Nov 2016	2	Build time

Delays mainly due to:

- Several different challenges with welding in production (TIG, e-beam)
- Supplier had to develop orbital welding machine for elliptical tube butt welds which tool much longer than expected
- Helicoflex seal issues
- A few components had mechanical errors when received despite factory inspection and had to be worked around / reworked
- Experiences still to be explored in more detail with supplier. Lessons to learn on both sides.

Lessons learned:

- More allowance to sort out problems with first production batch. No opportunity to catch up on series production in this case.
- Challenge supplier assumptions on manufacturing methods and timescales
- Define trials better in the tender / contract. More representative trials early on
- Define factory inspection requirements better. More detailed inspection drawings. Improve site inspection.
- Diamond technician training on handling delicate vessels at the supplier factory was very valuable

diamond Build and installation sequence

- Completed
 - Fully tested and qualified vessels (200°C bakeout) delivered from supplier(s)
 - Vessels and vacuum equipment trial-assembled on the 2 girders without magnets or NEG cartridges
 - Pump down and 200°C bakeout. Vessels uninstalled
 - Magnets aligned on girders and magnet tops removed
 - Vessels and vacuum equipment final-assembled on the 2 girders with magnet bottoms and NEG cartridges.
 - Pump down and 200°C bakeout. Remain under vacuum
 - Magnet tops re-fitted

diamond Build and installation sequence

- Next steps
 - Final preparations for installation
 - Installation in the storage ring tunnel under vacuum without venting and without re-baking
 - Connect up to adjacent vacuum sections and front end (re-bake these sections if necessary)
 - Open gate valves, inject beam and carry out beam vacuum conditioning



😔 diamond 🔹 Vacuum build sequence Lessons Learned

- Difficult to achieve required cleanliness with open vessels on the girder and other activities around. A leak seems to have been caused by particles / fibres trapped in the Helicoflex seal
 - Need to improve clean conditions around open vacuum vessels
 - Better housekeeping from all teams
- Due to shortened build time and cramped space there were issues with too many different teams working in the same area at the same time with inefficiency and risk of damage
 - Better coordination of different teams' activities
 - More space for working and storage



Small fibre (ca 10µm dia) and particle (ca 200µm) on Helicoflex[®] seal







diamond On-girder bakeout in practice


- Combination of Kapton film heaters (\leq 50VDC), heated jackets, braided heaters and flange band heaters (230VAC) with Al foil in places
- PLC-based control system •
- Trial bakeout 200°C without magnets
- Final bakeout (target 200°C) with magnet bottoms only and dipole magnets retracted – in practice limited to 180°C to keep magnet poles below 70°C.



Braided heater on x-ray extraction leg

Kapton film heater on elliptical





PLC bakeout control racks and display



	KAPTON	BAKEOUT	TEMPER	ATURES	1100000	
180°C		180°C		180°C		
180°C		181°C	178°C	180°C		
180°C		180°C		179°C		
STANDARD BAKEOUT TEMPERATURES						
180°C		180°C		180°C		
184°C		180°C		180°C		
180°C		180°C		180°C		
180°C		180°C	**	180°C		
180°C		180°C		180°C		
180°C						
MEAN 180. 1°C TARGET 180. 0°C Δ 6. 1°C						
BAKE PAUSED INTERLOCKS INFO MAIN						




Heated jacket on NEG pump housing

ALERT Workshop, Trieste, Sept 2016

diamond On-girder bakeout in practice

- Lessons learned
 - Generally worked well, however
 - Wiring was complicated and not well thought out
 - It took a lot of adjustment to get uniform ramp up and temperatures ±10°C
 - Due to bug in PLC code one trial bake overheated and caused some damage to heaters and vessels
 - Hardware over-temperature protection added
 - PLC code testing improved
 - Vessel was not exactly centred in magnet poles reducing clearance for heaters
 - Review tolerances
 - Magnet poles got hotter than expected







Hardware over-temperature protection added

Over-temperature damage



- Diamond-II
 - Design input, prototyping and series production of vessels and vacuum components (on time please !!!). Improved tolerances and inspection.
 - Coatings and surface treatments (low outgassing, low PSD/ESD, low SEY, pumping ...)
 - Novel materials, manufacturing and joining techniques (e.g., additive manufacturing ...)
 - Cost reduction of expensive processes for series
 production e.g. NEG coating



Thanks to

Diamond Vacuum Group Diamond DDBA Team Suppliers






Backup slides





😔 diamond 🛛 Existing (DBA) Arc Layout



diamond NEG cartridge pump interface studies

- Elliptical tube 27 x 18 internal x 1 mm WT
- 8 pumping slots 3 mm wide x 33.5 mm long
- Compromise between vacuum pumping and beam impedance
- NEG cartridge SAES Getters Capacitorr D400-2
- Does not pump CH₄ or inert gases







Comsol fmf results	H ₂	СО
Naked NEG cartridge pump speed	400 l/s	180 l/s
Gas flow in	1E-5 mbar l/s	1E-5 mbar l/s
P in pump body	2.21E-8 mbar	4.88E-8 mbar
Effective pump speed within pump body	452 l/s	205 I/s
P at pump port	5.32E-8 mbar	1.65e-7 mbar
Effective pump speed at beam tube	188 l/s	61 l/s

ALERT Workshop, Trieste, Sept 2016


diamond Calc pressure profile 100Ah no NEG coating



diamond Calc pressure profile 1000Ah no NEG coating




😔 diamond 🔰 Calc beam conditioning no NEG coating



ALERT Workshop, Trieste, Sept 2016

Calc beam conditioning NEG coating



 $I_{beam} = 300 \text{mA}$

ALERT Workshop, Trieste, Sept 2016

diamond

😔 diamond 👘 Vacuum vessel tests at supplier



Building up of vacuum strings




Flexible bellows / BPM units



RF gate valve alignment



Survey of vessel string assembly



Measurement of deflection on pump down

ALERT Workshop, Trieste, Sept 2016