

# FINDINGS AND CONCLUSIONS OF THE WORKING GROUP ON FUTURE IRRADIATION FACILITIES



I. Efthymiopoulos, EN/MEF - for the Irradiation Facilities WG

<http://cern.ch/irradiation-facilities>

## Outline

- Introduction on irradiation facilities
- Present situation
- User survey
  - ▣ Future prospects
  - ▣ Possible implementations
- Summary – next steps

# Irradiation facilities working group

2

## Composition

### CERN-wide working group:

- **L. Linssen – PH/DI (chair)**
- R. Assmann – BE/ABP
- J. Bauche – TE/MSC
- M. Brugger – EN/STI
- M. Capeans – PH/DT
- F. Corsanego – DG/SCG
- I. Efthymiopoulos – EN/MEF
- R. Losito – EN/STI
- H.G. Menzel – DG/SCR
- M. Moll – PH/DT
- C. Rembser – PH/ADE
- M. Silari – DG/SCR
- Y. Thurel – TE/PO
- R. Trant – DG/SCH
- E. Tsesmelis – DG/DG
- H. Vincke – DG/SCR
- T. Wijnands – EN/STI

### Mandate:

- Collect requirements for future irradiation facilities at CERN, taking into account availability of facilities outside CERN
- Put these requirements in the context of presently available facilities/infrastructures at CERN.
- Propose cost-effective options for future facilities, aiming for a maximum of synergy.
- Produce a (yellow) report on the findings

## Introduction

- ❑ Irradiation facilities – what for?
- ❑ Setup and operate an irradiation facility – what it really involves?

# Irradiation facilities

4

What for?

- Test and development of prototypes or final assemblies before installation in a radiation environment
  - ▣ issues addressed (not exhaustive)
    - SEE, radiation damage, performance degradation of electronics
    - beam impact or radiation damage on materials
    - performance degradation after long exposure (ageing)
    - performance evaluation under background/"noise" conditions
  - ▣ passive or "hot" (i.e. online) irradiations
  
- Test or calibration of components
  - ▣ radiation measurement devices
  - ▣ radiation monitoring devices
  - ▣ feedback data to simulation codes

# Setup and operate an irradiation facility

5

## What it really involves?

- **Deliver the desired beam**
  - intensity, beam spot, time structure (slow or fast extraction)
  - steering : beam and/or equipment (scanning table)
  - monitoring of beam intensity and radiation field
    - reference maps available to users
  
- **Control the radiation environment**
  - shielding, escaping radiation must remain within limits
  - for high intensities:
    - closed ventilation loop, humidity control
    - radiation in downstream areas
    - Impact on infrastructure – optimized maintenance procedures
  
- **Access conditions**
  - pre-test documentation, preparation and optimization: materials, time
  - access authorization, training
  - traceability : in/out movements, logs, RP control

# Setup and operate an irradiation facility

6

... what it really involves?

- **Auxiliary installations**
  - **storage area**
    - initial cool down just after exposure
    - medium/long term storage in view of future re-use
  - **qualified lab** to work on exposed materials
    - modify for re-use or next testing
    - analysis after irradiation
  - nearby control room for “hot” tests during exposure
  - **remote handling** of equipment and services
  
- **Final product: scientific results in use of the community**
  - document and spread out the knowledge
  - **results database**: materials, components, ..
  
- **.. and radioactive waste**
  - **must be considered from the beginning !**

# Present Irradiation Facilities

- PS

- **Proton irradiation** facility in the East Area

- SPS

- **GIF - Gamma Irradiation Facility** in the West Area
  - **CERF - CERN Reference Facility** in the North Area
  - (parasitic) irradiation of electronics in CNGS


- ... and ad-hoc tests** – now decommissioned

- (parasitic) irradiation of electronics in the SPS/TCC2 target area
    - material test (collimators, targets) in TT40 line
    - (parasitic) irradiation of materials or “target units” in ISOLDE

# Proton irradiation in the **PS East Area**

8

Layout



# Proton irradiation in the **PS East Area**

9



## Characteristics

- Protons and mixed field irradiations
  
- Intensities
  - ▣ **max  $10^{11}$  protons/extraction** (slow or fast-slow extraction)
  - ▣ up to  $10^{14}$  protons/(cm<sup>2</sup>hr) on a 2×2 cm<sup>2</sup> surface
  - ▣ up to  $10^{12}$  neutrons/(cm<sup>2</sup>hr) on a 30×30 cm<sup>2</sup> surface (1 MeV equiv.)
  
- In operation since 1992
  - ▣ up to **1500** irradiated samples per year
  - ▣ mainly used by detector communities: trackers, electronics
  
- **Drawback:** 😞
  - ▣ parasitic operation to DIRAC, access via primary beam area, personnel exposure, limited space, limited rate

# CERN Reference Facility – SPS NA

10

H6 beam in the SPS North Area EHN1 experimental hall



# CERN Reference Facility – SPS NA

11

## Characteristics

- SPS H6 secondary beam, **120 GeV/c hadrons**
  - ▣ 56% protons, 39% pions + 5% Kaons
  - ▣ well defined and simulated mixed radiation fields
  
- Intensities
  - ▣ **max  $10^8$  protons/pulse** (5s) (slow extraction)
  
- In operation since 1992, 1-2 weeks/year
  - ▣ mainly used for test/calibration of passive and active detectors for dosimetry or radiation monitoring
  - ▣ ~20 teams/week, internal and external users
  - ▣ FLUKA benchmarking, beam loss monitor studies
  
- Drawback: 😞
  - ▣ limited dose rates, muon background from TCC2 (reduced since 2006)

# Gamma Irradiation Facility – West Area


12

Area layout



The Cs<sup>137</sup> source container

The external screens and collimators



# Gamma Irradiation Facility – West Area

13


## Characteristics

- **740 GBq Cs<sup>137</sup>** source, irradiation over large surfaces
- Combined with (muon) beam from X5 line
- In operation since 1997
  - ▣ all year (source), some weeks (beam)
  - ▣ mainly used for tests of muon detectors for LHC experiments
    - ageing tests, performance under “background” conditions (photons from the source)
- **Drawback:** ☹
  - ▣ more intensity would be desirable (accelerated ageing) , combined with higher muon beam energy
  - ▣ space issue in bat.190 → space needed for LHC magnet lab

# Irradiation of electronics – SPS/TCC2

14

Parasitic mixed field irradiations – layout




- ❑ Mixed field irradiation, high doses within reasonable time
- ❑ Clients: LHC accelerator groups, testing components and electronics
  - ❑ up to 25 experiments/year
  - ❑ sufficient space to test complete systems
- ❑ Drawback: ☹
  - ❑ Parasitic ad-hoc test
    - ❑ no reproducible radiation conditions
    - ❑ high residual dose rate in the area (access, safety)

# Pulsed proton irradiation – **TT40 line**

15

Intense proton beam irradiation - layout





- Used for LHC collimator studies and material tests in 2004 and 2006
- Short pulses at 450 GeV/c
  - up to  $3.3 \times 10^{13}$  ppp (approx. 2 MJ)
- Drawback: ☹
  - limited space
  - interference with CNGS operation and LHC fill
  - area not ideal in terms RP aspects
    - production of radioactivity close to beam line elements
    - access conditions

# CNRAD electronics irradiation - CNGS

16

Parasitic mixed field irradiations CNGS service gallery - layout



Test stations in the service gallery



# CNRAD electronics irradiation - CNGS

17

## Characteristics

- Exposure to mixed high-energy radiation fields, well-known field thanks to extensive FLUKA simulations
  
- Mainly focused for SEE on installed LHC electronics
  - four stations fully equipped for remote control and readout of components
  - possible to test complete systems (crates)
  
- Dose rates :
  - CNGS : 1 to 150 Gy per week
  - LHC ARC-DS : 1 to 200 Gy per year
  
- Drawback: ☹  
Parasitic to CNGS, access conditions, long access tunnel, safety

# User survey

- ❑ Survey results
  - ❑ Requirements, future prospects,
  - ❑ Possible implementations

# User survey

19

## Future needs for irradiation facilities

- **Web-based questionnaire launched to a very wide community**
  - Details in : <http://cern.ch/irradiation-facilities>
  - **134 replies**
    - extensive requests from LHC experiments and accelerator groups for present and in view of the upgrade program equipment
  
- **Questions asked on:**
  - Beam type: gamma, proton, mixed field
    - particle energy, spill-type, ...
  - Total dose, irradiation surface, exposure profile
  - Dimensions of experimental area, infrastructure
  - Access needs during exposure
  
- Thorough analysis of the replies to understand the user requirements. The WG investigated the possibilities to combine needs and minimize the proposed facilities. Diverse requirements make several facilities necessary, at least in the present landscape of accelerators.

# User survey - conclusions

20

Identified needs

## 1. High-energy and high-density proton(ion) irradiations : 5 replies

↪ impact of intense pulsed beams to materials

↪ proposed facility : **HiRadMat**

↪ primary use : LHC collimators & absorbers

## 2. Gamma irradiations with beam : 36 replies

↪ study long-term exposure of equipment

↪ proposed facility : GIF → **GIF++**

↪ primary use : muon trackers of LHC experiments, detector or accelerator electronic components, beam diagnostic equipment

# User survey - conclusions

21

## Identified needs

### 3. High-intensity proton irradiation (slow, slow-fast extraction): 51 replies

- ↪ study long-term exposure of equipment
- ↪ proposed facility: continue with **PS East Area** → future???
- ↪ primary use: inner trackers of LHC experiments, detector or accelerator electronic components, beam diagnostic equipment

### 4. Mixed field irradiations : 36 replies

- ↪ study impact on system components exposed in radiation fields
- ↪ proposed facility : **CNGS**, CERF → **CERF++**
- ↪ primary use: LHC accelerator and detector components (SEE studies), radiation monitoring calibration

### Heavy ions: 12 replies

- ↪ the feedback does not indicate the need for a construction of an exclusive Heavy Ion Irradiation Facility. If the availability of ions can be added at low cost to the plans for one of the future CERN irradiation facilities, it should definitely be included.

# The **HIRADMAT** Facility

22


## Key assets

- Study the impact of intense pulsed beams on materials
  - ▣ Thermal management (heating)
    - material damage even below melting point
    - material vaporization (extreme conditions)
  - ▣ Radiation damage to materials – change of properties
  - ▣ Thermal shock - beam induced pressure waves
  
- Test bed, important for the design validation of LHC near-beam components before installation in the machine
  
- Requires **LHC-type** beam from **pilot to 288 nominal bunches**

# The HIRADMAT Facility


23

## Possible implementation in the TT60/WANF tunnel



Parameter	Unit	Value (proton beam)	Value (lead ion beam)
Beam energy	GeV	450	$36.9 \times 10^3$ (177.4 GeV/n)
Bunch intensity	particles	$5 \times 10^9$ to $1.15 \times 10^{11}$	$5 \times 10^9$ to $4.1 \times 10^{10}$
Bunch length	cm	11.2	11.2
Number of bunches	-	1 – 288	1 – 592
Bunch spacing	ns	25	$\geq 25$
Pulse energy	MJ	2.4	$28 \times 10^{-5}$
Pulse length	$\mu$ s	7.2	7.2
Peak power	GW	340	2.3
Normalized emittance ( $1\sigma$ )	$\mu$ m	3.5	1.4
$\sigma_x \times \sigma_y$ at exp. (baseline)	mm <sup>2</sup>	1.0	1.0
$\sigma_x \times \sigma_y$ at exp. (request)	mm <sup>2</sup>	0.25 – 4.0	0.25 – 4.0

- modify the TI2 extraction line to deflect an LHC-type beam towards the old WANF area tunnel
- max intensity:  $1 \times 10^{16}$  prot/year
  - ▣ 10 experiments,  $1 \times 10^{15}$  prot/exp
- requested start of operation: Oct'10
  - ▣ to be adapted to the new LHC schedule and long 09/10 shutdown



- Test area upstream the T9 target
- Convert T9 to a beam dump
  - ▣ Remove target head and replace with special blocks like in CNGS hadron stop: Graphite core, Al plates with cooling
  - ▣ Add lateral shielding (concrete)
  - ▣ Reuse blocks from T1 (TAX area) to add downstream shielding

- Cleanup the whole tunnel
- Dismantle/condition WANF equipment
  - ▣ Horns/He-tanks could be stored locally until disposal path (and budget) agreed
  - ▣ Move the rest to waste
- Maintain escape passage from tunnel end

# GIF++ facility

24

New GIF++ facility in the SPS North Area – H4 beam line

## □ Source

- **Cs<sup>137</sup> (662 keV) 10TBq** (GIF in West-area: 740GBq)
- movable filters, as present source
  - attenuation down to  $F=10^5$
- second irradiation facility


## □ Secondary beam – H4 line

- muon beam
  - 100GeV/c,  $\sim 10^4$   $\mu$ /spill, 10x10cm<sup>2</sup>
- electron beam

## □ Shielding

- Cs<sup>137</sup>: 0.092mSv/hr @1m ;
  - ↪ 10TBq: 1Sv/hr @1m
- radiation limits for supervised area: <3 $\mu$ Sv/h
  - ↪ factor 10<sup>6</sup> required,  $\rightarrow$  1.6m concrete

## □ Requested start of operation : 2010



# Proton irradiation

25

Proposal


- **Maintain with minimal investment the PS East Area facility**
  - ▣ improved duty time to gain x2 in integrated rate (scheduling?)
  - ▣ upgrade in the beam monitoring systems
  - ▣ upgrade in the mobile trolley and cabling
  
- **Possibility for major upgrade strongly linked to DIRAC experiment and PS machine lifetime**
  
- **Plan for a high-intensity proton irradiation facility coupled to the future machines (SPL/PS2)**
  - ▣ proton and mixed field irradiations could co-exist

# Proton irradiation

26


Possible implementation coupled to SPL /EURISOL project

IMPLANTATION DE L'ENSEMBLE Linac4-SPL-PS2 / Solution de base



- SPL beam towards
  - the CHORUS/NOMAD exp. Hall
  - or nTOF area

- Construct new irradiation facility coupled to the ISOLDE/EURISOL target area




# CERF++ mixed field irradiation facility

27


## Possible CERF++ implementation in the H4 beam line

- Transport an attenuated proton beam in the H4 beam line up to the entrance of EHN1 hall
  - Feature last used for NA31 in 1986
- Beam intensity :  $<1 \times 10^{11}$  p/spill
- measurement locations around the thick target

- FLUKA Simulation
- $10^{10}$  particles/spill @ 450 GeV/c
- Contour =  $15 \mu\text{Sv/h}$



Eduard.Felbaumer@cern.ch



# Summary

28

- The WG was a good opportunity to bring together experts from various departments to promote collaboration and common solutions
- A complete survey of the needs of the whole community for irradiation facilities was made. A summary report is under preparation
- Short and long term needs identified, supporting the request for improved facilities in view of the LHC (machine and detectors) upgrades
- Next steps: advance from the feasibility studies to implementation and technical designs
  - requires the endorsement from the management
  - budget and manpower issues need to be resolved ; some funding is available in the White Paper and EU/FP7 projects
- To meet the requested time scale and be in phase with the LHC upgrade studies work must start already this year!