

Session 9 : What will we do with beam in 2009/10 ?

What would we like to do ?	
Experiments desiderata	M. Ferro-Luzzi
Protons in LHC	W. Herr
Ions in LHC	J. Jowett
Are we ready to do it ?	
Beams in the injectors	E. Metral
Commissioning plan	S. Redaelli
Organization	G. Arduini

450 GeV running

Is it useful ?

- Yes! Contrary to a year ago: Experiments request a 900 GeV runlet
- All Experiments wish to make use of 2 or 3 shifts of stable colliding beams, still in the noise of the beam commissioning schedule

When ?

- As soon as possible
- Solenoids on
- No need to wait for high intensities
 - happy with $k_b = 2$, $\beta^* = \text{injection value}$, $N = \sim 9 \times 10^{10}$

for info: about $10^{28} \text{cm}^{-2} \text{s}^{-1}$
 $\times 10^5 \text{s} = \sim 1 \text{nb}^{-1}$
($\sim 5 \times 10^7$ inelastic interactions)

Why ?

- Mainly: time alignment, space alignment
- Also: physics cross check (a few basic distributions, cross section)

if luminosity measured
(fast separation scan?)

Discovery channels for General Purpose Detectors

- **With 50-100 pb⁻¹ good data at 10-8 TeV ⇒ many new limits set on hypothetical particles (some more stringent than Tevatron), or even discoveries possible!**
- **With 200-300 pb⁻¹ good data at 10-8 TeV ⇒ start competing with Tevatron for Higgs masses around 160 GeV**
- **With 1 fb⁻¹ good data at 10 TeV ⇒ find Higgs if around 160 GeV**
- **The higher the energy, the faster it goes...**
- **Note: below ~20-40 pb⁻¹ at 10-8 TeV, or at any lower energy, one would probably start talking about an "engineering run"**
(can still be very useful, but perhaps not in terms of immediate physics results)

Non GPD

■ LHCb

- B cross section does not vary as drastically as for high mass objects. Thus, the request to go to highest possible energy is milder
- Need $0.3\text{-}0.5 \text{ fb}^{-1}$ at $s^{1/2} \geq 8 \text{ TeV}$ to surpass Tevatron in B physics
- Need at least 5 pb^{-1} at $s^{1/2} \geq 4 \text{ TeV}$ to collect good sample of J/psi

■ ALICE with *pp*

- Not as strongly interested as GPDs in reaching the highest possible energy for *pp*
- What about $s^{1/2} = 5.5 \text{ TeV}$? (the *NN* equivalent in PbPb@14TeV)
 - not so crucial at this stage, but yes, would request to choose $E=2.75 \text{ TeV}$ if a beam energy between 2 and 3 TeV was being considered
- Will collect data at $\sim 10^{29} \text{ cm}^{-2} \text{ s}^{-1}$ (opt) or $3 \times 10^{30} \text{ cm}^{-2} \text{ s}^{-1}$ (max)
- Runs with smallest possible β^* (while remaining at desired luminosity, and with full B_{spectr})
- Particularly interested in “symmetric shift” filling schemes and in 50ns (as opposed to 25ns)

TOTEM and LHCf

- **TOTEM (IP5)**
 - T1, T2, all RP220 and some RP147 will be ready
 - TOTEM will operate under all running conditions
 - Early optics ($\beta^* = 3$ m): large $|t|$ elastic scattering, central diffraction
 - As soon as technically feasible: request $\beta^* = 90$ m optics (or a gradual unsqueezing from $\beta^* = 3$ m to higher values)
- **LHCf (IP1)**
 - Lumi limitation: degradation of non rad-hard components after few pb^{-1} in data taking position
 - move out by 10 cm when $L > 10^{30} \text{ cm}^{-2} \text{ s}^{-1}$
 - dismount & remove detector when $L > 10^{3?} \text{ cm}^{-2} \text{ s}^{-1}$
 - Preferred operating conditions:
 - 2x2 and 43x43, $L = 10^{29} \text{ cm}^{-2} \text{ s}^{-1}$, crossing angle 0 and 140 urad (enhanced acceptance)
 - 156x156 introduce pile-up (2us electronics)

LHC performance

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$\text{Eventrate} / \text{Cross} = \frac{L \sigma_{\text{TOT}}}{k_b f}$$

Key parameters are $\gamma N k_b \beta^*$ and they are strongly correlated

γ Energy not a free choice but has consequences for $F N \beta^*$

N Number of bunches has consequences for $F \beta^*$ and machine protection



k_b Bunch intensity has consequences for beam-beam and pileup

β^* Has consequences for $N F$ and aperture

Smaller emittances ? Could be problems

$$\Delta Q \propto \xi = \frac{N \cdot r_o \cdot \beta^*}{4\pi \gamma \sigma^2} = \frac{N \cdot r_o}{4\pi \epsilon_n}$$

Energy and β^*



43 and 156 bunch schemes (no crossing angle)

43 bunch operation				
displaced	0	4	11	19
IP1	43	43	43	43
IP2	42	34	21	4
IP5	43	43	43	43
IP8	0	4	11	19

156 bunch operation			
	no bunches displaced	option 1	option 2
IP1	156	156	156
IP2	152	76	16
IP5	156	156	156
IP8	0	36	68

Assuming $N = 0.4 \cdot 10^{11}$, $\epsilon_n = 3.75 \mu\text{m}$

Energy (TeV)	β^* (m)	\mathcal{L}_{43} ($\text{cm}^{-2}\text{s}^{-1}$)	\mathcal{L}_{156} ($\text{cm}^{-2}\text{s}^{-1}$)
0.45	6	$0.13 \cdot 10^{30}$	$0.47 \cdot 10^{30}$
2.75	1	$4.30 \cdot 10^{30}$	$15.6 \cdot 10^{30}$
5.00	0.6	$13.0 \cdot 10^{30}$	$47.0 \cdot 10^{30}$

All compatible with aperture, consider as limit

Multibunch operation (crossing angle)

Requires crossing angle α to avoid parasitic interactions


Bunch spacing	Δs	# long range encounters (per IP)
25 ns	3.75 m	32
50 ns	7.50 m	16
75 ns	11.25 m	12

Spacing	IP1	IP2	IP5	IP8
25 ns	2808	2736	2808	2622
50 ns	1404	1368	1404	0
75 ns	936	912	936	874

	a	b	c	d	e
IP1	1404	1404	1404	1404	1333
IP2	1368	684	0	72	2
IP5	1404	1404	1404	1404	1333
IP8	0	655	1311	1242	1173

Crossing angle

$$\alpha = \frac{d_{sep} \cdot \sqrt{\frac{\epsilon_n}{\gamma}}}{\sqrt{\beta^*}}$$



Operation with β^* between 1 m and 4 m very promising

Multibunch operation

Assume $0.5 \cdot 10^{11}$ per bunch, and crossing angle $\approx 300 \mu\text{rad}$

Luminosity (in IP1 and IP5) in units of $10^{32} \text{ cm}^{-2} \text{ s}^{-1}$

Energy (TeV)	β^* (m)	\mathcal{L}_{936} ($\text{cm}^{-2} \text{ s}^{-1}$)	\mathcal{L}_{1404} ($\text{cm}^{-2} \text{ s}^{-1}$)	\mathcal{L}_{2808} ($\text{cm}^{-2} \text{ s}^{-1}$)
5.0	3.0	0.9	1.4	2.8
5.0	2.0	1.4	2.1	4.2
5.0	1.0	2.6	4.0	8.0
7.0	3.0	1.3	2.00	4.0
7.0	2.0	2.0	3.00	6.0
7.0	1.0	4.0	6.00	12.0

Delivered luminosities

(10^6 seconds @ $\langle L \rangle$ of $10^{33} \text{ cm}^{-2} \text{ s}^{-1} \rightarrow 1 \text{ fb}^{-1}$)

- Without crossing angle

Could hit few $10^{31} \text{ cm}^{-2} \text{ s}^{-1}$ say $\langle L \rangle$ of $10^{31} \text{ cm}^{-2} \text{ s}^{-1}$

40% efficiency for physics $\rightarrow 10^6$ seconds collisions per month

Integrated luminosity per month = 10 pb^{-1}

- With crossing angle

Could hit few $10^{32} \text{ cm}^{-2} \text{ s}^{-1}$ say $\langle L \rangle$ of $10^{32} \text{ cm}^{-2} \text{ s}^{-1}$

40% efficiency for physics $\rightarrow 10^6$ seconds collisions per month

Integrated luminosity per month = 100 pb^{-1}

Heavy Ion Run

- **Keep option open**
 - **Injectors and LHC should be compatible with the possibility of a HI run**
 - **Note that even 1 day @ early scheme is enough to surpass RHIC**



Parameter	Units	Early Beam	Nominal
Energy per nucleon	TeV	2.76	2.76
Initial ion-ion Luminosity L_0	$\text{cm}^{-2} \text{s}^{-1}$	$\sim 5 \times 10^{25}$	1×10^{27}
No. bunches, k_b		62	592
Minimum bunch spacing	ns	1350	99.8
β^*	m	1.0	0.5 / 0.55
Number of Pb ions/bunch		$7 \cdot 10^7$	$7 \cdot 10^7$
Transv. norm. RMS emittance	μm	1.5	1.5
Longitudinal emittance	eV s/charge	2.5	2.5
Luminosity half-life (1,2,3 expts.)	h	14, 7.5, 5.5	8, 4.5, 3

Only possibility
for 2009 or
early 2010

Heavy Ion Run

- **Systems checked for readiness**
 - RF
 - BI
 - Collimators
 - Vacuum
 - Machine protection
 - Optics (essentially identical magnetic machine)
 - Controls (watch out for hard coded protons)
- **Hot switch strategy**
 - Working LHC with protons
 - Ions available from SPS


Web based procedures being put in place

Stage I	Initial commissioning Early Ion Beam (DRAFT)	Ring factor	Total Time [days]	Comments
I1	Injection and first turn	2	0.25	Magnetically identical to protons; 1 bunch/beam.
I2	Circulating beam	2	0.25	Magnetically identical to protons. Synchronisation of transfer lines and RF capture at -4.7 kHz frequency shift. Check lifetime in particular (IBS?).
I3	450 Z GeV initial commissioning	2	0.25	Beam instrumentation slightly different. Optics OK.
I4	450 Z GeV optics measurements	2	.5	Magnetically identical to protons but do minimal check.
I6	450 Z GeV - two beams	1	.5	>0.4 nominal bunch intensity, otherwise magnetically identical to protons.
I7	Collisions at 450 Z GeV	1	0	Not interesting.
I8	Snapback and ramp	2	0.5	Single and then two beams, Magnetically identical to protons. Check beam dump at various energies.
I9	7 Z TeV flat top checks	2	0.5	Single beam initially, performed following successful ramp
I12	Commission experimental magnets			Included already since done for protons.
I10	Setup for collisions - 7 Z TeV	1	0.5	
	Physics un-squeezed	1	?	Zero crossing angle in ALICE, leave as-is in CMS & ATLAS. LHCb separated.
	TOTAL to first collisions		6	
I11	Commission squeeze	2	2	Commission squeeze of ALICE to same as presently achieved with CMS and ATLAS (with ATLAS and CMS unsqueezed). May have been started with protons. Check separation. Include CMS & ATLAS squeeze depending on time.
I5	Increase intensity	2	1	Increase bunch number to 62 (Early Scheme).
	Set-up physics - partially squeezed.	1	2	
	Pilot physics run			Parasitic measurements during physics (BLMs, ...) of great interest.

Injectors - protons

◆ PROTONS: news in 2008

- Rephasing SPS-LHC → Possibility to extract p beams to LHC
- Low intensity probe beam: 2E9 p/b (instead of 5E9)
- 25 ns (LHC25) and 75 ns (LHC75) beams with intermediate intensities
- Controlled transverse emittance blow-up in SPS
- 2 requests from the LHCCWG held on 13/02/08
 - 1 LHCINDIV + 1 LHCPILOT (at the same time) in SPS
 - 50 ns beam (LHC50)
- Production of the LHC75(50) in 1 batch (instead of 2) into PS



Injectors - ions

- ◆ **IONS: news in 2007 and 2008**
 - Early beam → SPS commissioning in 2007
 - New 18 GHz source in 2008 (instead of 14.5 GHz)
- ◆ **EARLY BEAM:** Several weeks of setting-up and MD time are necessary to make a first LHC ion run possible (~ end of September)
- ◆ **NOMINAL BEAM**
 - Only LEIR made some progress in 2007
 - PS HW needs rebuilding, testing, setting up
 - Alternative filling schemes (to minimize IBS and SC) need to be tested in SPS
 - LHC crystal collimation studies → Many MDs foreseen in 2009
- ◆ *No ions in rings since November 2007 → Recommissioning needed (controls, RF, power supplies, etc.)*

Commissioning – 2008 experience – 3 days of beam

First turn (A.1)

Beam 1

- Commissioning of the last 100 m of the transfer line and the injection
- First commissioning of key beam instrumentation
- Commissioning of the trajectory acquisition and correction
- Threading the beam around the two rings (first turn)
- Closing the orbit

Circulating beam (A.2)

Beam 2

- Establishing closed orbit
- Commissioning of additional instrumentation: BPM intensity acquisition
- Preliminary orbit, tune, coupling and chromaticity adjustments
- Obtaining circulating beam (few thousand turns)
- SPS-LHC energy matching
- Commissioning of RF capture

Initial commissioning at 450 GeV (A.3)

- Commissioning of beam instrumentation
- Improving lifetime
- Rough optics checks
- Initial commissioning of beam dumping system

Detailed measurements at 450 GeV (A.4)

- Beta-beat measurements; initial commissioning of beam dump, ...

Commissioning – 2008 experience – sector tests

Commissioning phase A0 - Sector tests

A0.1 - Commissioning of injection region

Region downstream of TED with TDI closed

Timing synchronization of MKI

SPS-to-LHC timing aspects

A0.2 - Single-pass threading in the LHC

A0.3 - First BPM calibration and optics response matrices

First polarity checks of BPM's and COD's

Timing of BPM acquisitions

A0.4 - First commissioning of additional BI

Screens, BLM's

BCT if possible

A0.5 - SPS/LHC energy synchronization (LHC master)

Dispersion measurements

A0.6 - Aperture measurements

Injection region

Arcs / IR's / dump line


A0.7 - Polarity checks

A0.8 - Beam-induced quench tests

A0.9 - First commissioning of the dump line (Beam 2)





A0.10 - Basic beam checks for collimators (BLM calibr., VAC, temperature, ...)

September 10th would have been VERY different without the sector tests. Beam commissioning speeded up!



We propose to collect these procedures in a dedicated "A0" phase.

Commissioning – 2008 experience – dry runs



Commissioning – 2009

☑ Path to 7 TeV well thought of

First version of procedures finalized before 2008 operation

Used for the (limited) commissioning steps covered by beam operation

*Need to be updated to match the **new baseline commissioning strategy***

☑ We believe that we are ready for the 2009 operation

We know - on paper - how to do what we need to do...

We are more confident than 1 year ago that the tools will be available (dry-tests!)

☑ The machine protection procedures have to be systematically built into the existing procedures

☑ We need to know the scenario for 2009+ operation

Collision energy, β^ , desired bunch filling scheme, collisions at injection, ...*

☑ Will start dry-tests as soon as possible to be ready

... then the beam will tell!

Organisation – 2008 experience

- **Numerous activities**
 - Installation
 - Cool down
 - System integration
 - Dry runs
 - Machine checkout
 - Injection tests
 - Beam commissioning
- **It worked**
 - Thanks to all concerned
- **It was not always easy**
 - Interference between activities
 - Sharing of resources
 - Time pressure

Activities not
always done in
optimal order

Organisation – 2009

- **Lessons can and will be learned**
- **New things will have to be accommodated**
 - **Personnel changes**
 - **Access and powering restrictions**
 - **Machine protection largely untested**
 - **single bunch at injection energy in 2008**
 - **New magnet protection systems**
 - **have to work, have to allow operation**
- **Availability of experts**
 - **Machine protection (definition of safe envelope)**
 - **Magnet protection**
 - **On shift or on call ?**
- **Commissioning team should be involved early on**
 - + **Plenty to do before beam**
 - **Same people in the CCC for a year**