

l r f u

cea

saclay

# EuCARD HFM

## *Task 3 : High Field Magnet*

# Outline

---

I r f u

cea

saclay

- Task content
- Starting point
- What is expected from other tasks
- Future work
  
- Conclusion

## Task content (1/2)

I r f u

cea

saclay

- Design, build and test a **1.5 m long, 100 mm aperture dipole model** with a design field of **13 T** using **Nb3Sn** high current Rutherford cables.
- The **Nb3Sn technologies are to be brought together and tested in short models**. Several of these technologies (superconducting cable, insulation, coil design, support structures) were partly developed during the **FP6-CARE-NED project**.

## Task content (2/2)

I r f u

cea

saclay

- dipole model as a **test bed for large high field accelerator magnets**. A **1.5 m** long dipole model will be build with an aperture of **100 mm** and a design field of **13 T**
- the model will afterwards be used to upgrade the superconducting cable **test facility FRESCA** at CERN from 10 T to **13 T**.
- CEA-DSM and CERN will design together the magnet.
- CERN will do the conductor characterization.
- PWR will lead the thermal design and thermal component tests. CERN and CEA will participate to the task
- CEA-DSM will fabricate the coils and CERN will build the mechanical support structure.
- Combined teams will integrate the coils into the support structure.
- The cryogenic test of the model will be done in the CERN test station

# Starting Point (1/2)



- Part of the development was done during **FP6-CARE-NED project** :
  - The Heat Transfer Measurements Task : A test facility for heat transfer measurements is available
  - Quench computation :
  - Conductor development : 2500 A/mm<sup>2</sup> @4.2K and 12 T are feasible ... but
    - **Only one fabricant**
    - **are 2500 sufficient ?**
    - **Strand diameter (1,25 mm) OK ?**
  - Cable insulation : Polyimide-sized S2 glass fiber tape developed by CCLRC/RAL

# Starting point (2/2)


## Working Group: MDO: dipole concepts

l r f u

cea

saclay

### Concepts studied for future High Field Dipoles



1

# What is expected from other tasks

- Task1 : Coordination and communication:
  - Help in Coordination and communication
- Task 2 : Support studies
  - Even if the model will be used for fresca test facility, the design must be made in view of accelerator magnets → Radiation → **choice of materials** and **Thermal model**.
  - Very early input are necessary (start of model design)
  - Validation could come later (but before start of fabrication)

I r f u

cea

saclay

# What is expected from other tasks

• Task 3 : ...

• Task 4 : Very High Field dipole insert:

- Mechanical interface
- Magnetic coupling
  - Field on Nb<sub>3</sub>Sn Conductor ?
  - Protection

• Other tasks : Nothing

I r f u

cea

saclay



# Future work

I r f u  
cead  
saclay

- Write the model **specification**  
- **Collect** the existing **documentation** for the different possible magnetic configurations

T1

- **Comparative Study** of possible magnetic configurations **adjusted to specification**, **compatibility with conductor development** status

T2, T3

T3

- **Review**

- **Decision** of the magnetic configuration

Conductor must be determined and its feasibility verified

Thermal model = M36

- Start of detailed study

01/01/2010

- finalize **magnetic** design
- **Thermal** and **mechanical** design
- Tooling
- .....

# Conclusions

---

- The task deliverable is identified, but its characteristics must be specified

I r f u

cea

saclay

- Many magnetic configurations are possible. The first step is to choose one

- Some critical points are identified:

- Conductor
- Thermal model
- Radiation resistant material

- A lot of work is to be done .....

..... efficient communication and organisation are necessary