

# SRF cavity tests at CALIFES

CALIFES workshop, 10-12 October 2016, CERN

# Content



01 SRF projects at CERN

02 SRF R&D at CERN

03 Infrastructure needs



# High priority projects


- # Crab Cavities for HL-LHC
- # HIE ISOLDE
- # LHC spare cavities



# High Luminosity LHC

Test of a proof-of-principle cryo module in the SPS

## SPS test prototype



## LHC series production

Fabrication & tests

Preparation & Installation

## LHC pre-series

EYETS 16/17: Main time slot for infrastructure installation


YETS 17/18: Main time slot for cryo-module installation


- **Scope:** test one cryo module in the SPS with beam before LS2.
- **Beam tests in 2018:** i) show that CRAB cavities can be made invincible for the beam, ii) demonstrate crabbing effect.
- Demonstrate cavity and CM technology.


# High Luminosity LHC

Test of a proof-of-principle cryo module in the SPS

- Two double quarter wave (DQW) 400 MHz cavities including couplers, tuners, and all accessories and the complete cryo-module are constructed and assembled at CERN.
- A movable table with 510 mm displacement can move the CM into or out of the beam within 20 min.



 Everything needs to be ready for installation by end of 2017



<b>f</b>	400.8 MHz
<b>V<sub>kick</sub></b>	3.4 MV
<b>R/Q</b>	400 $\Omega$
<b>T</b>	2 K

# High Luminosity LHC

- Crab cavities have been tested on electron machines before (e.g. KEKB)
- No test so far on hadron machines —> interest in SPS test, verify if Crabs can be made invincible for the beam.
- Verify crabbing effect.

What could be done at CALIFES:

- CALIFES 3 GHz vs 400 MHz,
- **single bunch wakefield measurements,**
- advantage not to be bound to SPS operational schedule,
- **CALIFES cannot replace SPS test**
- but still needs the same infrastructure (cryogenics and RF) as in the SPS test stand



# HIE ISOLDE




- 5 QWR + 1 SC solenoid per cryo-module
- CM1 installed in 2015, first physics run in November 2015 (see WEOBA01, J.A. Rodriguez, IPAC16).
- CM2 is installed, first beam in June, physics run from August 2016 (11 weeks).
- CM3 scheduled for installation: 1/2 - 2017, physics run from May 2017 (25 weeks), followed by CM4.

**No scope for any tests at CALIFES**


<b>f</b>	101.3 MHz
<b>E<sub>acc</sub></b>	6 MV/m
<b>Q</b>	$5 \times 10^8$
<b>T</b>	4.5 K



# LHC spare cavities



LHC cryo-module with 4 Nb on Cu, 400 MHz single-cell cavities.



<b>f</b>	400.8 MHz
<b>E<sub>acc</sub></b>	5.5 MV/m
<b>Q</b>	$>2 \times 10^9$
<b>T</b>	4.5 K

- 2 trains of 4 cavities will be produced until mid 2019
- same geometry as original
- known behaviour, **no need for beam tests at CALIFES**





# R&D projects

# FCC


# High Gradient Bulk Nb

# WOW


# FCC cavities

	FCC-hh	Z	Z	W	H	$t\bar{t}$
Beam energy [GeV]	50,000	45.6		80	120	175
Beam current [mA]	0.5	1450		152	30	6.6
Bunches / beam		30180	91500	5260	780	81
Bunch spacing [ns]	25	7.5	2.5	50	400	4000
Bunch population [ $10^{11}$ ]	1.0	1.0	0.33	0.6	0.8	1.7
Crossing angle at IP [mrad]		30				
Bunch length [mm] (total)	300	6.7	3.8	3.1	2.4	2.5
Energy loss / turn [GeV]		0.03		0.33	1.67	7.55
Total RF voltage [GV]	0.032	0.4	0.2	0.8	3	10
RF frequency [MHz]		400				
cells×cavities×beams	1×25×2	1×150×2	1×75×2	2×150×2	2×400×2	2×1340
Luminosity/IP for 2IPs [ $10^{34} \text{ cm}^{-2}\text{s}^{-1}$ ]	5...30	207	89.4	19.1	5.1	1.3
SR power (total) $\approx$ total RF power [MW]	5	100				
Electric power for RF [MW]	$\approx$ 10	$\approx$ 165				
Total cryogenic power [MW]	0.4	2	2	5	23	39

400 MHz single cell



400/800 MHz 2-cell



Designs converge towards 2 cavity types to cover all FCC-ee machines and FCC-hh:

- FCC-hh, Z, W: 400 MHz single cell
- W, H,  $t\bar{t}$ : 400/800 MHz multi-cell (most likely 2-cell)

see O. Brunner, FCC Week Rome 2016



# FCC cavities

## SCRF Cavity Technologies

(CERN-INFN-STFC collaboration)

- surface processing & coating infrastructure for 800 MHz (CERN)
- RF test bench (CERN)
- Seamless 800 MHz cavities (INFN)
- 6 GHz cavities for coating R&D (INFN)
- 400 MHz cavity fabrication techniques (INFN)
- Microscopic and surface characterisation of samples (STFC)

## SCRF Cavity Material and Performance

(CERN, UNIGE, HZB, TUW)

- CU surface preparation,
- DC and AC sample testing,
- RF measurements and diagnostics
- Nb-Cu coatings
- A15 coatings (alternative materials)
- Preparation and test of bulk Nb surfaces


Electro-Hydraulic Forming (development started in the frame of the SPL study)



see E. Cantergiani, FCC Week Rome 2016

- present effort mostly on coating and forming technologies,
- HOM's will be a serious issue,
- **wakefield measurements at CALIFES could help to optimise cavity shapes and to test HOM couplers**

# High gradient 704 MHz module



- Legacy of the SPL study
- Goal: 25 MV/m at  $Q_0=1 \times 10^{10}$
- advance CM design and assembly know-how
- Bulk Nb performance is the reference for comparison with Nb on Cu coatings

- Assembly foreseen for 2018.
- **Beam tests would be interesting.**
- **Module could be used for a small ERL** (CERN management refused to have an 800 MHz ERL test facility at CERN, and now CEA is interested)







# Infrastructure

# RF

# Cryogenics



# Example: RF at 704 MHz




$U_k$	-110 kV
$I_k$	25 A
$P_{\text{pulse}}$	2.6 MW
$f_{\text{rep}}$	1-50 Hz
$Z_k$	4.4 k $\Omega$
$T_{\text{pulse}}/T_{\text{flat-top}}$	1/0.8
droop	1%

- Modulator for one 704 MHz klystron, probably enough for single bunch beam tests with 4 cavities,

- New compact 704 MHz klystron from Thoshiba




# Example: Cryo for SPS Crab Test




**Cold Box & ancillaries**

1.9 m x 2.2 m  
 1.9 m x 1 m  
 plus handling space



**Warm compressor & ancillaries**

2.4 m x 6.1 m  
 2.4 m x 6.1 m  
 plus handling space



**Proximity to CM**

Valve box & service box  
 helium pumps & piping  
 heater  
 plus handling space

**plus Helium storage: 15 m high, 2.5 m in diameter**



# Summary

- Califes would be of limited use for CERN's high-priority SRF projects, (CRAB cavities wake field measurements)
- It would be interesting for some of the low-priority R&D projects (e.g. FCC, WOW crab cavity, high-gradient program, ERL)
- Substantial infrastructure investment needed (RF, cryogenics, local mobile clean rooms for connections)
- Synergies with VELA and CLARA at Daresbury should be explored (SRF infrastructure already in place)

