




Current project Status of SPS Module May 26, 2016

On behalf of WP4

CERN - STFC status and future plans

Super proton
synchrotron (SPS)
Test Prototype
Module(s)

SM18 Area
Cavity cold testing, clean
room facilities & cryomodule
qualification



LHC Point 5 (horizontal)
16 cavities in total

LHC Point 1 (vertical)
16 cavities in total

E540 - V10/09/97


Cavities

Compact design to allow adjacent LHC beam pipe at 194 mm

Baseline : adopt both cavity types and exploit their natural RF topology



Double Quarter Wave (DQW) cavity –
Vertical – to be used in Point 1 (ATLAS)



RF Dipole (RFD) cavity –
Horizontal – to be used in Point 5 (CMS)

Dressed cavities


Double Quarter Wave



- Cavity Review - May 2014, BNL
- HOM Coupler Review - February 2015, JLAB
- Helium Vessel Review - May 2015, CERN


Dressed cavities

RF Dipole




- Cavity Review - May 2014, BNL
- HOM Coupler Review - February 2015, JLAB
- Helium Vessel Review - May 2015, CERN

SPS Cryomodule




- CM Review, Nov 2015 (Basic design choices approved)
- SPS cryomodule DQW developed as 1st priority, RFD will follow

SPS Cryomodule DQW




Revised Planning

- *First Re-Baselining after C&S Review I*
 - *US cavities delayed (+ unresolved “conformity standards”)*
 - *CERN cavity production (DQW) for SPS is adopted as baseline*
- *Impact on SPS is significant*



Plans for DQW SPS-CM



today


Contingency

1st Cryomodule ready for cold test in SM18 (November 2017)



LHC

- LHC layout: 4 “SPS like” cryomodules x 2 cavities each / IP side




Basic choices for the design:

Maximize modularity


Maximize compatibility between SPS and LHC

Standardize the solutions for the 2 types of cavities




Revised Plan, LHC Series





Revised Plan, LHC Series




Example Shaping Simulations




Dwg: LHCACFCA0067




Effective Plastic Strain





Weld Map

16 complex welds to qualify & perform
(with tight tolerances)



WELDING TESTS & QUALIFICATIONS - CRAB CAVITY										DATE: 30/10/15	Issued/Réalise: P.Freijedo & T.Tardy		
Weld N ^o / N ^o soudure & SEQUENCE	Joint identification	Joint configuration	PASS	Dwg's reference / Références plans de détail	Joint Type / Type de joint	Dimension			Proce ss / Procé dé	Sample for Welding tests & Qualification (EN-15614-11) (Configuration & Dimensions)	MATERIAL NEEDED	pWPS /pDMOS Preliminary Description de Mode	REMARKS
						Øint (mm)	Esp. (mm)	Esp.Est ⁱ mé (mm)					
W01			Par l'extérieur cavité: 1er pass: Soudage Par l'intérieur cavité : 2nd pass- Soudage 3th pass- Lissage	LHCACFA0023	BW with full penetration	-	4	4	511- EBW		PLATE 520X520X4 (1 Unit)		
W05			Par l'extérieur cavité: Soudage	LHCACFA0023	BW with full penetration	37,63	3	2	511- EBW		PLATE 520X520X3 (1 Unit)		Thickness to be defined
W04A			Par l'extérieur cavité: 1er pass: Soudage en deux cycles	LHCACFA0023	BW with full penetration	83,7	3		511- EBW		PLATE 520X520X4 (1 Unit)		Thickness to be defined
W04B			Par l'intérieur cavité : 2nd pass- Lissage local interieur										
W08			Par l'extérieur cavité: Soudage	LHCACFA0023	BW with full penetration	37,63	3	3	511- EBW	Already qualified with circular sample for W05			
W06A			Par l'extérieur cavité: Soudage	LHCACFA0023	BW with full penetration	61,67	3		511- EBW		PLATE 520X520X4 (1 Unit)		Thickness to be defined
W06B													
W06C													
W06D													
W07A			Par l'extérieur cavité: Soudage			83,7	3	3	511- EBW				
W07B													
W09A			Par l'extérieur cavité: Soudage	LHCACFA0001	BW with partial penetration			2	511- EBW		NbTi/Nb	Preliminary test performed: 	
W09B													
W09C													
W09D													
W10A													
W10B													
W02A			Par l'intérieur cavité : 1er pass-Soudage 3-Lissage	LHCACFA0023	BW with full penetration	238	4	4-3	511- EBW		PLATE 520X520X4 (3 Units)		Thickness to be defined
W02B			Par l'extérieur cavité: 2-Soudage										
W03A			Par l'extérieur cavité: Soudage	LHCACFA0023	BW with full penetration	398	4	4-3	511- EBW				
W03B													


Difficult Weld

A Sample Weld




Nb-Nb: W03A/B Final ellipsoidal welds :

Welding in 3mm of thickness performed on 1 side.

Two configurations tested: Key (Clé) and BW (Bords droits)






BW



INTERNAL SIDE - RF


KEY



INTERNAL SIDE - RF


BOTH CONFIGURATIONS WITH SATISFACTORY RESULTS

Helium Vessel




Bolted/welded concept was chosen for structural integrity & **minimal stress to cavity**

A dummy prototype was launched for experimental verification of assembly procedure, stress, vacuum integrity and other aspects.




They are now verified

Prototype Helium Vessel



WELDING STEPS


- 1- Vertical welds
- 2- Welds around the top/bottom plate
- 3- Longitudinal Covers
- 4- Circular Covers & Beam pipe



Pressure tests (2.6 bar)

The vacuum levels remained at $\leq 10^{-9}$ mbar (5 thermal cycles)

Tests vs. Simulations




Cavity Stress, cool down

- $\Delta T_{\max} = 40 \text{ K}$ top/bottom of tank (input constraint)


Type: Equivalent (von-Mises) Stress
Unit: MPa
Time: 1
11/05/2016 17:01

22.728 Max
21.104
19.481
17.858
16.234
14.611
12.988
11.364
9.7409
8.1176
6.4942
4.8709
3.2475
1.6242
0.00082859 Min



Type: Temperature
Unit: K
Time: 1
11/05/2016 17:04


295.15 Max
290.71
286.26
281.82
277.37
272.93
268.48
264.04
259.59
255.15 Min




- Stress on cavity is **low** ($\leq 10\%$ of allowable)
- Slower cool-down rate can further reduce if necessary

Cavity Chemistry, DQW & RFD


DQW: Very light chemistry on Parts & Bulk Chemistry on assembled cavity



RFD: Bulk Chemistry on Parts & Light Chemistry on assembled cavity



CERN Setup, Cavity Chemistry (PoP)




General procedure uses acid circulation
between 10 – 15⁰ C (~ 40 min, indicative)

Small tilting for trapped gas removal

Fluid Dynamics for Chemistry

See Talk: T. Jones



→ = Inlet

All other ports outlets

Gravity acts down as shown in images

Analysis	1	2	3	4	5	6
Range (cm/s)	0.63	1.82	0.90	0.65	1.23	0.92
Standard Deviation (cm/s)	0.21	0.40	0.24	0.21	0.26	0.23
Av. Velocity (cm/s)	0.29	0.38	0.33	0.31	0.36	0.28

Data taken for 21 points throughout the cavity for each orientation

Frequency Tracking

See Talk: S. De Silva, S. Verdu


FREQUENCY SHIFTS

Target: 400.79 MHz (-60 kHz)


	Effect	Magnitude	Uncertainty	Unit	Premises under which value was calculated	
Fabrication	Last weld-A shrinkage (assumed ~1 mm)	$\Delta f_{\text{ShrinkWeldA}}$ 980	-490	+980	kHz	Freq shift calculated as expected shrinkage times trim sensitivity. Cumulative freq shift from both shrinkage and sagging of last weld-A will be known after welding the "next-to-last" weld.
	Last weld-A sagging (assumed 0.5mm-deep, 5mm-thick bead)	$\Delta f_{\text{SaggWeldA}}$ -70	-50	+70	kHz	From simulations.
	High-T baking	$\Delta f_{\text{High-T}}$ 0			kHz	
	Low-T baking	$\Delta f_{\text{Low-T}}$ 0			kHz	
	BCP (210 μm)	Δf_{BCP} -170	-50	+50	kHz	Models prepared for CST simulations. Take about ~30% for error due to thickness removal uncertainty and unhomogeneity. Error may be reduced if BCP performed in several iterations and in rotating facility.
Assembly	Couplers and ports (bare cavity --> baseline aseembly of cavity with couplers)	Δf_{C} -89	??	??	kHz	Estimate uncertainty coming from assembly error that will turn into penetration error.
	Test couplers out --> in	Δf_{TestC} 0			kHz	
	Helium vessel mounting and magnetic shield assembly	Δf_{Mount} 0			kHz	
	Welding of helium vessel	$\Delta f_{\text{TankWeld}}$ -150	-116	+416	kHz	Magnitude: form measurement of displacements in dummy tank after welding used as input for ACE3P simulations. Uncertainty: worst-case scenario for tolerance error of ± 0.1 mm.
Setup	Frequency change from air to vacuum	Δf_{e} 133.3			kHz	Formula
	Frequency sensitivity to pressure	$\Delta f_{\text{p}} / P$ -0.103			Hz/mbar	ANSYS-APDL
	Frequency change from 300 K to 2 K	Δf_{T} 573			kHz	ANSYS-APDL
Operation	Lorentz detuning coefficient	$\Delta f_{\text{U}} / (Vt)^2$ -40			Hz/(MV) ²	CST simulation for model including tuning system and vessel.
	LF detuning: RF power off --> on	Δf_{LD} -0.4			kHz	
	Beam loading	Δf_{BL} 0			kHz	Formula

2K Internal Magnetic Shields

Double QW






RF Dipole



- *Internal magnetic shields already integrated by STFC-UK !!*
 - *1 mm Cryophy, annealed after shaping, supported by Ti brackets*
 - *Controls done: dimensions, shielding reduction factor*
 - *At CERN waiting for cavities...*

Comparison of Data and Simulations



- measured 1
- measured 2
- simulated

Nominal input:
Earth field ($\sim 42 \mu\text{T}$)
along beam axis


SPS data taken in
LSS6 zone from YETS

HOM Couplers


See Talk: M. Garlasche

DQW Status




- Niobium pieces & other ancillaries produced
- Final metrology & welding tests ongoing before assembly



RFD material at CERN, fabrication in 2016




HOM Testbox



See Talk: J. Mitchell



HOM Lines

- Optimized for static/dynamic heat loads to 2K
- Coax line for 1 kW, 316LN, Cu sputtered ($5\mu\text{m}$)
- Flexibility using spherical joints & themalization with alumina disk
- Destructive tests for validation 2016



Tuner Tests (on PoP)


See Talk: A. Castilla



Tuner preparation for Cold Tests planned during Jun 2016




- Assembly into SM18_V3 & protection for cooldown actions ongoing
- PLC based control system successfully tested in a feedback loop

Repeatability precision
 $\sim 0.5 \mu\text{m} \sim 100 \text{ Hz}$




Tuning Fixtures

- Warm frequency tuning limited by tuning fixture
- Limiting factor is the strength of NbTi fixture and weld
 - CERN (NbTi), USLARP (Nb with reinforced shape)





DQW Pre-tuning: ≥ 0.3 mm
permanent deformation





RFD: ~ 1.4 mm (7000 kN elastic limit)

Power Coupler

Most FPC parts (+spares) completed



RF Test Box



2 DQW + 2 RFD Couplers by end of May (spares in Oct)


RF Test box ready by Sept. → Clean room assembly in Oct

Two DQW couplers ready April 2017

Cavity Supports & Alignment



Top plate – kinematic mount, option with levelling jacks as vertical supports

Three point alignment which are blocked after
Additional points for rigidity



Position monitoring system (BCAM + FSI)



- BCAM + FSI (1:1) full system mock-up under construction
- Irradiation campaign of reflective targets and collimators finished
- FSI head prototypes designed and under manufacturing
- BCAM → System performance initially validated on the mock-up. Tests and calibration of camera vacuum viewports pending
- Cryogenic tests of reflective targets planned in the next 2 months




- Fiducialisation of the helium tank mock-up on CMM and laboratory verification of full system performance
- FSI head test in operation conditions (vacuum, reflector at 4K)
- Irradiation campaign of FSI heads assemblies
- SM18, SPS - DAQ and data processing software development
- Measurements in SM18 – validation of the final system

Warm Magnetic Shield

- Field measured in SPS and applied to Warm Magnetic Shield
- Gaps between plates induces field leaks, fine tuning





Results with optimal proposed design



Peak B $\leq 5 \mu T$ @extremeties

CM Thermal Shields

- After several studies, Cu chosen as baseline
- Connection between cooling pipe and plates under study
- Design & integration finishing



Result Summary		Pipe Temperature		Pipe Convection	
		T_{\min} (K)	T_{\max} (K)	T_{\min} (K)	T_{\max} (K)
Al/SS	Panels	64	81	70	87
	Pipe	50	105	50	139
Cu	Panels	53	75	55	84
	Pipe	50	70	50	75

CM Cryo-Circuits



Cool down and 2 K normal operation

DQW static HL: 12.5 W


RFD static HL: 12 W

DQW dynamic HL: 18.1 W

RFD dynamic HL: 15.9 W



Thermal screen bayonet interfaces







Vacuum Vessel


- Trapezoidal design for assembly (adopted from Triumph)
- Stainless steel with Al lateral windows (max access)
- Deformation on top must be limited to mitigate misalignments
- Deformation to be limited for vacuum integrity

C: Static Structural No Reinforcements

Figure
Type: Total Deformation
Unit: mm
Time: 1
11/05/2016 16:37





SM18 Clean Room & CM Assembly




SPS-LSS6 Implantation

11.5m overall space, CM installed in a by-pass & motorized transfer table



Multiple Vacuum sectorization to accommodate bypass & module replacement



RF & Cryo on movable table with liquid Helium