

Injector Physics Design

John Schmerge LCLS-II SLAC Director's Review

30 August-1 September, 2016





Outline

- Injector Overview
- Injector Design
 - Beamline layout optimization
 - Beam with temporal laser modulation
 - RF coupler correction
 - Wakefield effect
 - RF jitter requirement
- Commissioning

Parameter	nominal	range
Electron Energy at gun exit (keV)	750	500 - 800
Electron Energy (MeV)	98	90 - 120
Bunch Charge (pC)	100	10 - 300
Bunch Repetition Rate (MHz)	0.62	0 - 0.93
Dark e-current (nA)	0	0 - 400
Peak e- current (A)	12	4 - 50
Average e- current (mA)	0.062	0.0 - 0.3
Normalized slice emittance (rms, µm, 95%)	0.4	0.2 - 0.6
Bunch length (rms, mm)	1	0.3-2
Slice energy spread (rms, keV)	1	1-5
Cathode quantum efficiency (%)	2	0.5 - 10
Laser Energy at cathode (µJ)	0.02	0.0 - 0.3

LCLSII-2.2-PR-0084-R0

CW (1MHz) injector baseline schematic



- Cs₂Te cathode
- UV/IR lasers for cathode/laser heater
- 185.7 MHz NC RF gun
- NC 1.3 GHz 2-cell buncher
- SC 1.3 GHz 8-cavity CM

- LCLSII-2.2-PR-0084-R0
- 2 emittance compensating solenoids with quad correctors
- BPM Diagnostics

LCLS-II Director's Review, 30 August-1 September, 2016

Cs₂Te cathode

- Demonstrated performances at APEX
 - low thermal emittance (0.8 μm/mm)
 - High QE (5-10%)
 - long lifetime (>14 days)
 - < 1ps response</p>
 - < 1nA of low dark current (LCLS-II spec <0.4 μA at 100 MeV)
- Cathodes provided by LBNL/INFN for commissioning
- SLAC to fabricate cathodes for long term operations

Lasers

- Two identical 50 W lasers for photocathode and laser heater
 - 50W IR laser (50 μ J/pulse, 2 ps, 1 MHz) is commercially available
 - Includes oscillator, stretcher, pulse slicer, amplifier, and compressor
 - Award of contract in August 2016
- SLAC laser group will design and build
 - Synchronization system
 - UV conversion
 - Pulse stacker for UV
 - Pulse stretcher for laser heater
 - Spatial shaping
 - Imaging and transport systems
 - Diagnostics and controls

LCLSII-2.2-PR-0086 LCLSII-2.2-PR-0085 FDR was June 2016



RF Gun and Buncher

- 186 MHz CW NC Gun
 - ~19.5MV/m on cathode (80KW)
 - 750keV energy gain

LCLSII-2.3-PR-0166-R0

- 1.3 GHz CW NC buncher
 - 4 rf feeds with 2.5 kW/feed
 - 3X compression

LCLSII-2.3-PR-0167-R0

 Performance of both described in APEX experience talk





CM, Solenoids and BPMs

- 1.3GHz, 8 9-cell cavities standard CM
 - 1 HOM coupler upstream and 1 downstream
 - 1 power coupler downstream
 - 1st cavity ~8MV/m
 - 2nd and 3rd cavity <2-3MV/m for emittance compensation
 - 95 MeV energy at the injector exit
- Two NC solenoids before and after the buncher
 - One pair of weak normal & skew quads per solenoid for correction of field perturbations LCLSII-2.3-PR-0165
- Two stripline BPMs (1pC and 30µm res specification)

LCLSII-2.4-PR-0136

Optimized injector layout

- 2013 layout (CDR): NGLS design
- 2014 layout: added 50cm with non-standard CM endcap
- 2015 layout: added another 21cm with standard endcap
- Final layout: new shorter solenoid, BPM with larger aperture, modified drift between SOL2 and CM, and moved SOL1 closer to cathode



Final layout: emittance vs. bunch length



Final layout: emittance



LCLS-II Director's Review, 30 August-1 September, 2016

Final layout apertures



- SOL/BPM aperture increased 50%
- Laser box aperture increased 60%
- Increased the ratio of the half aperture to rms beam-size from 2.5 to 4

Final layout: longitudinal beam





Elegant code tracking including wake, CSR and LSC with new injector beam (100pC)

With more realistic temporal laser (100 pC)



16-32 laser pulses (4-5 BBO crystals) will be stacked to generate 30-60 ps long pulse



- Emittance increases 0.3%
- High order (>2) δE reduces 2%
- Current profile looks similar

HOM coupler beam perturbation correction

- Emittance growth is dominated by the spatial varying HOM field perturbation for short bunches
- The effect can be effectively corrected with one pair of normal and skew quads
 - <5Gs at SOL2
 - Almost fully corrected for 100pC
 - About 20% emittance growth after the correction for 300pC



Wakefield effect – laser box (worst case)



- Beam parameters:
 - Charge = 300 pC
 - Energy = 865 keV
 - $\sigma_z = 4.5 \text{ mm}$
 - Transverse offset 2mm
- Emittance growth <5% for the very conservative 2mm beam offset



Z. Li

RF stability requirements

	Jitter	Arrival time (fs)
Laser timing	80 fs	48
Gun phase	0.04°	32
Gun amplitude	0.01%	45
Buncher phase	0.015°	43
Buncher amplitude	0.03%	12
Cav1 phase	0.05°	20
Cav1 amplitude	0.03%	17
Total arrival time jitter at 95 MeV (4 GeV- after x100 compression)	-	90 (<1)

Transverse alignment requirements

- Extensive simulations with Astra code show relaxed alignment requirements:
 - Alignment laser position on cathode <100 μ m for <2% of ϵ -growth
 - Solenoid alignment <0.5mm or 2mrad for <2.5% of ε-growth
 - Buncher alignment <1mm or 2mrad for <3% ϵ -growth
 - CM01 alignment <0.6mm or 0.5mrad for <1% ϵ -growth

Injector Commissioning Plan

- SLAC injector group actively participates in APEX commissioning efforts
 - 20 pC measurements in early 2016
 - 100 pC measurements soon
 - Testing/developing tuning strategies/codes
- LCLS-II Injector Source (< 1 MeV) Commissioning
 - Fall 2017 RF processing begins
 - Winter 2018 laser commissioning
 - Spring 2018 commissioning 1-MeV electron beamline
 - Charge, QE, QE life time, and thermal emittance
 - Beam based calibration for the laser, buncher phases, and gun/buncher amplitudes
 - Beam energy and BBA
- Full Injector (100 MeV) Commissioning June 2019
 - CMs are cold and operational
 - 10 Hz beam into diagnostic line

Commissioning Schedule



LCLS-II Director's Review, 30 August-1 September, 2016

Detailed Injector Laser Schedule

Jan Feb Mar Apr May Jun Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Jun Jul Aug <th>Sep Oct No</th>	Sep Oct No
100 Englector Lasers 736 days Tue 7/18/17 St 10/12/19 100 LSS certification 1 day Tue 7/18/17 St 0/18/17 110 Drive Laser 85 days Sat 2/17/18 Sun 5/13/18 111 Laser Synchronization 15 days Sat 2/17/18 Sun 3/4/18 112 IR Pulse-train 10 days Fri 2/23/18 Sun 3/4/18 113 UV voltai table prep at gun 10 days Fri 2/23/18 Sun 3/4/18 114 UV voltai table prep at gun 10 days Fri 2/23/18 Sun 3/4/18 115 UV opticai table prep at gun 10 days Fri 2/23/18 Int 3/2/18 115 UV opticai table setup at gun 10 days Tu 3/2/18 Int 3/2/18 114 UV remoral Shaping 12 days Sat 3/3/18 Int 3/2/18 Int 3/2/18 118 UV opticai table setup at gun 10 days Sht 3/3/18 Int 3/2/18 Int 5/23/18 Int 5/23/18 Int 5/23/18 Int 5/23/18 In	
100 LSS Certification 1 day Tue 7/18/17 Tue 7/18/17 111 Laser Synchronization 15 days Sat 2/17/18 Sun 3/4/18 111 Laser Synchronization 15 days Sat 2/17/18 Sun 3/4/18 112 IR Pulse-train 5 days Sat 2/17/18 Thu 2/22/18 Sat 3/3/18 113 "UV 37 days Fri 2/23/18 Sun 3/4/18 I 114 UV Pulse-train 10 days Fri 2/23/18 Sun 3/4/18 I 115 UV Ortal table pere at gun 10 days Fri 2/23/18 Sun 3/4/18 I 115 UV Ortansport Unine S days Sat 3/10/18 Mon 3/19/18 I 117 UV Spatial Shaping 12 days Sat 3/18 Sat 3/3/18 I 118 UV Temsport Unine S days Sat 3/3/18 Sat 3/3/18 I 118 UV Spatial Shaping 12 days Sat 3/3/18 Sat 3/3/18 I 122 Laser Characterization 28 days Mon 5/14/18 Sat 7/7/18 I 123 I Reater Laser Sat days Mon 5/14/18	
110 \frown Drive Laser 85 days Sat 2/17/18 Sun 3/1/18 111 Laser Synchronization 15 days Sat 2/17/18 Sun 3/4/18 Image: Sun 3/4/18 112 IR Pulse-train 5 days Sat 3/1/18 Sun 3/4/18 Image: Sun 3/4/18 113 \Box UV 37 days Fri 2/23/18 Sun 3/4/18 Image: S	
111 Laser Synchronization 15 days Sat 2/17/18 Sun 3/4/18 4 112 IR Pulse-train 5 days Sat 2/17/18 Sat 3/1/18 1 113 = UV 37 days Fri 2/23/18 Sat 3/1/18 1 114 UV Pulse-train 10 days Fri 2/23/18 Sun 3/4/18 1 115 UV optical table prep at gun 10 days Fri 2/23/18 Sun 3/4/18 1 115 UV optical table prep at gun 10 days Fri 2/23/18 Sun 3/4/18 1 116 UV Transport Line 5 days Mon 3/5/18 1 1 117 UV Soptial Shaping 10 days Sat 3/1/18 1 118 UV Tremsport Line 5 days Mon 3/5/18 1 120 DRIVE LASER TTO 0 days Sat 3/1/18 1 121 Diagnostics/EPICS/Controls 15 days Mon 5/1/18 1 1 122 Laser Characterization 25 days Mon 5/1/18 1 1 123 F Heater Laser 5 days Mon 5/1/18 1 1	
112 IR Pulse-train 5 days Sat 2/17/18 Thu 2/22/18 1 113 IV 37 days Fri 2/23/18 Sat 3/31/18 1 114 UV Pulse-train 10 days Fri 2/23/18 Sun 3/4/18 1 115 UV optical table prep at gun 10 days Fri 2/23/18 Sun 3/4/18 1 115 UV Optical table prep at gun 10 days Fri 2/23/18 Sun 3/4/18 1 116 UV Temporal Shaping 10 days Sat 3/10/18 Mon 3/3/18 1 118 UV Temporal Shaping 10 days Sat 3/31/18 Sat 3/31/18 1 120 DRIVE LASER TTO 0 days Sat 3/31/18 Sat 3/31/18 1 121 Diagnostics/EPICS/Control 15 days Mon 5/14/18 Sat 7/17/18 1 122 Laser Characterization 28 days Mon 5/14/18 Sat 5/19/18 1 123 IR Pulse-train 5 days Mon 5/14/18 Sat 5/23/18 1 124 Laser Synchronization 15 days Sat 5/19/18 Ved 5/23/18 1 125 IR Pul	
113	
114 UV Pulse-train 10 days Fit 2/23/18 Sun 3/4/18 1 115 UV voltical table prep at gun 10 days Fit 2/23/18 Sun 3/4/18 1 115 UV Transport Line 5 days Mon 3/5/18 Fit 3/23/18 Sun 3/4/18 1 117 UV Spatial Shaping 10 days Sat 3/10/18 Mon 3/19/18 1 118 UV Temporal Shaping 12 days Sat 3/10/18 Wed 3/22/18 1 119 UV optical table setup at gun 10 days Fit 3/23/18 Sat 3/31/18 1 120 DBRIVE LASER TTO 0 days Sat 3/31/18 1 1 122 Laser Characterization 28 days Mon 5/14/18 Sun 5/13/18 1 123 Fit Relater Laser Sat days Mon 5/14/18 Sat 7/7/18 1 124 Laser Synchronization 15 days Sat 5/19/18 1 1 125 IR Pulse-train 5 days Sat 5/19/18 1 1 126 Temporal Shaping 5 days Sat 7/7/18 1 127 IR Transport <td< td=""><td></td></td<>	
115 UV optical table prep at gun 10 days Fri 2/23/18 Sun 3/4/18 1 116 UV Transport Line 5 days Mon 3/5/18 Fri 3/9/18 1 117 UV Spatial Shaping 10 days Sat3/10/18 Ved 3/21/18 1 118 UV Temporal Shaping 10 days Sat3/31/18 1 119 UV optical table setup at gun 10 days Sat3/31/18 1 120 DRIVE LASER TTO 0 days Sat3/31/18 1 121 Diagnostics/EPICS/Controls 15 days Sun 4/1/18 Sun 4/1/18 1 122 Laser Characterization 12 days Sat 3/31/18 1 1 122 Laser Characterization 15 days Mon 5/14/18 Tue 5/23/18 1 123 IR Pulse-train 5 days Sat 5/19/18 1 1 124 Laser Characterization 15 days Sat 5/18 1 125 IR Pulse-train 5 days Sat 5/19/18 1 126 Temporal Shaping 5 days Sat 5/19/18 1 127 IR Transp	
116 UV Transport Line 5 days Mon 3/5/18 Fri 3/9/18 1 117 UV Spatial Shaping 10 days Sat 3/10/18 Mon 3/19/18 1 118 UV Temporal Shaping 12 days Sat 3/10/18 Mon 3/19/18 1 119 UV optical table setup at gun 10 days Sat 3/11/18 Sat 3/31/18 1 120 DRIVE LASER TTO 0 days Sat 3/31/18 Sat 3/31/18 1 121 Diagnostics/EPICS/Controls 15 days Sun 4/1/18 Sun 4/1/18 Sun 4/1/18 1 122 Laser Characterization 28 days Mon 5/14/18 Sun 5/13/18 1 1 123 F Heater Laser S3 days Mon 5/14/18 Tue 5/29/18 1 1 124 Laser Synchronization 15 days Sat 5/19/18 Wed 5/23/18 1 1 125 IR Pulse-train S days Sat 5/19/18 Wed 5/23/18 1 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 1 127 Diagnostits/EPICS/Controls 10 days	
117 UV Spatial Shaping 10 days Sat 3/10/18 Mon 3/19/18 1 118 UV Temporal Shaping 12 days Sat 3/10/18 Wed 3/21/18 1 119 UV optical table setup at gu 10 days Thu 3/22/18 Sat 3/31/18 1 120 DRINE LASER TTO 0 days Sat 3/31/18 Sat 3/31/18 1 121 Diagnostics/EPICS/Controls 15 days Sun 4/1/18 Sun 4/15/18 1 122 Laser Characterization 28 days Mon 5/14/18 Sat 7/7/18 1 123 F Heater Laser Sad days Mon 5/14/18 Tu 2/5/2/18 1 124 Laser Synchronization 15 days Mon 5/14/18 Tu 2/5/2/18 1 125 IR Pulse-train 5 days Sat 5/19/18 Wed 5/2/2/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/2/2/18 1 127 IR Transport 5 days Sat 6/9/18 Sat 7/7/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 1 130 Laser Character	
118 UV Temporal Shaping 12 days Sat 3/10/18 Wed 3/21/18 1 119 UV optical table setup at gun 10 days Thu 3/22/18 Sat 3/31/18 1 120 DRIVE LASER TTO 0 days Sat 3/31/18 1 121 Diagnostics/EPICS/Controls 15 days Sun 4/1/18 Sat 3/31/18 1 122 Laser Characterization 28 days Mon 5/14/18 Sat 7/7/18 1 123 F Heater Laser Sat 3/s Mon 5/14/18 Tue 5/29/18 1 124 Laser Synchronization 15 days Mon 5/14/18 Tue 5/29/18 1 125 IR Pulse-train 5 days Sat 5/19/18 Wed 5/23/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 6/9/18 Sat 7/7/18 1 128 HEATER LASER TTO O days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 7/7/18	
119 UV optical table setup at gun 10 days Thu 3/22/18 Sat 3/31/18 1 120 DRIVE LASER TTO 0 days Sat 3/31/18 1 121 Diagnostics/EPICS/Controls 15 days Sun 4/15/18 1 122 Laser Characterization 28 days Mon 5/14/18 Sun 4/15/18 1 122 Laser Synchronization 15 days Mon 5/14/18 Tue 5/29/18 1 124 Laser Synchronization 15 days Mon 5/14/18 Tue 5/29/18 1 125 IR Pulse-train 5 days Sat 5/19/18 Wed 5/23/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO O days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 7/7/18 1 131 Optimize Drive/Heater Laser 40 days Mon 5/14/18 Tue 8/13/19 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18	
120 DRIVE LASER TTO 0 days Sat 3/31/18 Sat 3/31/18 1 121 Diagnostics/EPICS/Controls 15 days Sun 4/1/18 Sun 4/15/18 1 122 Laser Characterization 28 days Mon 4/16/18 Sun 5/13/18 1 123 ² Heater Laser S3 days Mon 5/14/18 sat 7/7/18 1 124 Laser Synchronization 15 days Mon 5/14/18 Tue 5/29/18 1 125 IR Pulse-train 5 days Mon 5/14/18 Tue 5/29/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO O days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 ² Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 1 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
121 Diagnostics/EPICS/Controls 15 days Sun 4/1/18 Sun 4/1/18 Sun 4/15/18 1 122 Laser Characterization 28 days Mon 4/16/18 Sun 5/13/18 1 123 Image: Heater Laser S3 days Mon 5/14/18 Sut 7/7/18 1 124 Laser Synchronization 15 days Mon 5/14/18 Sut 7/7/18 1 125 IR Pulse-train 5 days Mon 5/14/18 Tue 5/29/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
122 Laser Characterization 28 days Mon 4/16/18 Sun 5/13/18 1 123 ⁻ Heater Laser 53 days Mon 5/14/18 Sat 7/7.18 1 124 Laser Synchronization 15 days Mon 5/14/18 Tue 5/29/18 1 125 IR Pulse-train 5 days Mon 5/14/18 Tue 5/29/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
123 Beater Laser 53 days Mon 5/14/18 Sat 7/7/18 124 Laser Synchronization 15 days Mon 5/14/18 Tue 5/29/18 1 125 IR Pulse-train 5 days Mon 5/14/18 Tue 5/29/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 5/19/18 Tue 8/13/19 131 Coptimize Drive/Heater Laser 400 days Mon 5/14/18 Tue 8/13/19 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
124 Laser Synchronization 15 days Mon 5/14/18 Tue 5/29/18 1 125 IR Pulse-train 5 days Mon 5/14/18 Fri 5/18/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/1/18 1 131 ^{CD} Optimize Drive/Heater Laser 400 days Mon 5/14/18 Tue 8/13/19 1 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
125 IR Pulse-train 5 days Mon 5/14/18 Fri 5/18/18 1 126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 © Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 1 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
126 Temporal Shaping 5 days Sat 5/19/18 Wed 5/23/18 1 127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 © Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 1 132 Environmental stability 90 days Mon 5/14/18 1	
127 IR Transport 5 days Sat 5/19/18 Wed 5/23/18 1 128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/23/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 © Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 1 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
128 HEATER LASER TTO 0 days Wed 5/23/18 1 129 Diagnostics/EPICS/Controls 10 days Wed 5/30/18 Fri 6/8/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 © Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 1 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
129 Diagnostics/EPICS/Controls 10 days Wed 5/30/18 Fri 6/8/18 1 130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 © Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18	
130 Laser Characterization 28 days Sat 6/9/18 Sat 7/7/18 1 131 © Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 • 132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
131 © Optimize Drive/Heater Laser 440 days Mon 5/14/18 Tue 8/13/19 Image: Control of the stability Tue 8/13/19 Image: Control of the stability Image: Contro	
132 Environmental stability 90 days Mon 5/14/18 Mon 8/13/18 1	
133 Spatial Profile 20 days Tue 8/14/18 Sun 9/2/18 1	
134 Temporal Profile 60 days Tue 9/4/18 Fri 11/2/18 1	
135 Beam pointing stabilization 90 days Sat 11/3/18 Thu 2/14/19 1	
136 Rep Rate flexibility 90 days Fri 2/15/19 Wed 5/15/19 1	
137 Pulse energy 90 days Thu 5/16/19 Tue 8/13/19 1	
138 Spare Laser 60 days Wed 8/14/19 Sat 10/12/19	
139 Commission spare laser 30 days Wed 8/14/19 Thu 9/12/19 1	— 1
140 Commission hot swaps 30 days Fri 9/13/19 Sat 10/12/19 1	*

Detailed Injector Source Schedule

	Task Name 🗸 🖕	Duration 🖕	Start 🖕	Finish 🖕	Predecessors	3rd Quarter		4th Quarter		1st Quarter		2r	nd Quarter		3rd Qu	arter		4th Q	uarter		1st Q	uarter	
	+					Jul Au	g Sep	D Oct Nov	/ Dec	Jan Feb	Ma	r /	Apr May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
142	Injector Source	297 days	Thu 9/14/17	Sat 8/25/18		-																	
143	Pre-Beam	85 days	Thu 9/14/17	Mon 1/22/18																			
144	ARR	3 days	Thu 9/14/17	Mon 9/18/17	7FS-60 days		40		1														
145	Pre-Beam Checkout	7 days	Mon 12/11/17	Wed 1/3/18	7				Ě	h													
146	PPS/BCS Certification	3 days	Thu 1/4/18	Sat 1/6/18	145					ň													
147	LLRF/SSA	1 day	Sun 1/7/18	Sun 1/7/18	146					ĥ													
148	Gun/buncher Processing	14 days	Mon 1/8/18	Mon 1/22/18	147					Δh 👘													
149	Dark Current Characterization	44 days	Tue 1/23/18	Thu 3/8/18								h											
150	Dark Current I	19 days	Tue 1/23/18	Sat 2/10/18	148					Č.													
151	Survey	1 day	Tue 1/23/18	Tue 1/23/18	150SS					4													
152	Install Collimator	4 days	Sun 2/11/18	Wed 2/14/18	150					័													
153	Controls Checkout	2 days	Thu 2/15/18	Fri 2/16/18	152					Ť.	1												
154	BL Components Operational	2 days	Thu 2/15/18	Fri 2/16/18	153FF					P	J												
155	Dark Current II	21 days	Thu 2/15/18	Thu 3/8/18	152					č													
156	Initial Photo-Beam	15 days	Sat 3/31/18	Sun 4/15/18									թյ										
157	First Photoelectrons	0 days	Sat 3/31/18	Sat 3/31/18	149,120							₩ ¶	3/31										
158	Low Energy E-beam	15 days	Sun 4/1/18	Sun 4/15/18	157							ſſ	.										
159	MPS/BCS checkout	2 days	Sun 4/1/18	Mon 4/2/18	158SS							h											
160	Survey	1 day	Sun 4/15/18	Sun 4/15/18	158FF		N −																
161	INJECTOR TTO	0 days	Sun 4/15/18	Sun 4/15/18	156							կ	4/1 5										
162	Cathode characterization	30 days	Mon 4/16/18	Tue 5/15/18	161								Ť,										
163	E-beam alignment	30 days	Wed 5/16/18	Fri 6/15/18	162									_									
164	E-beam optimization	30 days	Sat 6/16/18	Mon 7/16/18	163									Ľ	_								
165	CW RF thermal management	14 days	Tue 7/17/18	Mon 7/30/18	164											հ							
166	Dark Current III	21 days	Tue 7/31/18	Mon 8/20/18	165											Շ							
167	Remove temporary dump/diagnostics	5 days	Tue 8/21/18	Sat 8/25/18	166											ð							
168	Infant mortality	120 days	Mon 4/16/18	Wed 8/15/18	161								Ċ.										

Summary

- Injector beamline is well optimized
 - Exit emittance is close to the thermal emittance
- Imperfections from laser, RF couplers, wakefields, jitter and alignment have been evaluated and/or mitigated.
- Started to prepare for early commissioning in FY18
 - SLAC team has actively participated in the APEX commissioning
 - Beam tuning (RF phase/amplitude calibration and BBA) procedure is developed
 - Will develop the related HLA software

Early commissioning (1MeV)

- No energy spectrometer is available for the RF gun/buncher phase/amplitude calibration and energy measurement
 - But keep space for future adding a dipole
- Have to use existing devices (ICT, YAG screen, BPMs, correctors and solenoids) for:
 - Calibration of the gun/buncher phase and amplitude
 - Beam energy measurements
- Laser phase calibration
 - Gun phase is fixed, similar to LCLS1
 - Scan the charge (w/ ICT) vs.
 laser phase to determine zerocrossing laser phase w.r.t. RF



Buncher phase calibration for zero-crossing phase:

- Beam energy with buncher's zero-crossing phase ≈ gun energy
 ⇒ zero-crossing phase determined
- Zero-crossing bunching: larger beam size at YAG screen
- Zero-crossing debunching: smaller beam size at YAG



LCLS-II Director's Review, 30 August-1 September, 2016

Gun & buncher amplitude is calibrated with the beam energy measurement:

- Using a weak corrector: measure the slope of x-offset at YAG screen/BPM2 vs. a corrector strength ⇒ may resolve ~10keV energy
- And/or using a solenoid



LCLS-II Director's Review, 30 August-1 September, 2016

Alignment for laser position on cathode:

- Cathode plug is aligned well with the gun
- Usually only central 5mm of the cathode center is doped with Cs for electron emission
- QE mapping ⇒ boundary of the central 5mm ⇒ cathode center
- Can align <100μm according to APEX experience
 - Emittance growth <2%

Using the solenoid matrix, offset at the entrance of the solenoid can be estimated via measuring beam offset at BPM or YAG screen

- Can be aligned < 50 μ m and <0.5mrad
- Emittance growth negligible



BBA for buncher

- Set buncher to debunching zero-crossing
 - Eliminated the effect of dispersion due to the stray fields (zero-crossing)
 - Smaller beam size (extra focusing from debunching phase)
- Turn on SOL1 and adjust its strength to focus the beam at YAG
- Correct the offset using pairs of correctors xc01/02 measuring difference of centroid beam at YAG for buncher on/off
 - <100µm emittance growth negligible

