


HLS and WPS at SLAC

Georg Gassner, Franz Peters, Robert Ruland
SLAC, Metrology


- WPS and HLS at the BABAR detector (decommissioned system)**
- HLS in SPEAR3 (22 sensors)**
- WPS and HLS in LCLS undulator hall (136 HLS and 99 WPS)**

- System contained 6 HLS sensors and ~6 WPS sensors from (~2002-2008) to monitor relative positions of magnets and detector
 - HLS
 - First generation BINP sensors,
 - serial data communication
 - Insufficient protection of sensor surface from water
 - Pipe:
 - 30 m pipes
 - 1 and 1 ½ inch copper pipes, copper works as a anti algae but copper oxidation flakes off
 - WPS
 - Inductive sensors (Wei Wang, Zack Wolf, LCLS-TN-05-27).


- WPS (Wei Wang, Zack Wolf, LCLS-TN-05-27).
 - Sensors contain magnetic sensors and an integrated lock-in amplifier.
 - 40 kHz Signal on copper beryllium wire
 - Vertical and horizontal pickup
 - DC signal analyzed at a data acquisition rack
 - Resolution <1 micrometer




- System contains 22 HLS sensors (in various configurations since 2005)
 - Third generation BINP sensors,
 - TCP/IP
 - Power over Ethernet
 - Sensor calibration at SLAC
 - 300 m circumference
 - 2 inch PVC pipe throughout




Latest results




- BL7 U
- BL7 D
- BL10 U
- BL10 D
- BL9 U
- BL9 D
- BL12-2 U / E Pit
- BL12-2 D / E Pit
- BL12-2 M0 mirror
- BL12-2 mono
- BL12-2 M1/M2 mirrors
- BL6 U
- BL6 D
- BL6 M0 mirror
- BL11 U
- BL11 D
- BL13 U
- BL13 D
- WPit U
- WPit D



- Stable temperature
 - <math><0.5\text{ degC}</math>
- Low Radiation
- Stability over 1 week period
- Relative motion over 140 m distance better than <math><2\ \mu\text{m}</math>




- HLS
 - 103 capacitive
 - 33 ultrasound
 - Refill station
- WPS
 - RF inductive




- 102 Capacitive sensors BINP
 - Precision $< 1 \mu\text{m}$
 - Instrument Drift $\sim 1\text{-}2 \mu\text{m} / \text{month}$
 - Accuracy $< 0.1 \%$ of full Scale
 - PoE Ethernet connection
 - Calibrated at SLAC
- 33 Ultrasound sensors
 - Precision $< 0.1 \mu\text{m}$
 - Instrument Drift potentially no drift
 - Accuracy $< 0.1 \%$ of full Scale
 - Transducer GE Inspection Technology
 - Electronic Box BINP
- Common
 - Moving Range $\pm 2.5 \text{ mm}$
 - Availability: 10 minutes settling period after movement
- 2 inch CPVC pipe, half filled, 140 m long, 10 min damping time


10 Days of Hydro Leveling System readouts - the tide effect -



10 Days of vertical girder positions by HLS - tide effect eliminated -




Snap shot: Vertical girder positions after 7 days of tracking with HLS




DESY development for the SLAC FFTB experiment (1991 – 1993)
 Since 2002 adaptation for LCLS by Franz Peters

WPM at girder



Function principle




■ 140 RF sensors


- Resolution < 100 nm in X & Y Direction
- Instrument Drift < 100 nm per day
- Moving Range ± 1.5 mm in X & Y Direction
- Accuracy 0.1 % of full Scale
- Availability Permanent, no Interrupts


■ Wire


- 140 m gold plated stainless steel wire
- 140 mm wire sag (30kg tension)
- Transverse harmonic frequency of the 138 m wire 1.36 Hz (0.73 sec)
- Wire oscillation, due to surrounding vibrations up to ~ 10 Micrometer
- High resolution needs averaging about 5 to 10 periods 7.3 Sec / Monitor





Horizontal wire position readouts - highly correlated -














■ HLS:

- Third generation capacitive sensors (BINP):
 - Electronics in sensor head
 - Reliable
 - Drift < 2 μm / week
- Ultrasound sensors (BINP)
 - Electronics not at the sensor
 - Not as reliable (5 out of 33 transducer needed to be replaced so far)
 - In theory no drift

■ WPM

- Inductive System (Wei, Wolf)
 - Electronics next to pick up
- RF inductive system
 - Very low drift < 1 μm / week
 - No electronics at the sensor itself
 - Max length of 200 m