


Status of the MICE RF System

The MICE RF team

Headline update



• Distribution network

- Adapted from components procured under NSF-MRI for earlier configuration
- Contractor identified, trial section modified
 - Modified component returned- quality of work high
 - Workshop viewed as qualified
 - Less expensive and faster than further procurement

• Status of RF drive system


- Upgraded triode modulator No.1 operational at Daresbury
- Triode No. 2 under test, started mid March
 - Exploiting 1st tetrode, and upgraded No. 1 modulator racks
 - Triode achieved 1MW using ex-ISIS valve (close to limit of valve)
- Interface channels for RF controls defined

• Muon-RF phase determination

- Subsample method with Fourier domain signal reconstruction
- Accurately rebuilding signals from MTA experiments
- Digitisation hardware is on order
- RF discriminator delivered, currently under test at Strathclyde


MICE High Power RF system: Requirements

- MICE High Power RF system – Likely requirements have evolved
 - Two cavities, driven by ONE RF power amplifier- 2MW output
 - In place of two separate 2MW RF systems
 - Estimated gradient decreases from 10.3 MV/m to 7.2 MV/m
 - Allowing for realistic LLRF overhead and losses
 - 1st Amplifier proven and installed @ RAL(triode stage remains installed)
 - Cavity proving complete @ MTA
 - At much higher gradients
 - Cavity performance risk enormously mitigated
 - Cavity construction in hand @ LBNL




MICE High Power RF system: Requirements



- MICE High Power RF system – Likely requirements have evolved
 - Two cavities, driven by ONE RF power amplifier- 2MW output
 - In place of two separate 2MW RF systems
 - Lower gradient means less risk/lower cost at cost of reduced p_z uplift
 - Not without its own issues
 - No longer have electronic control of relative phase
 - Either predefined fixed phase setting or increments by mechanical adjustment of the transmission lines
 - Alternative: Quote received \$25k US for 1.5m trombone phase shifter
 - Note: Means we lose control of the impedance presented at the amplifier



RF Distribution Network




- Must Support 2MW in 6" line and 500 kW in 4" line with full reflect
 - 4" lines rated to 1.12MW at 1 atmosphere in dry air
 - Therefore will be pressurised by N₂ (with slow ramp) or SF₆ or gas
 - Will be treated as pressure vessels
 - Some of the 6" and 4" line from the NSF MRI procurement will be modified
 - All components/devices will be drawn from the NSF procured stock
 - Calibration components procured
 - Distribution network assembly at Daresbury advanced
 - A Grant, A Muir, N Rimmer




RF Drive System

- 1st triode modulator upgraded with solid state crowbar
- Crowbar bench test previously reported
- Now tested up to 35kV (maximum intended operating voltage) in triode modulator
 - Coupled to the triode amplifier
- C White, S Griffiths & Daresbury Team




RF Drive Systems



- 1st Modulator set and Tetrode recommissioned at Darebury
- 2nd Triode now under proving tests
 - 1MW achieved using ex ISIS triode valve at 25kV
 - η : 57%, Gain: 8.6 dB, Tetrode: 136kW, η : 52%, Gain: 19 dB
 - Triode input return loss 11.5 dB
 - At MICE duty and pulse duration
- A Moss, T Stanley, C White, S Alsari, K Ronald, M Popovic, N Rimmer

RF Drive System



- Glitches observed in modulator current traces when Tetrode operates above 50 kW output
- Completely independent of RF output tuning of tetrode, triode, bias voltages on triode
- Maps to modulation of output signal of both triode and tetrode
- Does not happen when tetrode drives resistive load at MUCH higher power
 - Structure is very regular- suggested possible switching power supplies
 - Further tests with Daresbury EE eliminated this possibility- to be resumed

RF Drive System



- **First Amplifier Chain**

- Has delivered required 2MW at Daresbury test stand
- Installed and commissioned at RAL autumn 2013- delivered 500kW
- Output (triode) stage remains installed at RAL
- Modulators and preamplifiers returned to Daresbury
 - **Crowbar upgraded**
- Preamplifier recommissioned at Daresbury
 - **Includes modification to the input circuit- improves reliability**
 - **Delivered 220kW**


- **Second amplifier chain**

- Output stage complete and under test
- Second tetrode amplifier mechanically complete
- Solid state power amplifier tested
- Components for second modulator under construction
- **C White et al, Daresbury**
- ISIS Injector team working on upgrade to tetrode screen grid modulator



LLRF Control System

- LLRF hardware development with effort from ISIS Injector RF team
 - Bob Anderson, ISIS Linac RF Team
- Selection of clock and operation frequency refined
 - Hardware under test- prototype batch of filters delivered
 - Next batch of filters will be slightly refined, leading to order for production filters
 - Required for both MICE and ISIS LLRF future requirements
 - Block diagram of system shown
 - Imminent test on ISIS debuncher



RF Controls and Monitoring Systems




- A channel list and state machine has been defined for the RF amplifier controls
- T Stanley, A Kurup, S Alsari, K Ronald
 - Enable the build of the controls hardware at Daresbury- Underway by Daresbury Electrical Engineering (Chris White)
 - Also defines the logical interaction with the system states
 - Software development now underway: associating channels with variables for EPICS control
- Considering RF feedback model to keep cavities on tune:
 - Estimate correct gain for feedback loop to tuners to hold cavity on frequency
 - Plan to use measurement of reflection amplitude after several hundred microseconds
 - Arrange feedback loop to minimise this indicator
 - Dynamics: Cavity is 227 kg copper thermal mass,
 - Dissipated energy is $< 2\text{kJ/pulse}$,
 - Tuning rate vs cavity body temperature = about -6 kHz/C ,
 - Water must be supplied at precisely regulated temperature,
- Note: At the MTA it has been shown the cavity can be held on resonance with feedback
 - Even in the face of a substantial thermal walk in the coolant system
 - $\sim 1\text{kHz}$ in $\sim 150\text{s}$ compensated by variation in pressure in tuners

RF Controls and Monitoring Systems



- Overview of RF monitoring parameters


- NI hardware being developed at Daresbury to implement monitoring
- For reasons of speed and cost will use relatively simple but well characterised rectifiers rather than power meters for most measurements
- Envelope detectors and wide dynamic range log detectors on each measurement port
- K Dumbell & A Moss




RF Controls and Monitoring Systems



- Relative RF phase set by LLRF feedback- helpful to have independent analogue validation
 - Special quadrature phase detector being developed
 - Ensure accurate measurement over entire RF relative phase range
 - NI subsystem will communicate to EPICS via well known routines







Muon Transit Phase Detection

- Need to be able to select particles for analysis by their RF transit phase
 - Allows the 'bundling' of particles for coherent analysis
 - i.e. As if we are considering the interactions of a real particle 'bunch'
- Cavity transit time inferred by the ToF transit time and the tracker measurement of momentum
 - Combining ToF resolution and Momentum projection resolution $\sim \pm 51.5\text{ps}$
 - Desire to know RF phase to better than 0.3 of this $\sim 17\text{ps}$
- Two Approaches
 - Digitisation (subsampling) of the RF waveform on the pickup probes
 - Direct recording of the wave inside the cavity
 - TDC recording of the RF waveform
 - Records zero crossings of a reference oscillator/Cavity waveform - provides RF phase reference for TDC particle events
 - [Alex Dick has been working on this](#)


Muon Transit Phase Detection





- Time domain: signal (blue) from FNAL cavity tests - 500µs window sampled at 5G.Sa/sec
- Subsample (red) at 12.5M.Sa/sec, reduce data by x400, and $48x < Nyquist @ 200MHz$
- Note time domain signal 'windowed': New data from MTA will remove this process
- Freq. domain: Red fft of entire recorded data, Blue enhanced dft of subsampled data



Muon Transit Phase Detection



- Freq. domain reconstructions: high fidelity to raw signal over entire pulse duration (no spark)
- **Blue** is original data through 1MHz Butterworth filter, **Red** is reconstructed subsample data
- Note dft is effectively a (hard edged) 100kHz filter
- 10ps precision achieved on arbitrary pulses from MTA test- various dft widths analysed
- Further test on additional MTA data in different conditions also look promising




- Digitiser is in hand: CAEN V1760 VME unit
- Will need to synchronise digitiser trigger with TDC's TRST signal- discussion with CAEN suggests several routes

Muon Transit Phase Detection



- Studied variation in mean offset phase delay as a function of dFT linewidth
- Note- in spite of 'enhancements' in the dFT resolution we only analyse a tiny fraction of the spectrum
- Likewise iFT back only needs to be a few RF cycles


Average Phase Difference for different Linewidths of dFT



Muon Transit Phase Detection




- Hardware for TDC method now available
- 4 Ch. 300 MHz leading edge discriminator (Philips 704D) on test at Strathclyde
- Non-updating, gate on a single period on RF wave, use output to trigger second discriminator channel and use that to veto the discriminator- select 1 in 17 or so events
- Detail setting of trigger levels critical to edge stability



Muon Transit Phase Detection



- Hardware for TDC method now available
- 4 Ch. 300 MHz leading edge discriminator (Philips 704D) on test at Strathclyde
- Some variation in edge alignment to understand- filtration may help detail jitter
 - Oscilloscope is 20 GHz!
 - Big offsets may be related to jitter in veto'ing
- Offset variation on different records (see different colours being investigated- perhaps thermal)



RF Cavities: Proving Tests

MICE production cavity: Tests underway at MTA

- Using production couplers, spring – summer 2016
- Installation verifies much easier tuning expected for revised design
 - Tuned to 2% of critical coupling, arms balanced to 1%
 - Opportunity taken to inspect cavity
 - No evidence of sparks
- Couplers and cavity continue to behave as expected under high power
 - MTA tests continue to provide critical data to Strathclyde for Muon timing diagnostics
- Cavity room frequency centre frequency adjusted by Al spacing rings
 - Brings f_0 201.3MHz (from 200.8MHz). Tuning range +300/-400kHz
- MICE RF hugely derisked- Excellent work of Y Torun and team at MTA



Summary



- **Distribution Network**
 - Capacity for modification of line lengths validated
 - Ready to modify other lengths of co-axial line as required
 - Calibration components ordered
 - Primary distribution network elements assembled and on hangers
- **Power Amplifier tests Ongoing**
 - Input structure of first tetrode improved, tetrode proven at 220kW
 - 2nd Triode completed trials underway (> 1MW achieved)
 - Second SSPA proven at MICE duty
- **LLRF**
 - Frequencies for the clock and RF refined
 - Filters designed- 2nd refined batch built
 - ISIS variation of the prototype is to be tested imminently
- **Diagnostics, controls, monitoring and feedback**
 - Channel list defined- allows hardware fabrication and software development
 - Hardware for monitoring system outlines, procurement underway, will interface to EPICS
 - Subsample diagnostic has required performance and minimises mathematics,
 - Hardware for TDC diagnostic under test
 - Hardware for Digitiser approach delivered
- **Major capital expenditure realised (esp if we stop at one amplifier), remaining are:**
 - Completion of control hardware and software/diagnostics
 - Installation