

DAQ Update - CM45


Y. Karadzhov

UNIGE - DPNC

July 28, 2016


Prescaled Trigger for MICE

Aimed to measure the particle transmission efficiency of the MICE Cooling channel



A trigger can be generated by TOF0, TOF1 or TOF2.

Prescaled Trigger for MICE




Trigger logic simulation

In this example:

The simulated spill includes 81 events of different types.

Different configurations of the logic will be tested against this input (always the same)


Input of the simulation



Breakdown of the input events:


- TOF0 only - 52 event.
- TOF0 and TOF1 - 16 event.
- TOF0, TOF1 and TOF2 - 8 event.
- TOF1 only - 4 event.
- TOF2 only - 1 event.

TOF1 Trigger (the most simple case)



28 Particle triggers.

TOF1 Trigger Prescaled (scale factor 4)



- Events, being filtered by the prescaler.
- Events, being considered by the trigger logic.


7 Particle triggers. But be careful - when you measure 7 Prescaled Particle triggers, this does not mean that the real number of triggers is 28 (25, 26 or 27 will do the same).

TOF0 OR TOF1 Prescaled (TOF0 scale factor 4)



41 Particle triggers.

TOF0 OR TOF1 OR TOF2 Prescaled (TOF0 scale factor 10, TOF1 scale factor 3)



24 Particle triggers.

Debugging with beam.

A bug has been found in the new version of the firmware of the trigger.
The issue is described here:


<https://micewww.pp.rl.ac.uk/elog/Shift+summary/126>

- The problem was discovered by the shift crew.
- I wasn't able to provide a quick fix, I decided to roll-back to the old version of the firmware.

Debugging with beam.

Run 7981 taken with the old version of the trigger firmware - expected behaviour:


TOF hits per spill



Debugging with beam.

Run 7980 taken with the new version of the trigger firmware - unexpected behaviour:

TOF hits per spill



Debugging with beam.

- The reason for this unexpected behaviour is not clear yet.
- I am not able to reproduce it in the simulation of the logic of the trigger.
- I will need at least 1/2 day beam time dedicated only for the debugging of the trigger in order to investigate the problem.

Tracker Hall Probes

- The readout of the hall probes is recorded in the binary data stream.
- This is implemented using the DATE \leftrightarrow Epics interface.
- We must be very careful - a malfunction of one or more probes will cause a DAQ error and will stop the run automatically.
- The problem can be worked around by removing the corresponding PV from the configuration file of the DATE \leftrightarrow Epics interface (this is what we do right now).
- However, such a modification needs to be very well documented and taken into account when interpreting the binary data.

Conclusion

- A new version of the Trigger firmware which includes prescalers has been developed.
- The prescaled trigger logic will introduce additional level of complexity in the reconstruction of the raw data, therefore this modification has to be well motivated.
- Although the new firmware was fully simulated, a bug has been found during the operation with beam.
- At the moment we use the old firmware and an additional debugging with beam will be needed before migrating to the new version.
- The readout of the hall probes is recorded in the binary data.
- We need to decide what to do in the case of a malfunction of one ore more probes.