



Crab Cavities: CERN Program for SPS Tests

HL-LHC WP4, CERN

6th HL-LHC Collaboration Meeting, Nov 14-16

Special thanks to EN-MME/INT, RF-PM/SRF, TE-CRG/VSC, USLARP, UK-STFC




~10 Years Ago

PROCEEDINGS LHC-LUMI-06

Third [CARE-HHH-APD](#) Workshop

Towards a Roadmap for the Upgrade of the LHC and GSI
Accelerator Complex



IR Upgrade II

R. Tomas, [Crab Cavity IR Optics Design with \$Q=8\$ mrad](#)

R. Calaga, R. Tomas, F. Zimmermann, [Crab Cavity Option for LHC IR Upgrade](#)


J. Tuckmantel, [Technological Aspects of Crab Cavities](#)

The first ideas on LHC crab cavities emerged... at that time we were discussing about voltages & crossing angles in excess of 200 MV and 8 mrad!

Today we are a bit more humble

Reminder, Basic Parameters

- Voltage = **3.4 MV /cavity** (2 cavities /beam /IP side) – 16 total
- Frequency = 400.79 MHz
- $Q_{ext} = 5 \times 10^5$, $Q_0 \approx 10^{10}$
- RF power source = 80 kW (SPS \leq 40 kW)
- Cavity tuning = ± 100 kHz (LFD \sim 0.5 kHz)
- Operating temperature = 2.0 K




Impact of (Cost & Schedule) Reviews

- *SPS Tests*
 - *SPS-LSS6 dedicated test stand for beam tests in 2018*
 - *Integration almost complete, installation starts in 2 months*
- *LHC*
 - *½ system (16 cavities) as a new baseline*
 - *New production strategy with industry starting 2017*
 - *UK pre-series cryostat & US contribution (10 RFD dressed Cav)*
 - *RF power infrastructure reduction to 40 kW-CW (80 kW peak)*


WP4 Planning

SPS prototype beam tests



2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026
	Run 2			LS2		Run 3			LS3		Run 4


LHC pre-series




LHC series production & Installation (8 CMs)




SPS Test Setup




LHC Installation




SPS Tests Program – Weekly Schedule



Missing 12 days




Prototype Cryomodules



Vertical crossing for ATLAS,
first one to go to SPS 2018

Horizontal crossing for CMS
Cavities starting 2017




SPS Cavities, 2K Volume

DQW



RFD




280 mm

Bulk Nb cavities, Dipolar symmetry

$$V_T = 3.4 \text{ MV} (E_p, B_p \leq 40 \text{ MV/m}, 70 \text{ mT})$$

Stored energy $\sim 10 - 12 \text{ J}$

CERN insourced DQW production
Nov 2015



281 mm

Manufacturing Status


Before starting on crabs

Today



Cavity Status

- First CERN cavity frequency trimming in 1 week




Cavity I cold test mid-Feb 2017 (Cavity 2 in early March)

USLARP & KEK Progress

3-piece assembly before surface treatment

RF Dipole



Known non-conformities in fabrication
not possible to test in SPS

However, wealth of information
obtained from assembly

3-piece assembly during, trim tuning




DQW

KEK e-polishing setup



Dressed Cavities (2K volume)



Main Mechanical interfaces:

He-vessel: Bolted-welded concept

Cold magnetic shield

Tuner: Sym. tuning with warm actuation

Three point support + alignment system

Main RF interfaces



1 FPC: Single ceramic coaxial line

3 HOMs: Two stage filter, coaxial

1 PU: Cu-Nb for field probe + HOM

Similar concept for RFD with different HOM interfaces

Prototype He Vessel, Manufacturing R&D




Internal magnetic shield
(UK contribution)


Successful pressure, vacuum & magnetic tests done

Mock-up Tuner Tests, SM18


Tuner Mock up tests in performed in Jul 2016



Extremely good results from the vertical tests in SM18, frequency resolution well below the specification of 100 Hz



Higher Order Mode Couplers, DQW




6+2 HOM couplers machined, final welding in process
RFD couplers will follow immediately after



HOM-RF Lines

- Internal RF transmission lines for HOM extraction
- Test setup for destructive testing well beyond the 1 kW-CW specification




RF line high power
destructive test setup




Fundamental Power Coupler

- Input power of 40 kW CW (80 kW peak)
- Four couplers fabricated and ready for testing




FPC test-box



Cu-SS sputtering for FPC outer conductor




4 FPCs assembled in vacuum



SPS RF Power





- Inductive Output Tube (IOT) as baseline solution for SPS & LHC
 - IOT Cubicle 60 kW-CW at 400 MHz validated
 - Parallel SSA solution under study as a possible compact/cheaper option in future



- Integration of the LHC type circulators & loads completed and procured.
 - Will also serve as spares for LHC

RF Integration (WP15-WP4)



The space reserved for full installation (32 HPRF)

- Cores, all built in LS3 even if not use
- Larger UA/Faraday Cage to allow space for HPRF, HV transformers and CV equipment

SPS LLRF

- Strong synergy with the Linac4 design
 - Identical VME crates (installed in SM18), Self-excited loop test early 2017 + Tuner driven tests Spring 2017
 - Re-use Linac4 modules after changing a few passive components to optimize to the new RF frequency
 - CC: RF @ 400.8 MHz, LO @ 375.75 MHz, IF @ 25.05 MHz sampled with ADC clocked @ 100.2 Msps
- Some modifications required in the firmware (CW vs. pulsed, MIMO feedback, Self-Excited Loop option) and in the FESA classes - ongoing

Standard CO-supplied CPU with timing card (CTRV/P)

Custom-designed RF VME crate

Crate Management module (same as LHC and L4)


Clock Distributor module. Generates the harmonically related LO and ADC clocks. Adapted from L4

Color-coded Status:

Available

FESA class needed

New firmware and FESA class needed





Cavity Loop module (RF feedback). Firmware being modified. Fesa class to be written

Switch and Limit module. Receives the RF power intlk. (adapted from L4)

Tuner module. Firmware ready for test in SM18. Fesa class to be written

RF “Slow” System, PLC

- RF power system & tuner/table motor control, Fast interlocks
- Expert /Operator user interfaces
- Most of the LINAC4 infrastructure is used as the basis for the SPS-Crab Cavity tests






SM18 Activities

- Insourcing cavity production new tooling in SM18 for cavity preparation, treatment & assembly

HPR facility upgrade	Operational
Clean room tools & procedures (Reviewed last month)	Coherent plan and clear methodology. Review advised reinforced coordination, organisational plan, identify additional resources, bottom-up methods via training & tests on mock-ups.
Vertical cryostats for single cavity test	1 insert operational, 1 insert in assembly
LLRF & Controls	Development & test on PoP cavity Nov16
Infrastructure in M7 Bunker	New cabling & vacuum equipment
Cryo distribution	IT DO-30148 purchase procedure launched Oct16



SM18 Assembly & Testing





Clean Room (ISO4/5)
String Assembly

CM Vertically
mounted on Top Plate

CM Bunker Testing




SPS infrastructure



Surface Prep (YETS15-16)	BA6 cleared, uncabing tunnel
Integration	Finalized EYETS16-17,
Cryogenic distribution	Contract placed, phase1 in EYETS16-17
Infrastructure	Pipework, cables, handling rails: installation in EYETS16-17
Transfer Table	MS at Spec committee, Tech. Spec in final stages
Cryogenic Refrigeration	Offers received, LoI asked to confirm delivery end of 2017

Cryogenics architecture

View of SPS tunnel
~40 m underground



TE-CRG

Some Final Comments

- A new paradigm on SC compact deflecting cavities will soon be validated with the highest energy protons for the first time in the world
- There is an intense level of activity on many fronts
 - USLARP & UK collaborations were an integral part w/o which it SPS tests be impossible
- The design choices for the CM & RF services (after many iterations) are robust. We have validated most important elements by prototyping (cavity, tuner, He-vessel...)



Thank you
(mainly to those behind the scenes)

And also to some curious visitors from Paris



Need for SPS Tests

- Operation of such type of cavities in high current and high energy CW (proton) circular machines has never been done!
- Injection, capture, acceleration where the cavities are carefully counter-phased (transparency) and re-phased during collisions. Ultra-precise control of cavity voltage and phase guarantee the preservation of beam quality throughout the cycle.
- Guarantee the operation of cavities with a trip rate significantly below the LHC availability. To validate this in SPS is pre-requisite both with and w/o beam.
- Unlike electrons, there are many aspects (emittance growth, machine protection, RF non-linearity, instabilities) where proton beam tests are the only conclusive answer.

CCTC II for SPS Preparation

- Technical CM Coordination, bi-weekly
 - **System Integration Workflow** : location, team, duration, tools, tests
 - Reviews of specific activities (clean room) and items (FPC, tuner)
- Procurement of Vessel for Cryomodule launched – on track
- Production of cavities and auxiliaries – on track

System Integration Workflow :


<https://edms.cern.ch/document/1703245/9>

ID	Activity	Location	Team	Start	End	Notes	Category	Team	Phase	Start	End	Duration		
14	Cavity inspection	112	base cavity	Marco		NO tests	Daily finalisation, inspection and metrology	Marco	SHOULD	0	0	11		
14	Leak test	112											2	0
15	RF frequency	72	base cavity	Rama									1	0
16	Alternative Tuning	72	base cavity	Marco									0	0
17	RF frequency	72	base cavity	Rama					8	0				
18	Metrology	72	base cavity	Marco, Mateusz		Finalizing metrology measurement of the electric cavity, visual inspection					0			
19	Mount handling frame	72	base cavity + frame	Marco		Frame for handling				1	0			
20	Cleaning + Heavy BCP	8022 + 8118	base cavity + frame	Leonel		both ending speed is been speed (July to September)				15	1			
21	RF frequency, with pressure for used tests	72	base cavity + frame	Rama, Adrien						1	1			
22	Alternative Tuning	72	base cavity + frame	Marco						5	0	56.5		
23	RF frequency	72	base cavity + frame	Rama						3	0			
24	Metrology	72	base cavity + frame	Marco, Mateusz						1.5	0			
25	Cleaning	8022	base cavity + frame	Leonel						2	0			
26	Heat treatment	8053	base cavity	Leonel		To be defined depending on HT tests				5	0			
27	Light BCP	8118	base cavity + frame	Leonel						3	1			
28	RF Vessel Rinsing	SM18	base cavity + frame	Alicia						1	0			
29	Assembly base cavity	SM18	clean room	Alicia						1	0			
30	Transfer cavity to mount	SM18	base cavity + frame	Alicia		Frame for supporting the cavity during BCP test				1	0			
31	Balance	SM18	base cavity + frame	Alicia						2	0	24		
32	Coil Mount	SM18	base cavity + frame	Alicia						2	0			
33	Warmup	SM18	base cavity + frame	Alicia						4	0			
34	Removal of test parameters and preparation for transport	SM18	clean room	Alicia						1	0			


Crab Cavity Technical Coordination: <https://indico.cern.ch/category/8048/>

SPS Installation – EYETS planning

- Space Reservation request and description of the future test stand
- Main Activities
 - Cryogenic distribution line TL
 - Cable installation (30km purchased)
 - New vacuum layout
 - New handling equipment
 - New supporting structures in BA6
- ECR for underground areas are issued
- Safety review (Hazards & LSA), layout of the ODH and other safety alarms



Schedule series




Infrastructure needed at CERN (existing):

- One BCP stand
- One thermal treatment furnace
- Two vertical tests stands (one for bare and one for dressed cavities)
- One clean room string assembly zone (SM18)
- One cryomodule assembly zone (SM18)
- One cryomodule cold test stand in bunker (SM18)

Cavity Tuning & Control

- Motorized control using concentric Ti-Cylinders + tuning frame to symmetrically deform the cavity
- A CERN standard controller board driven via ethernet to adjust the position with input from LLRF.

The tuner control with LLRF feedback to be tested in Spring 2017



An example of 6 motor controller for HIE-Isolde tuning system