

LARP

MQXF status and plans

Paolo Ferracin and Giorgio Ambrosio
on behalf of the MQXF collaboration

6th HL-LHC Collaboration Meeting
14-16 November 2016
Paris

Acknowledgments

- CERN

- A. Ballarino, H. Bajas, M. Bajko, B. Bordini, J.C. Perez, S. Izquierdo Bermudez, P. Fessia, C. Fichera, P. Grosclaude, M. Guinchard, P. Hagen, F. Lackner, H. Prin, E. Rochepault, S. Sequeira Tavares, E. Todesco, G. Vallone

- BNL

- M. Anerella, A. Ghosh, J. Muratore, J. Schmalzle, P. Wanderer

- FNAL

- G. Ambrosio, R. Bossert, G. Chlachidze, L. Cooley, E. Holik, S. Krave, F. Nobrega, I. Novitsky, S. Stoynev, T. Strauss, M. Yu,

- LBNL

- D. Cheng, D.R. Dietderich, R. Hafalia, M. Marchevsky, H. Pan, I. Pong, E. Ravaoli, G. Sabbi, X. Wang

- CEA Saclay

- H. Felice

- LASA

- V. Marinozzi, M. Sorbi

- Tampere University of Technology

- T. Salmi


Outline

- Short model program
- LARP prototype program
- CERN prototype program

Short model program

Coil fabrication


- 1st generation coils: **13**
 - CERN: **7**
 - 1 Cu and 1 low-grade
 - 3 RRP 132/169 and 2 PIT
 - LARP: **6**
 - All RRP 108/127
- Available for test: **9**
- **1** tested in MQXFSM1
 - Coil 2
- **4** tested in MQXFS1
 - 103,104,3,5
- **4** to be tested in MQXFS2
 - 102 (splice issue)
 - 201- 202 (low J_c and RRR)
 - Coil 6



Short model program

Coil fabrication

- 2st generation coils: **17** planned
 - CERN: **11**
 - RRP: 3, 132/169 and 1, 108/127
 - PIT 5 (no barrier) and 2 (barrier)
 - LARP: **6**
 - RRP 3, 132/169 + 2, 144/169 +1, 108/127
- **Proposal**: 2 LARP coils fabricated by CERN with LARP components
- Available for test: **17**
- **4** tested in MQXFS3
 - 105,106,107,7
- **4** to be tested in MQXFS5
 - 203,204,205,206
- **4** to be tested in MQXFS4
 - 9,108,109,110
- **4** to be tested in MQXFS6
 - 207,208,209,8



Short model program

Coil fabrication


- Summary
 - **22** coils fabricated from early 2014
 - **14** by CERN
 - **8** by LARP
 - **8** coils to be fabricated by end of 2017
 - **6** by CERN
 - **2** by LARP
 - Total
 - **30** coils

Short model program

Magnets status

- **MQXFSM1**

- Tested at FNAL in May 2015
- Coil **2**
- **Successfully demonstrated** coil & parts design, and coil fabrication process





Short model program

Magnets status

• MQXFS1a

- Tested at FNAL in April 2016 with coils **3,5,103,104**
- Demonstrated **temperature margin** and **excellent memory**
- Exceeded **ultimate current**
- Quenches distributed on the pole turn
 - Training was stopped to increase azimuthal preload





Short model program

Magnets status

- **MQXFS1b**

- Re-loaded at LBNL in summer 2016
- Azimuthal coil pre-load increased by **20 MPa**
 - From **80 to 100 MPa**
- Shift of pole **strain plateau**
- Axial pre-load unchanged, still $\frac{1}{2}$ of e.m. force (1.2 MN)
 - Same approach in HQ (but with 0.8 MN)




Short model program

Magnets status

• MQXFS1b

- Again, **good memory**
- Stably **above ultimate**
 - Only 1 quench below
- **87%** of I_{ss} at **1.9 K**
- **95%** of I_{ss} at **4.5 K**
- **Slower** training than MQXFS1a
- Quenches in the **ends**





Short model program

Magnets status

- **MQXFS3**

- Tested at CERN in October 2016 with coils **105,106,107,7**
- Same **azimuthal pre-load** as MQXFS1b
- Similar **axial pre-load** as MQXFS1b
 - $\frac{1}{2}$ of e.m. force (1.2 MN)





Short model program

Magnets status

• MQXFS3

- At nominal in 7 quenches
- Training mainly in the ends and coil 105
- Detraining after quench 19 and plateau in coil 7
- Full recovery after high ramp-rate quenches
 - **81%** of I_{ss} at **1.9 K** and about **89%** of I_{ss} at **4.5 K**





Short model program

Magnets status

MQXFS1b vs. MQXFS3


- Very **similar** axial and azimuthal **pre-load**
 - wrt MQXFS1, same axial, +20 MPa azimuthal
- Similar training** slope
 - Although at different current level
 - ...but 1b not virgin
 - Slower than MQXFS1a
- Similar quench** locations
 - End region, I3I4 segment



Short model program

Plans for MQXFS1 and MQXFS3 (I)

- **Analysis** in progress
 - More detailed analysis with **quench antenna** in MQXFS1b
 - Adjusted quench antenna to pinpoint quench locations
 - Comparison of **HQ03 and MQXF** pre-loading levels
 - **Strain gauges** measurements
 - Pole strain plateau levels
 - **Finite element model**
 - Ratio between axial load and e.m. forces
 - Contact pressure between coil and end parts
 - Model of the LE
 - Check for differences between MQXFS1a/1b/3a




Short model program

Plans for MQXFS1 and MQXFS3 (II)


- **MQXFS3b**

- Retest with **axial pre-load increased**
 - Pre-load increased by about a factor two at cold last Friday
 - No need of disassembly
- Insertion of a **new quench antenna** with 40 mm long coils
- Test expected in December 2016

MQXFS3: Longitudinal Loading




MQXFS3 Longitudinal Loading



Short model program

Plans for MQXFS1 and MQXFS3 (III)

- **MQXFS3c**
 - Full disassembly and coil visual inspection
 - Reassembly and re-loading with higher azimuthal pre-stress
 - Depending on 3b test and visual inspection
- **MQXFS1c** (currently stainless steel shell test)
 - Increase of axial pre-load under consideration



Short model program


Upcoming tests (I)

- **MQXFS5**

- Test of four PIT coils (203,204,205,206) with 2nd generation cable design
 - Strand without bundle barrier

- **MQXFS3d**

- Stainless steel shells test



Short model program


Upcoming tests (II)

• MQXFS2

- Test of 3 non conform 1st generation coils
 - 102 (RRP, splice issue), 201-203 (PIT, low J_c and RRR)
 - Together with coil 6

• MQXFS6

- Test of PIT strand with bundle barrier (208,209)
 - Together 207 (PIT no barrier) and 108 (RRP)





Short model program

Upcoming tests (III)

• MQXFS4

- Second RRP 2nd generation magnet, as S3
 - **Reproducibility**
- Test of **pole/mid-plane shims** to correct allowed harmonics
- 1st test of **laminated structure** by LARP




Short model program Summary

- **MQXFS1**
 - LARP 3: 108/127, first generation cable
 - LARP 5: 108/127, first generation cable
 - CERN 103: 132/169, first generation cable
 - CERN 104: 132/169, first generation cable
- **MQXFS2**
 - LARP 6: 108/127, first generation cable
 - CERN 102: 132/169, first generation cable
 - CERN 201: PIT 192, first generation cable
 - CERN 202: PIT 192, first generation cable
- **MQXFS3**
 - LARP 7: 108/127, second generation cable
 - CERN 105: 132/169, second generation cable
 - CERN 106: 132/169, second generation cable
 - CERN 107: 132/169, second generation cable
- **MQXFS4**
 - LARP 9: 144/169, second generation cable, with shift for field quality adjustment
 - CERN 108: RRP 108/127, second generation cable, with shift for field quality adjustment
 - CERN 109: 132/169, second generation cable, with shift for field quality adjustment
 - CERN 110: 132/169, second generation cable, with shift for field quality adjustment
- **MQXFS5**
 - CERN 203: PIT 192, second generation cable
 - CERN 204: PIT 192, second generation cable
 - CERN 205: PIT 192, second generation cable
 - CERN 206: PIT 192, second generation cable
- **MQXFS6**
 - CERN 207: PIT 192, second generation cable
 - CERN 208: PIT 192 (with barrier), second generation cable
 - CERN 209: PIT 192, (with barrier) second generation cable
 - LARP 8: 144/169, second generation cable

Short model program

Plan for tests


- Test schedule defined relying on
 - **CERN CLUSTER D** station available in 2017 for MQXFS by ~Feb.
 - **FNAL test facility** (MQXFS4)
- Also, 3.5 structures available and 2 trained teams for assembly and loading



Short model program

Field quality

- Good prediction of effect of **corrective strategies**
 - Magnetic shims
 - Coil shims during coil pack assembly to compensate for coil size differences
- **Saturation effect** well reproduced
- Still, field errors mainly due to differences in **coil size**
 - To be pointed out: **MQXFS5** is the only model with 4 coils with the same strand, cable, parts, and fabricated in the same lab



Short model program

Quench protection

- MQXFS1 tests confirmed strategy and validated **outer layer heater** simulations
 - Very good agreement with outer Layer heaters data
 - Inner layer delays are longer than in simulations
- MQXFS3
 - Outer layer heaters perform as expected.
 - Two inner layer heater strips were lost. Investigations needed to understand the source of the problems.
 - Quench integral studies indicate that the heaters effectively quench the magnet.
- CLIC test in progress in MQXFS1b

Outline


- Short model program
- **LARP prototype program**
- CERN prototype program

LARP prototype program

Coil fabrication


- Coils for practice & mirror: **2** coil, 4-m long, completed
 - Coil 01 for mirror (1st generation cable)
 - Coil 01b practice (1st generation cable)
- Coils for MQXFA1: **4** coils, 4-m long, ~completed
 - Coil 02 (1st generation cable)
 - Coil 03,04,05 (2nd generation cable)

- **12** Coils for MQXFA2-3 & for practice of BNL W&C line (4.2 m long)
 - **9** W&C at FNAL
 - 6 R&I at FNAL
 - 3 R&I at BNL
 - **3** W&C, R&I at BNL



LARP prototype program

Coil fabrication



LARP prototype program

Coil test

- **MQXFPM1**


- Vertical Test Facility @ BNL commissioned in September-October 2016
- Test results at 1.9 K
 - **First quench:** 14387 A, **65%** of I_{ss} (22.1 kA)
 - Outer layer mid-plane block
 - **Second quench:** 16040 A, **73%** of I_{ss}
 - Inner layer pole turn straight section
- Replacement of IGBT blown at discharge of quench 2 in progress
- Training resuming this week



LARP prototype program

Prototype plans

- **MQXFA1** (4 m long)
 - Test in summer 2017 with coils **02,03,04,05**
- **MQXFA2** (4.2 m long)
 - Test in early 2018
- **MQXFA3** (4.2 m long)
 - Test in early 2019
- **Prototype cold mass**: end of 2019, early 2020



LARP prototype program

Support structure

- **MQXFA1** structure
 - All parts by early December, mech. model in January
- **MQXFA2** structure
 - Procurement cycle has started.



- **MQXFA3** structure
 - Under discussion: procurement of thin laminations
 - possibly provided by CERN (exchange with other parts)
 - In the meantime, practice with MQXFS4


Outline

- Short model program
- LARP prototype program
- **CERN prototype program**

CERN prototype program

Coil fabrication

- **2** coils with Cu cable and **1** with low grade Nb₃Sn **wound and cured**
 - 4th coil with low grade Nb₃Sn being wound
- **1** Cu coil **reacted**
 - 10 m long oven site acceptance test passed
- **1** Cu coil being **prep for impregnation**
- Then, **6** RRP and **6** PIT coils to be produced



CERN prototype program


Coil fabrication



CERN prototype program

Prototype plans


- **MQXFB mechanical test**
 - Cool-down of cold-mass with practice coils by end 2017
- **MQXFB1**
 - Test by end 2018
- **MQXFB2**
 - Test in mid 2019



CERN prototype program


Prototype plans

- Support structure for **MQXFB mechanical test and MQXFB1** expected by March 2017
- Material for components for **MQXFB2** procured




Additional items addressed since last CM (I)

- **Stainless steel shell**
 - Further finite element analysis
 - General agreement to set as a tension target after welding 50 ± 50 MPa



- **Connection box and powering scheme**
 - Two different connection box designs but same coil sequence
 - eP1-i-iP4e-iP2e-eP3i



Additional items addressed since last CM (II)

- **Voltage withstand levels**

- Agreement on the values to be met for the acceptance of a MQXF cold mass


By F. Rodriguez Mateos

Circuit Element	Expected Vmax [V]	V hi-pot	I hi-pot [μ A]	Minimum time duration [s]
Coil to Ground at RT *	n.a.	3 kV	10	30
Coil to Quench Heater at RT *	n.a.	3 kV	10	30
Coil to Ground at cold **	520	1.5 kV	10	30
Coil to Quench Heater at cold **	900	2.3 kV	10	30

* Room Temperature conditions refer to air at 20 ± 3 °C and relative humidity lower than 60%

** Cold conditions refer to nominal cryogenic conditions (superfluid helium)

And finally, series production



Appendix

Schedule Q2 series

- Coil fabrication
 - 75-80 days per coil
 - 1 coil every 3 weeks (winding 3 weeks, reaction 3 weeks)
 - 50 coils fabricated in 4 years
- Cryo-assemblies
 - About 1 year from coil-pack assembly to “ready for installation”
 - 3 cryo-assemblies per year
 - Imposed by time required to fabricate 5 coils
 - 10 cryo-assemblies fabricated in 4.5 years

