



**Associated Cryogenics for HL-LHC project**

**2<sup>nd</sup> HiLumi Industry Day – October 31<sup>st</sup> 2016**

Laurent Delprat – CERN





CERN – 2<sup>nd</sup> HiLumi Industry Day – October 31<sup>st</sup> 2016 – IST Lisbon

# OUTLOOK

- Main sub-systems concerned (to be cooled)
- The Cryogenic part of it
- Concluding remarks

# HL-LHC configuration

HL-LHC



HL-LHC systems are entering detailed integration phase


New baseline adopted to increase operating margins (Nb3Sn quadrupoles)

In-kind contribution and Collaborations for HW design and prototypes

# Cold Powering System HTS links


- Design and construction of test station with 20 m long SC Link cryostat (CERN)
- Development of MgB<sub>2</sub> round wire (CERN with Columbus – Genova)
- Development of high-current (20 kA) MgB<sub>2</sub> cables (CERN)
- Launched procurement of 80 km of MgB<sub>2</sub> round wire - which will be delivered as from April 2015

MgB<sub>2</sub> Wire  
( $\Phi = 0.9$  mm)



MgB<sub>2</sub> Cables

$\Phi = 19.5$  mm



I=20 kA @ 24 K



L= 20 m



Excellent results obtained for elementary part of the cable

Global engineering (termination boxes, supporting) under study




# Effect of the crab-cavities

*To compensate for the larger crossing angle*




Double 1/4-wave:  
Coaxial couplers with  
hook-type antenna



# OUTLOOK

- Main sub-systems concerned (to be cooled)
- The Cryogenic part of it
- Concluding remarks

# HL-LHC Cryo Upgrade




- Existing cryoplant
- New HL-LHC cryoplant

- 2 new cryoplants ( $\sim 18$  kW @ 4.5 K incl.  $\sim 3$  kW @ 1.8 K) at P1 and P5 for high-luminosity insertions
- 1 new cryoplant ( $\sim 4$  kW @ 4.5 K) at P4 for SRF cryomodules. (Alternative under study: upgrade of 1 existing LHC cryoplant and distribution)
- 11T + Q5@P6
- SRF test facility with beam at SPS-BA6 primarily for Crab-Cavities

*SM18 related activities not reported here*

# New insertions at P1 & P5

- HTS SC link
- Cryogenic distribution line
- Warm recovery line
- Warm piping
- LTS SC link



Hi-Lumi LHC

Ground level


Shaft

CCB Cavern

×

Q1 Q2

Upgrade layout



Nominal layout

- Cryogenics for new cryo-assemblies (Crab cavities (CC), insertion cryomagnets, DFBs, HTS links...)
- 1 warm compressor station (WCS) in noise insulated surface building
- 1 upper cold box (UCB) in surface building
- 1 cold quench buffer (QV) in surface
- 1 or 2 cold compressor boxes (CCB) in underground cavern
- 2 main cryogenic distribution lines
- 2 interconnection valve boxes with existing QRL (partial redundancy)

18kW@4.5K incl. 3kW@1.8K  
(integrated - mixed cycle)  
And lines, vessels, ...






# Technical Infrastructures at P5



SU Ventilation units



Building sizes and interfaces defined by integration studies of similar equipment and plants existing at CERN



SU chillers & pumping stations



SD He refrigerator



SF cooling towers



SHM Helium compressor station




New surface buildings, shafts and caverns to be constructed, to accommodate for new Hardware to be installed



# Size of underground structures (e.g. US/UW cavern)


Size defined by integration and transport studies of similar equipment existing at CERN



Cooling & ventilation

Safe room

Transformers



Ventilation & smoke-extraction ducts


Cold box

# New insertion at P4

Cooling capacity revised (decreased!) + staggered in time

6kW => 3kW, upgradable?

+ Testing needs during Long Shut-downs ?



Option under evaluation:

Upgrading an existing Refrigerator

+ dedicated 700W refrigerator for LS


- Cryogenics for 800 MHz SRF cryomodules and e-lenses
- 1 warm compressor station (WCS) in noise insulated surface build
- 1 lower cold box (LCB) in UX45 cavern
- 1 valve box in UX45 cavern
- 2 main cryogenic distribution lines
- 2 interconnection lines with existing QRL service modules (redundancy by sector cryoplants)



# Test & Qualification

## THE ZONES in the Building 2173

SM18 building, 100m x 80m, 6kW@4.5K



A serious transformation of this test station and cryogenic hardware has started and is to be continued to validate all the HL-LHC superconducting sub-systems

# SM18 – RF M7 Bunker upgrade




Ready


DO 30148

DO 30000


M7 layout - top view



M7 layout - side view



M7 Bunker Layout






# Thermometry

6'000 units, +/- 10 mK @ 2K in LHC radiation conditions




From 'sensor' to 'thermometer' with signal processing






# HL-LHC Cryogenics Master Schedule



## Major HL-LHC Cryo activities

*(SPS-BA6 on tracks, in parallel with SM18 activities)*



## P4-RF:

=> Decision baseline/alternative by end of 2016 for work @LS2

=> Then specification work during 2017, for contracts by end'2017

## P1/P5:

=> 4-5 years to complete design, clarify interfaces and prepare for tendering

# Concluding remarks

- The High-Luminosity LHC is a worldwide funded project corresponding to a 1.2km new accelerator (advanced Nb3Sn, Crab cavities, HTS links) progressively switching to construction, with European institutes and industry heavily involved
  - **Series of qualification and testing of components foreseen in the coming years**
  - Now, civil works and global lay-out has been decided, with project fully approved. Precise evaluation of heat-loads and cryogenic architecture are being refined prior to future call for tenders.
- ⇒ We will need new refrigerators, valve boxes, cryo-lines, vessels ... and we are here to help you selecting what could be adapted to your abilities !



***Thank you for your attention***






## *Spare Slides*





# HL-LHC configuration

## The Inner Triplet region with in-kinds



## The MS regions with in-kinds



## The Insertion Region (till Q4)



# What it would look like: Surface

## Helium Vessels




## Compressor station

New surface buildings, shafts and caverns to be constructed, to accommodate for new Hardware to be installed



## One cold box



## LN2 storage ?




# New HL-LHC surface buildings at P1

SF (Cooling & ventilation)


SU (Cooling & ventilation)

SE (Electrical distribution)



SHM (Cryogenics)

# New HL-LHC surface buildings at P5






# HL-LHC underground structures at P1


Based on double-decker with:

- vertical cores connecting to the LHC tunnel
- Personnel escape galleries (UPR) at both ends.




- No direct CE interface with Experiment structures.
- Minimum distance of  
~ 15 m between HL-LHC and experiment structures  
~ 7 m between HL-LHC galleries and LHC tunnel  
(reduction of radiation & deformation impacts)

# HL-LHC underground structures at P5




# HFM & Cluster D: procurement breakdown


- **HFM**
  - Cryogenic valves : DO-28760
  - Cryogenic Distribution System : IT-3944
  - Quench Buffer : DO-28932
  - Gas management panel, warm pipework : CERN
- **Cluster D**
  - Similar to HFM -> procurement w/o tendering, negotiated with companies in charge of HFM contracts



**High Field  
Magnet  
layout**



# SM18 Upgrade: baseline concept





# Technology validation of Crab Cavities

Service module to CC cryo module interface:

- Welded internal lines, equipped with flexible hoses
- Bolted external bellow with vacuum sealing

Cryogenic part studied and designed in collaboration between CRG and MME

He supply from buffer tank

DO: 30 000

Service module

Sub-cooling 2 K heat exchanger

Connections between double phase line and He tanks of the CC

CC cryo module

