



Linac4 BIS Configuration for the 160 MeV Phase


Andrea Apollonio
MPP, 29 July 2016

Acknowledgements to Christophe Martin, Bettina Mikulec, David Nisbet, Markus Zerlauth, Daniel Wollmann

General Considerations - MPS


- BIS for the 160 MeV phase should be as close as possible to final (also on the user side)
- All MPS-relevant inputs are considered mandatory at this stage
- Nevertheless, the BIS configuration should allow performing all required actions for efficient commissioning
- Different requirements on pulse length for different destinations to be taken into account

LINAC4 BIS : 160 MeV + HST



The Linac4 BIS architecture for the 160 MeV phase requires 2 additional BICs wrt 100 MeV phase

LINAC4 BIS : 160 MeV + HST



The Linac4 BIS architecture for the 160 MeV phase requires 2 additional BICs wrt 100 MeV phase

Master BIC RF Source: the real situation

			Interlock Element	Ch.
1	1	1	SIS	0
0	0	1	Source Start	1
1	1	x	Source Internal	2
1	1	x	Source HV	3
1	x	x	Pre-chopper	4
1	0	0	Source Beam Stoppers Out/Moving	5
0	1	1	Source Beam Stoppers In	6
1	x	x	Chopper	7
1	x	x	L4 Low-Energy Watchdog	8
1	x	x	L4 Low-Energy Vacuum Valves	9
1	x	x	L4L.ChopperQuads	10
1	x	x	RFQ	11
1	x	x	CCC Operator Veto	12
1	x	x	L4 Operator Veto	13
x	x	x	Not used	14
1	1	1	H- Source Beam_Permit	OUT



Not Ready (mask inside the user's PLC)



Not Ready before FGC3 available (monitored in the SIS)



Variable timing implemented (voltage not yet monitored)



Need to change the logic following new BCT position



Wide thresholds (I_magnet in range [20A, 200A])



Does not include LLRF



Not Present (before commissioning dump)



- RF control ✓
- Pre-chopper ✓

Master BIC Chopper : the real situation

				Interlock Element	Ch
1	1	1	1	SIS	0
1	1	1	0	Source Beam Stoppers Out / Moving	1
0	0	0	1	Source Beam Stoppers In	2
1	1	1	x	Linac4 OK	3
0	0	1	x	AQN L4T.MBH_DUMP	4
x	x	1	x	L4Z OK	5
1	1	0	x	AQN L4T.MBH_LT	6
1	1	x	x	Linac4 Transfer OK	7
0	1	x	x	AQN LTB.BHZ40_LBE	8
x	1	x	x	LBE OK	9
1	0	x	x	AQN LTB.BHZ40_PSB	10
1	x	x	x	PSB Injection 1 OK	11
1	x	x	x	PSB Injection 2 OK	12
1	x	x	x	PS OK	13
x	x	x	x	Not used	14
1	1	1	1	Choppers Beam_Permit	OUT

First 3 out of the 4 destinations are required for the 160 MeV + HST phase:

- Beam to stopper
- Beam to L4 Dump
- Beam to HST (replacing LBE destination)

Forced to "TRUE"
Forced to "TRUE"
Forced to "FALSE"

Inputs not required: permits are forced to the required level in order to allow decoding the third destination "Beam to HST"

- RF control ✓
- Pre-chopper ✓
- PSB RF X

Slave BIC L4 : the real situation

	Interlock Element	Ch.
1	SIS	0
1	External Conditions	1
1	L4 Vacuum Valves + L4T.WGS.0101	2
1	BLMs L4+L4Z	3
x	Not used	4
1	WIC L4	5
x	Not used	6
x	Not used	7
1	L4 RF	8
x	Not used	9
x	Not used	10
x	Not used	11
x	Not used	12
x	Not used	13
x	Not used	14
1	H- Source Beam_Permit	OUT



Forced to "TRUE", not required for the 160 MeV

BLMs available, thresholds to be hardcoded

Temporary watchdog removed

- L4 RF moved on "Maskable" input for 160MeV commissioning phase (as for previous phases)
- What's the long term view?

Does not include LLRF



- Master RF Chopper

Slave BIC L4Z : the real situation


	Interlock Element	Ch.	
1	SIS	0	✓
1	L4Z Dump OK	1	✓
1	L4 Z Dump WD	2	✓
1	L4Z Vaccum Valve	3	✓
x	Not used	4	
x	Not used	5	
x	Not used	6	
x	Not used	7	
x	Not used	8	
x	Not used	9	
x	Not used	10	
x	Not used	11	
x	Not used	12	
x	Not used	13	
x	Not used	14	
1	L4Z OK Beam_Permit	OUT	

Slave BIC L4T : the real situation

	Interlock Element	Ch.
1	SIS	0
1	L4T WD	1
1	L4T Beam Stopper Out	2
1	AQN LT.BHZ20	3
1	AQN LT.BHZ30	4
1	AQN L4T.MBV	5
1	BLMs L4T+LT+LTB	6
1	LT + LTB Vacuum Valves	7
1	L4T.VVGS.1751 Vacuum Valve	8
1	WIC L4T	9
1	WIC LT+LTB	10
x	<i>not used</i>	11
x	<i>not used</i>	12
x	<i>not used</i>	13
x	<i>not used</i>	14
1	Transfer Line OK	OUT

Slave BIC L4T : the real situation

	Interlock Element	Ch.
1	SIS	0
1	L4T WD	1
1	L4T Beam Stopper Out	2
1	AQN LT.BHZ20	3
1	AQN LT.BHZ30	4
1	AQN L4T.MBV	5
1	BLMs L4T+LT+LTB	6
1	LT + LTB Vacuum Valves	7
1	L4T.VVGS.1751 Vacuum Valve	8
1	WIC L4T	9
1	WIC LT+LTB	10
x	not used	11
x	not used	12
x	not used	13
x	not used	14
1	Transfer Line OK	OUT




	Interlock Element	Ch.
1	SIS	0
1	L4T WD (L4L.BCT.4013 and L4H.BCT.1073)	1
1	L4T Beam Stopper Out	2
1	External Dump OK	3
1	H ⁰ /H ⁻ Dump OK	4
1	H ⁰ /H ⁻ Current Monitor	5
1	BLMs L4T until HST	6
1	Vacuum Valves between L4T MBH% and HST end	7
1	Injection Foil Status	8
1	WIC L4T (for magnets until HST end)	9
1	BSW3/4 Status	10
1	Destination HST	11
1	Linac4 Foil OUT	12
x	not used	13
x	not used	14
1	Transfer Line OK	OUT

- ✓ Orange Inputs: consider different elements than final (WIC, BLMs, VV, WD)
- ✓ External dump is the commissioning dump (max 100 us)
- ✓ Destination HST: timing module and SIS will limit pulse length to 100-150 μs
- ✓ IF DEST = HST then L4 foil must be OUT, otherwise the stripped H⁻ could be lost in the bending magnets

SIS for LINAC4

- Operational
- BI requirements
 - Comprehensive list received from F. Roncarolo
 - All SEM grids and Wire Scanners shall limit max beam pulse
 - SIS shall limit beam pulse length to 100us if device in beam
 - BTV?
- New requirements for HST?
 - Limit pulse length depending on destinations?



BIS Commissioning

CERN

CH-1211 Geneva 23
Switzerland



the
Linac4
project

LINAC4 Project Document No.

L4-CIB-ES-0001 rev. 1.0

CERN Div./Group or Supplier/Contractor Document No.

BE/OP

EDMS Document No.

1016233

CERN

CH-1211 Geneva 23
Switzerland



the
Linac4
project

EDMS NO.

1310007

REV.

0.2

VALIDITY

DRAFT

REFERENCE

L4-CIB-ES-0005

Date: 2014-03-05

Engineering Specification

THE COMMISSIONING STEPS OF THE LINAC4 BEAM INTERLOCK SYSTEM

ABSTRACT:

The Beam Interlock System for Linac4 and its transfer lines to the PSB will be deployed in accordance with the global Linac4 schedule which includes five commissioning phases: 3MeV, 12MeV, 50MeV, 100MeV and 160MeV.

This document describes the steps to deploy the different Beam Interlock Controllers and to identify the connected systems which will be required for each phase of the commissioning.

BEAM INTERLOCK LINAC4, BOC

The beam interlock system is a mixed system comprising hardware (Beam Interlock System), software interlock (Beam Interlock System) and the concept of External Control (Beam Interlock System). This document summarises the beam interlock system and the PSB transfer lines and the

Prepared by:

Conclusion

- Operation at 160MeV allows testing the BIS in the (almost) final configuration for Linac4
- Important to have also user inputs in the final configuration
- 2 additional slave BICs installed, L4T slave requires modifications for HST
- Requirements on pulse length for different destinations to be enforced (SIS?)
- When should we foresee the 'final' configuration?

