

Life-cycle and Reliability of accelerators

JUAS 2017

part 1: life-cycle

part 2: reliability

SOME OF THE SLIDES

Samuel Meyroneinc


Centre de Protonthérapie – Orsay

Institut Curie

9th March 2017



institutCurie



Users (customers)

The typical steps of lifecycle of Accelerators (one of the naming possible)

- Desire- Need
- Preliminary design
- Detailed design
- Construction-installation
- Tests & Commissioning
- Operations- Maintenances
- Stop



Desire-
Need

Preliminary
design

Detailed
design


Construction-
Installation

Tests
Com.

Operations
Maintenances

Stop

Australian Synchrotron Construction Timeline



- 2001**
Australian Synchrotron Project funding announced by the Victorian Government
- 2002**
Formation of scientific and machine advisory committees
Site launch and preparation
- 2003**
Machine design announced
Building and associated facilities contract awarded
Construction started
Injection system contract awarded
- 2004**
All particle accelerator systems contracts awarded
Beamline design process starts
Formation of industry advisory committee
- 2005**
Building complete
Machine assembly starts
- 2006**
Installation and commissioning of machine and beamlines begins
Selection of operator
- 2007**
Commissioning of first beamlines complete
31 July: Australian Synchrotron formal opening

EUROPEAN SPALLATION SOURCE

ESS in Lund/Sweden

- Brightest neutron source worldwide
- 17 European member states
- First Neutrons: 2019
- Full power operation: 2025
- Decommissioning: 2065
- Investment: 1800 MEURO
- Sustainable energy concept
- 95% overall reliability

ARW2013, Annika Nördt, Melbourne, 2013-04-17

Step « desire-need »


Formulate the desires

Idea-concept-feasibility-willingness


Formulate the needs

Request, requirement, specifies

Description of the need



Increase flux of neutrons




Difference between Preliminary design/ Detailed design

Preliminary design

Obtaining the dimensioning data

Detailed design

All the data required for the construction



Paramètres FCC-hh comparés à LHC

parameter	LHC	HL-LHC	FCC-hh
c.m. energy [TeV]	14		100
dipole magnet field [T]	8.33		16 (20)
circumference [km]	36.7		100 (83)
luminosity [$10^{34} \text{ cm}^{-2}\text{s}^{-1}$]	1	5	5 [$\rightarrow 20?$]
bunch spacing [ns]	25		25 {5}
events / bunch crossing	27	135	170 {34}
bunch population [10^{11}]	1.15	2.2	1 {0.2}
norm. transverse emitt. [μm]	3.75	2.5	2.2 {0.44}
IP beta-function [m]	0.55	0.15	1.1
IP beam size [μm]	16.7	7.1	6.8 {3}
synchrotron rad. [W/m/aperture]	0.17	0.33	28 (44)
critical energy [keV]	0.044		4.3 (5.5)
total syn.rad. power [MW]	0.0072	0.0146	4.8 (5.8)
longitudinal damping time [h]	12.9		0.54 (0.32)



What we know-what we can (internal, external)

**Internal: experience, skills (people, teams),
methods, ...**

**External: we can ask to do
(partnership, collaborations, sub-contract, ...)**

Development – the V cycle

***Needs
Analysis***

***Operations
maintenance***

***System
Specification***

***System
Validation***

***Sub-systems
Design***

***Sub-systems
Validation***

***Preliminary
Design***

***Tests &
integration***

***Detailed
Designed***

***sub-system
Tests***


Realisation

Construction-Installation

The Building

The Equipment

(the overall: the « facility »)



The building-the infrastructure

- The instrument is the « overall »
- Building first: 1st milestone “Building Occupancy Date”
- Building and ancillaries are specific and complex
- Interfaces, large numbers of areas
- To be designed for users, maintenance, upgrades, ...
- Cost ?
- Cost = 30%to 50% of the total cost

- 1 Good point : designers&builders often with more experience than Large Instruments stakeolders (ex: The building world as the reference for the naming of steps)
- 1 Bad point : many features are no more ajustable after first design

Construction-Installation

The Equipment




Figure 6-1: Cut-away diagram of an XFEL vacuum vessel.

Example of the cryo-modules X-Fel







Figure 12-1 : schedule of the assembly according with the availability of cavity.

Tests and Commissioning

Tests, Tests, Tests, ...

The commissioning: « The process during which components and systems, after construction, are made operational and verified to be in accordance with design assumptions and performance criteria”.



4 main dimensions during life-cycle

- **Politics**
- **Money-Fundings**
- **Customers/Providers**
- **Regulatories**

International collaborations 1 843M€ construction


Suède et Danemark – hosting countries:


47.5% Construction
15% Operations
100% Cash

Partners countries:

52.5% Construction
85% Operations
70%/30% in kind / in cash

Estimated running budget <140M€
Life-time ~40 years





Of interest for accelerators



Fundings and budgets

1. For studies

2. for construction (investment)

3. for operations

salaries


fees (consumables, running costs...)

upgrades

1. in cash


2. in kind (contribution)

provider



customer

Hirsch index or Hirsch number



22

Level of delivery	The supplier is delivering	The customer is expecting (so testing, accepting)	Example in particle accelerator
Parts	Part of hardware, part of software	technological data	Power supply
System	A global system	Individual technological & physics performances	RF Cavity
Systems Integrated	Many systems integrated	Global performances	BEAM
Facility	Conditions to perform the whole « job »	Resultst: experiments or production achieved	Users of Synchrotron
Societal	Service or science advances	New society	Higgs boson completing the standard model

Regulatories (why ?)

Why

Risks on personal (workers)

radiation protection, fire, mechanical ...

Risks on environment

2 kinds of approach:

Authorization


Control

Internal/ external

internal: safety officer, radiation officer , procedures, rules

external: national authorities, control office, norms

End of the life-cycle



Stop

Consignate

Lock-out all the networks and clearances

Dismantle

“Decommissioning”

The process by which the facility is permanently taken out of operation at the end of the plant lifecycle with adequate regard for the health and safety of workers and the public, and protection of the environment.

A little history on management of facilities

years	Facilities considered	Classical management of the end of the facility
Before the 19th century	buildings, « classical » factories, etc ...	abandon, reconversion, demolition. The garbage are put in ... the trash
from 1970	Begining of the complex factories, including nuclear facilities	Dismantlement considered at the end of the use. The garbage are stocked.
1970-2000	Begining of the end of some nuclear facilities	Authorities introduce the question of the dismantlement at the begining of the facility
From 2000	all	Sustainable approach

some of the definitions

Main term	Other terms and notions	goal
Desire-need	Feasibility -exploration	Express of interest
Preliminary design		Data to dimension
Detailed Design		All the data ready to build
Construction/ installation	Realisation-Production Building /Equipement Academic/Industrial	From design to real
Test/ commissioning	Acceptance/Qualification	Before starting the operations
Operations	Maintenance/upgrade	Use
Stop	Decommissioning Dismantle	Clean & clear (re-use)

Specificities of accelerators

Many parameters linked to the **beam** (IS, magnetic field, vacuum, RF, ...)

Large: money (threshold), politics, time, building...

Long Duration (knowledge management, quality, obsolescence, ...)

Science: uncertainties-risk, complexity,...

International (language, culture, politics, interface, regulatory, ...)

Radiation: risk, safety, long-term, regulatory, ...

Dimensions of analysis :


Technologies/Physics

Academics / industrials


Projects/Operations

Time scale

Upgrade de l'ESRF : ESRF II



- Nov 2012 White paper (conceptual design)
- Nov 2012- Dec 2014 Technical Design Study
- June 2014 Project approved by the Council
- Jan 2015 – Oct 2018 Detailed design and procurement
- Oct 2018 – Sep 2019 Shutdown for installation
- Sep 2019 – Jun 2020 Commissioning
- June 2020 User Mode Operation



Start shutdown:
October 2018

Life-cycle and Reliability of accelerators

JUAS 2017

part 1: life-cycle

SOME OF THE SLIDES

part 2: reliability

Samuel Meyroneinc

Centre de Protonthérapie – Orsay

Institut Curie

9 th March 2017

Definition of reliability

1st basic approach

$$\text{Reliability} = \frac{\text{Time the systems works} - \text{Time of breakdowns}}{\text{Time the system works}}$$

Definitions of reliability

The **reliability** is the ability of a system or component to perform its required functions under stated conditions for a specified period of time

The reliability ($R(t)$) is the probability to have no failure at the time t .

MTBF: Mean Time Between Failures

MTTR: Mean Time To Repair

The **availability** of the system is the ratio of the time when the system is operational by the time it was supposed to be operational

$$\text{Availability} = \text{MTBF} / (\text{MTBF} + \text{MTTR})$$

exercise


An accelerator is used from 10:00 to 20:00

During this time, there were:

- 10 small failures of ion sources lasting 5 min for each
- 2 times (15h and 19h) a failure of a magnet power supply, requiring 30 min to retune the beam

What is the MTBF ?

What is the problem to solve first to do the best « physics » ?



What is the **product (service)** delivered ?
What is the **quality** defined ?
Who is defining the reliability ?

Reliability and Accelerators

- Power- Energy & Motion

Electricity, cooling, regular motion systems

-Critical and/or sensitive Technologies

Radio-Frequency, vacuum, electronics, cryogenics, software, ...

- Risks

radiation-protection, costs, ...


-Complexity

mix of technologies, %research%production, regulations


- Using &Users (Customers / Providers)

beams: current, energies, duration, ...

the 4 layers of reliability



Life-cycle of Large Instruments



The « operations » for an accelerator

- All the process to be managed in order to deliver the required beam (and associated services) during the planned period

This includes:

- Startup of the system, Tuning of the beam
- check of the normal behaviour of the systems during
- monitor and record parameters (automatic or manual, log-books, ...)
- fix any unplanned event (troubleshooting, corrective actions level 1,2,...)

- planning of the activities (discussion with users): day, month, year
- managing the documentation (procedures, drawings, ...)
- training of operators level 1, 2, ...

- in direct relation with maintenance and project issue

Operations / Projects

Goal: keeping a process stable


Key Performances
Indicators (KPI): reliability, production outputs for users (ex: hours of beam)

Goal: reaching a specific target (new)


Key Performances
Indicators (KPI): Milestones (dates), level of completion achieved, performances reached, reliability of planning ...

Plan – Do – Check – Act (PDCA)

(to manage Operations)




The reliability Weibull Model



Maintenances

Modelisation, experience




Inspect, clean, check,
lubrify, calibrate, read,
replace, test ,...

< 20% with high periodicity
Ex: Ions Sources

Maintenances


Modelisation, experience



- Awareness of problem(s)
- Diagnosis
- Fix-replace
- test

Maintenances

Modelisation, experience



planning

Building
Ancillaries




margins

Magnet
RF
Power Supplies



Integration
Test
Commissioning



Contracting with

With the provider of the accelerator

- performances and acceptance tests
- contents and limits of interfaces (beam, building , control, ...)
- training - documents
- budgets (bonus / penalties)
- maintenance contract

With the provider of building and ancillaries

With the users (« real » needs, constraints, freedoms, evolutions...)


With the payers (budget and resources)

- for investment
- for ramp-up and contingencies
- for operations, maintenance, ...

Science of Organisations

Henry Mintzberg: different kinds of coordination

- **Mutual adjustment**
- **Direct supervision**
- **Standardization of work processes**
- **Standardization of outputs**
- **Standardization of skills**
- **Standardization of norms**






+

Quality Assurance




contract



institutCurie

RAMI approach (Reliability, Availability, Maintainability, Inspectability) for project IFMIF



Concepts and reliability

Principles to increase reliability:

- Redundancy
- accessibility
- over-engineering
- maintainability
- ...

Parameters increasing risks on reliability

- Technological innovations
- Lonely experience
- Number of specific interfaces
- pressure on quality, budget, delay
- ...

The (wellknown) recipes for a good reliability

A system (hardware & software) well designed

- specifications, model of developpement, tests
- principles of reliability, a lot of diagnosis

A well-maintained system

- Preventive, real, adaptative, reactivity for corrective
- Spare parts (a lot, ready for use)
- time dedicated for operations


Human resources and good organization

- people trained, skilled, enough, here when required
- efficient and clean organization, data-base, Knowledge Management

Briefly: resources (men, budget), consistency, willingness...



**Synchro-cyclotron - HCL
Harvard (1949-2003)**



**Cyclotron 88 inch - LBL
Berkeley (1961 - ...)**



**Cyclotron PSI (590 MeV)- CH
designed for 100 μ A (1974)
an now at 2,2 mA (2012)**

