


Introduction to the SPL

- 1. Context**
- 2. LP-SPL**
- 3. SPL high power options**


1. Context



Main requirements of PS2 on its injector:


Requirement	Parameter	Value
2.2 x ultimate brightness with nominal emittances	Injection energy	4 GeV
	Nb. of protons / cycle for LHC (180 bunches)	6.7×10^{13}
Single pulse filling of SPS for fixed target physics	Nb. of protons / cycle for SPS fixed target	1.1×10^{14}
Provide all beam time structures for LHC	Bunch spacing	25/50/75 ns
	Number of bunches / missing bunches	1 - 168
Flexible control of emittance and intensity per bunch	$\varepsilon_{x,y} / \varepsilon_L / N_b$	

Site layout



Implementation of the new injectors: **LP-SPL + PS2**

Construction of LP-SPL and PS2 will not interfere with the regular operation of Linac4 + PSB for physics.
Similarly, beam commissioning of LP-SPL and PS2 will take place without interference with physics.



- First milestones**
- Project proposal: 2011- 2012
 - Project start: January 2013

Goal of the SPL study (2008-2012)

from Note on 31/03/2009 (EDMS Id 993472)

The goal of the SPL study is to prepare for a start of construction of the low power SPL optimized for PS2 and LHC at the beginning of 2013.

For that purpose, a detailed Conceptual Design Report and a cost estimate will be published in May 2012. The cost of leaving the possibility of a later upgrade to 5 GeV and high beam power will also be quantified.

2. LP-SPL

Stage 1: Linac4 - Main characteristics

Ion species	H ⁻	
Output Energy	160	MeV
Bunch Frequency	352.2	MHz
Max. Rep. Rate	2	Hz
Max. Beam Pulse Length	1.2	ms
Max. Beam Duty Cycle	0.24	%
Chopper Beam-on Factor	65	%
Chopping scheme: 222 transmitted /133 empty buckets		
Source current	80	mA
RFQ output current	70	mA
Linac pulse current	40	mA
N. particles per pulse	1.0	$\times 10^{14}$
Transverse emittance	0.4	π mm mrad

Max. rep. rate for accelerating structures: 50 Hz

H⁻ \Rightarrow charge exchange injection and painting in the synchrotron (PSB / PS2).

Higher injection energy in PSB (160/50 MeV, factor 2 in $\beta\gamma^2$) \rightarrow same tune shift with twice the intensity.

Re-use of LEP RF components: klystrons, waveguides, circulators.

Chopping at low energy to reduce capture loss in the synchrotron (PSB / PS2).


- Structures and klystrons dimensioned for 50 Hz
- Power supplies and electronics dimensioned for 2 Hz, 1.2 ms pulse.

Stage 1: Linac4 - Block diagram

Normal conducting RF accelerating structures: 4 types (RFQ, DTL, CCDTL, PIMS)

Frequency: 352.2 MHz

Duty cycle: 0.1% phase 1 (Linac4), 3-4% phase 2 (SPL), (design: 10%)



Ion current:
40 mA (avg.),
65 mA (peak)

Linac4: 80 m, 18 klystrons (352 MHz)

Stage 1: Linac4 - Civil engineering status



Linac4 tunnel (“cut and cover” excavation) seen from high-energy side.

Final concrete works starting at low-energy side, excavation proceeding at high energy side.


Tunnel level -12 m, length 100 m.

Delivery of tunnel and surface equipment building end of 2010.



High-energy side of Linac4 tunnel, with beam dump chamber and connecting tunnel to Linac2 line.

Stage 1 - Planning



← project duration: 6 years →

- MILESTONES:
- ✓ Building delivery: December 2010
 - ✓ Infrastructure installation: 2011
 - ✓ Machine and equipment installation: 2012
 - ✓ Linac commissioning: 2013
 - ✓ PSB modifications: shut-down 2013/14.
 - ✓ Beam from PSB: April 2014.

Stage 2: LP-SPL - Main characteristics

Ion species	H ⁻	
Output Energy	4	GeV
Bunch Frequency	352.2	MHz
Max. Rep. Rate	2	Hz
Max. Beam Pulse Length	0.9	ms
Max. Beam Duty Cycle	0.2	%
Nominal chopping factor (Flexible chopping scheme)	65	%
Source current	40	mA
Linac pulse current	20	mA
Number of ions per pulse	1.1	$\times 10^{14}$
Transverse emittance	0.4	π mm mrad

Max. rep. rate for
accelerating structures
and klystrons:

50 Hz

Required for flexibility and low loss in PS2

Required by space charge tune spread at the specified beam brightness

Re-use of LEP RF components in Front-end (Linac4)

Required for flexibility and low loss in PS2 (linac4 chopper with new driver)

➤ Structures and klystrons dimensioned for 50 Hz
➤ Power supplies and electronics dimensioned for 2 Hz, 2 ms pulse.

Frequency/temperature:

704 MHz and 2 K are confirmed,

Cavity gradient:

- 25 MV/m “on average” (= with a high yield) is very challenging and may be costly (in terms of reprocessing),
- 20 MV/m seems more achievable but will have an impact on linac length (or energy).




High-power RF cavity tests of fully equipped cryo-modules are mandatory for realistic SPL layout estimates!!

Ref.: Assessment of the basic Parameters of the CERN SPL, CERN-AB-2008-067-BI-RF,
<http://cdsweb.cern.ch/record/1136901/files/CERN-AB-2008-067.pdf>

Stage 2: LP-SPL - Block diagram


SC-linac (160 MeV → 4 GeV) with ejection at intermediate energy



Stage 2: LP-SPL - Cryomodules



Medium β cryomodule

Energy range: 160 MeV – 732 MeV
 5 cell cavities
 Geometrical β : 0.65
 Maximum energy gain: 19.4 MeV/m
 54 cavities (9 cryomodules)
 Length of medium β section: ~ 110.35 m



High β cryomodule

Energy range: 732 MeV – 4 GeV
 5 cell cavities
 Geometrical β : 1
 Maximum energy gain: 25 MeV/m
 152 cavities (19 cryomodules)
 Length of medium β section: ~ 286.2 m




3. SPL options

High Power proton beams (HP-SPL)



- Replacement of klystron power supplies, upgraded infrastructure (cooling & electricity, etc.)
- Addition of 5 high β cryomodules to accelerate up to 5 GeV (π production for ν Factory)

SC-linac (160 MeV \rightarrow 5 GeV) with ejection at intermediate energy



High Power proton beams (HP-SPL)

Beam characteristics of the main options

	Option 1	Option 2
Energy (GeV)	2.5 or 5	2.5 and 5
Beam power (MW) 	2.25 MW (2.5 GeV)	4 MW (2.5 GeV)
	<u>or</u>	<u>and</u>
	4.5 MW (5 GeV) 	4 MW (5 GeV)
Rep. frequency (Hz)	50	50
Protons/pulse ($\times 10^{14}$)	1.1	2 (2.5 GeV) + 1 (5 GeV)
Av. Pulse current (mA)	20	40
Pulse duration (ms)	0.9	0.8 (2.5 GeV) + 0.4 (5 GeV)

Faster rep. rate
 \Rightarrow new power supplies, more cooling etc.


$2 \times$ beam current $\Rightarrow 2 \times$ nb. of klystrons etc .

e⁺/e⁻ acceleration

LHeC: 20 GeV e⁺/e⁻ from the SPL (5-pass acceleration in the $\beta=1$ section) as a pre-injector for a lepton ring in the LHC tunnel (Ring/Ring option)

New Injector from future SPL to Point 2 (ALICE) via T12 tunnel with :

- New re-circulating loop (20m radius)



**THANK YOU
FOR YOUR ATTENTION!**

High power proton applications

