



Installation of the CLIC Stripline Kicker at the ALBA Storage Ring for its beam characterisation

2017 CLIC Workshop

M.Pont, on behalf of the ALBA team




Outline

- 1. Introduction**
- 2. Design issues**
- 3. Installation**
- 4. Conditioning**
- 5. Beam characterisation**

$E = 3.0 \text{ GeV}$
 $C = 268.8 \text{ m}$
 $\epsilon = 4.0 \text{ nm}\cdot\text{rad}$



8 BL x In operation

3 BL x In construction






Introduction to ALBA



Design issues


STRIPLINE KICKER


- Beam pipe of 40.50mm ID
- Total length 1.7 m
- Al electrodes hold in position by MACOR rings (28.8 mm ID)
- Distance between electrodes 20 mm



[1] C. Belver-Aguilar et al, Beam impedance study of the stripline kicker for the CLIC damping ring, Proc. IPAC 2012

CLIC stripline installed in a medium straight section of the SR






Design issues


Absorber design is critical:

- should protect stripline from SR
- but should not limit the horizontal aperture of the SR

1) Rotate the stripline by 90°




2) But still MACOR rings



Absorber design is critical:

- should protect stripline from SR
- but should not limit the hor aperture of the SR

3) Reduce safety margin: Only 1 mm between SR fan and last MACOR ring



4) Distance: tip absorber – beam
9.4 mm
comparable to SR limiting aperture




Installation



- TCs installed at the outer side of electrodes and at the chamber
 - RGA installed 10 m upstream from stripline
 - Work with open ended stripline
- Calculations by C.Belver indicated that the T at the electrodes could reached 80°C, which seemed acceptable.*

Pressure


Since the nominal conditions for beam for users were not achieved, the stripline was replaced



- For $I < 110$ mA pressure is slowly decreasing, OK
- For $I > 110$ mA the behaviour is not explained, NOK
- RGA (placed 10 m upstream) shows a clean spectra

Temperature

Since the nominal conditions for beam for users were not achieved, the stripline was replaced



- Reached 45°C in the outer side of the connector
- Temp reached on the electrode?

SOURCES OF HEAT INSIDE THE STRIPLINE

- 1) Because the stripline is not terminated, beam image currents flow and stay on the electrodes

$$>33\text{W}/4 \text{ feedthrough} = >8 \text{ W/feedthrough}$$


$$T_{\text{electrode}} = 80^{\circ}\text{C}$$

- 2) Synchrotron radiation impinging on the MACOR rings.

SOURCES OF PRESSURE INCREASE INSIDE THE STRIPLINE

- 3) Photodesorption due to SR on the absorber
- 4) Thermal desorption

Zoom in at stripline exit, last MACOR ring



SR hitting the MACOR rings

- What happens to MACOR under radiation?
- RGA indicates a clean scan but is it close enough?

- Re-aligned Stripline
- Stripline connected to loads to avoid T increase
- RGA installed next to the stripline



4 x 100W loads
from DICONEX




RGA




Conditioning_2



125 mA



135 mA



MACOR degradation ?



Plan for measurements with beam



Stripline characterisation with beam

- 1) Measurements without HV DC power supplies: Beam coupling impedance
 - The striplines assembly, together with the absorber, could have an impact on the ring impedance.
 - ❑ Measuring the beam impedance of the total ring before and after the installation of the striplines.
 - ❑ Single bunch measurements to determine TMCI threshold and detuning slope.
 - Following impedance measurements of the striplines, they will be replaced by a beam pipe and measurements remade: this will allow the influence of the absorber to be assessed.



Stripline characterisation with beam

- 2) Measurements with the HV DC power supplies: **Transverse field homogeneity**
- The electrodes will be powered by DC HV power supplies and will not be resistively terminated.
 - Simulations shown that powering the electrodes with DC voltage does not result in higher field inhomogeneity.
 - ❑ Only electrostatic field will be used to deflect the beam (the striplines will be open-circuited).
 - ❑ One issue that could appear when the terminations are open-circuited is the temperature increase at the electrodes
 - A voltage of 45 V to 60 V will be delivered to the FUG power supplies due to the image currents flowing through the electrodes, when a beam of 150 mA is circulating through the striplines [calculations done in ALBA].
 - A low-pass filter could be used to protect the FUG power supplies (presently being studied).



Stripline characterisation with beam

- 2) Measurements with the HV DC power supplies: **Transverse field homogeneity**
- A local angle measurement will be performed with 4 BPMs
 - Slow acquisition
 - Using a multibunch filling pattern
 - Calibration of the BPM non linear behaviour is under way




Stripline characterisation with beam

- 3) Measurements with the Inductive Adder: **Field flat-top stability, pulse-pulse repeatability, longitudinal field homogeneity.**
- Two inductive adders (J. Holma's presentation) are expected to be supplied by CERN at the end of 2017.
 - There is some concern about the radiation next to the beam line and its potential influence upon the MOSFETS of the inductive adders.
 - The inductive adder could be placed in another area and connected to the striplines by using 10 – 15 m long cables.
 - Transient studies of the magnetic field pulse have been completed (C.Belver presentation).

Stripline characterisation with beam

3) Measurements with the Inductive Adder: **Field flat-top stability, pulse-pulse repeatability, longitudinal field homogeneity.**

- Variable pulse delay
- Flat top might be an issue, ALBA rev time is 897 ns
- Measurements done in single bunch
- Using BPMs TbT readings with enough averaging
- Use global amplitude measurement with all 122 BPMs





NEXT STEPS

- 1) Find another solution for the MACOR rings
→ Already under discussion with the manufacturer
- 2) Conditioning the stripline with beam
- 3) Impedance measurements
- 4) Conditioning stripline with HV
- 5) Measurements with beam and dc HV
- 6) Measurements with the inductive adder