



china eu india japan korea russia usa



Status of the ITER Cryodistribution

H.-S. Chang¹, H. Vaghela², P. Patel², A. Rizzato¹, M. Cursan¹, D. Henry¹,
A. Forgeas¹, D. Grillot¹, B. Sarkar¹, S. Muralidhara², J. Das², V. Shukla², E. Adler³
¹ITER Organization, Route de Vinon sur Verdon, 13115 St Paul Lez Durance, France
²ITER-India Institute for Plasma Research, Block-A Sangath Skyz, 380 005 Ahmedabad, India
³Linde Kryotechnik AG, Dättlikonerstrasse 5, 8422 Pfungen, Switzerland




Abstract

Since the conceptual design of the ITER Cryodistribution (CD) many modifications and changes have been applied due to both system optimization and improved knowledge of the clients' requirements. A summary of present design status and component configuration of the CD with all the changes implemented which aim at process optimization and simplification as well as operational reliability, stability and flexibility will be presented.

LHe	Liquid Helium	CTCB	Cryoplant Termination Cold Box	CCL	Cold Circulator	CS	Central Solenoid (coil)
SHe	Supercritical Helium	ACB	Auxiliary Cold Box	CCP	Cold Compressor	TF	Toroidal Field (coil)
GHe	Gaseous Helium	TCVB	Thermal Shield Cold Valve Box	HX	Heat eXchanger	ST	(magnet) STructure
LN ₂	Liquid Nitrogen	TS	Thermal Shield	PS	Phase Separator	PF&CC	Poloidal Field & Correction Coils

→	LHe (line A) from LHe tank	→	50 K GHe to current leads (line H)	→	LN ₂
↔	GHe (line B), return of flash/tank pressurization	→	SHe downstream CCL (line CC)	→	SHe upstream CCL (line CD)
↔	J-T stream SHe (line C)	→	80 K GHe to TS (line E)	→	Cold recovery from CP (line CR)
↔	Evaporated GHe (line D)	→	100 K GHe from TS (line F)		
⊗	Valve 100 % open	○	Temperature sensor	⊗	80 K thermal shield
⊗	Valve control opened	□	Pressure sensor	⊗	Coriolis mass flow meter
⊗	Valve closed	⊗	Mass flow meter	⊗	Connection to test cryostat
⊗	Cold circulator	⊗	CRM warm-up port	⊗	SHe/LHe HX
⊗	Cold compressor	⊗	CRM thermal shield	⊗	SHe/GHe HX
				⊗	LHe level sensor
				⊗	ΔP sensor

1. Schematic Overview of the ITER Cryogenic System




2. Status of the Cryoplant Termination Cold Box (CTCB)

Valves at CTCB interfaces with Cryolines are for (dis)connection with Cryoplant and ACBs/TSCS are fully open or closed without active control during operation and managed by the Cryogenic System Master Controller (MC).

Active controls managed by CTCB are:

- SHe downstream last turbine T4 of each LHe plant is collected in line C manifold and then expanded to the LHe tank via V_{C0} (or V_{C9}), while keeping P close to 5 bar (same for line H downstream first turbine T1 of each LHe plant using V_{H0});
- In case only one LHe plant has to be operated and connection to the ACBs is not allowed (e.g.: liquefaction of GHe into LHe tank for inventory storage during Tokamak maintenance) P of line C can be adjusted by the valves V_{CN} ($N=1-3$);
- During warm-up, SC magnets (total mass of ~10,000 tons) act as cold source. For thermal balance inside LHe plants (i.e. keep ΔT_{CD} below 20 K), V_C is closed, $V_{C'}/V_{C''}/V_{CC}$ opened and heaters are operated. When heater power is at maximum and ΔT_{CD} close to limit value, V_{CD} is opened to decrease ΔT_{CD} ;
- The TS T of the LHe-plant/tank-interfacing Cryolines and the CTCB itself is controlled by maintaining ΔT between the supply and return GHe within 20 K by using V_{FN} ($N=0-4$) (applicable for all operation modes like cool-down/warm-up of the TS's);
- Coriolis flow meter with a valve upstream, heater and T sensor downstream are acceptance plan and performance measurement of the ITER Cryoline system.





3. Optimizations of the Auxiliary Cold Box (ACB) Configuration

Due to the additional nuclear load during the D-T plasma phase, cooling power to maintain the thermal stability of the SC magnets can be beyond the capacity of the Cryoplant.

To allocate more cooling power to the magnet system, each ACB is equipped with own CCP (removal of Cold Compressor Box) and double PS which allowed standardization of ACB configuration:

- Outer vacuum jacket (OVJ) of the ACBs: same physical dimension;
- PS1/PS2 and HX1/HX2/HX3: same physical dimensions and specifications for all ACBs;
- CCL: Same type for all five except different cold casing and impeller for ACB-3 (ST) [6];
- CCP: Same warm part for all five, for cold parts (cold casing and impeller) three different types for ACB-1/4 (CS/PF&CC), ACB-2/3 (TF/ST) and ACB-5 (CP).




Valves at ACB interfaces with Cryolines are for (dis)connection with CTCB and client cold boxes are managed by the MC.


The ACB control system has to manage the automatic switching (when requested by the MC) among operation modes

Active process controls to be managed by the ACB control system are:

- Keep the LHe level of PS1/PS2 within acceptable range using V_{JT1}/V_{JT2} ;
- Rotational speed control of CCP to maintain the vapor pressure of PS2 within allowed range;
- Surge protection of CCP using V_{S1} (warm mass flow feed) and V_{S2}/V_{S3} (cold mass flow feed);
- Surge protection of CCL (operated at constant rotational speed) by using V_{bp} ;
- As in case of CTCB, maintain the ΔT between the supply and return GHe within 20 K by controlling the V_{FN} ($N=0-2$);
- In case of ACB-4, since it is foreseen that the SHe T upstream HX1 can be lower than the LHe T in PS1, to prevent cooling of PS1 (normally to be evaporated for heat exchange), HX1 is by-passed by opening V_{HX1} and closing V_{CCLin} .



4. Status of the Thermal Shield Cold Valve Box (TCVB)



Conclusion

- The ITER CD has been optimized with respect to its interfacing system process as well as clients' requirement changes and is in the final design (ACBs/TCVB) and manufacturing (CTCB) phase at Linde Kryotechnik.
- One CCL (TF) manufactured and tested, others in manufacturing phase at IHI
- The on-site delivery starts with the CTCB on May 2018 to match the commissioning of the three LHe plants' parallel operation. ACBs and TCVB will be delivered until late 2020, installed and commissioned to be ready for the ITER first plasma in 2025