

CEC - ICMC 2017, July
Madison, WI



**First operational experience with the
HIE-Isolde helium cryogenic system
including several RF cryo-modules**

Main author: N. GUILLOTIN

Co-authors:

T. Dupont

Ph. Gayet

O. Pirotte




Outline

- ❑ **Introduction**
- ❑ **First cryogenics operation in 2015 with 1 cryo-module**
- ❑ **Cryogenics operation in 2016 with 2 cryo-modules**
- ❑ **Upgrade during the Extended Year End Technical Stop 2016/2017**
- ❑ **Cool down and commissioning in 2017 with 3 cryo-modules**
- ❑ **Conclusion and next milestones**




HIE-ISOLDE Cryogenic System



✓ **Compressor station:**

Two-stage – 160g/s with HP @ 14bara and LP @ 1.04bara

✓ **Cold Box:** Sulzer TCF200 cold-box type with 2 turbines, refurbished for HIE-Isolde
[refrigerat. power ~630W @4.5K and He liq. rate ~1.5g/s]



First cool down in 2015 with CM1


□ Cool-down in five phases:

- ✓ Shield cool-down to 80K with **GHe**
- ✓ Vessel and frame cool-down to ~100K with **GHe**
- ✓ Cav. and solenoid cool-down to ~ 100K with **GHe**
- ✓ Vessel and frame cool-down to 4.5K with **LHe**
- ✓ Cav. cool-down and filling with **LHe** at 4.5K


Thermal gradients	Localisation	ΔT
Shield: Outlet - Inlet	★	< 50K
Frame	★	< 40K
Frame – Vessel	★	< 100K

□ 13 days for the CM1 cool down - June 2015

- ✓ Cool down phases managed manually;
- ✓ Basic interlocks to respect the temperature gradients;



2015 Operation with CM1



- ❑ Overheating of the ~10kW electrical heater in the cold box – by-pass return line;
- ❑ Burst of the CM1 rupture disk (> 2.5 barg) ⇔ combination of hardware/software unappropriated settings;
 - ↳ Quick and efficient repair

❑ From Sept. to Nov. 2015 (physics run) : availability of the cryo plant = 100% ✓

- ❑ Measure of CM1 static heat load : 9.5W at 4.5K (expected design value);
- ❑ Warm-up of CM1 ⇒ sent to the clean room to upgrade the RF couplers

2016 Operation with 2 CM

❑ **Compressor conditioning and CM1 + CM2 cool down hardly started in May:**

- ✓ CP Helium circuit with H₂O and N₂ pollution,
- ✓ CP flow limitation (140 g/s max)




❑ **14 days to cool down the shields to ~75K, due to:**

- ✓ Several unwanted stops of the compressor
- ✓ Unappropriated interlocks for CB and JB
- ✓ Process predominantly manual

❑ **2 additional weeks necessary to revise interlocks and process**


❑ **Then cool down with LHe:**

- ✓ **Not possible to fill in parallel the 2 CM with LHe**



❑ **Machine commissioning with CM1 + CM2**

Strong thermal and pressure oscillations in the 4.5K return **line D**
 ⇒ **tripping of the cavities**



Nominal operation: 60 W 50 W



❑ Capacity test: 220 W 120 W



➔ Oscillations reduced by **activating the elec. heaters in each vessel + opening (+10%) of the by-pass valve in the return box**

↪ Indication of bad LHe quality supply + high heat load in CDS



❑ **2016 availability of the cryo plant = 100%**





Upgrades during the Extended Year-End Technical Stop 2016/2017 (EYETS)

□ Endoscopic investigations of JB and TL:

- ✓ Revealed contacts of 4.5K pipes with Al shield




Direct contacts were suppressed (G10 or PTFE rollers), but not in all points of the line D (risk of breaking)



□ Review during the EYETS of the safety concept concerning :

- ✓ Global process ⇒ ease gas exhaust before a significant CM pressure increase;
- ✓ NO / NC valve status on all return lines up to Compressor;
- ✓ Installation of 2 additional safety valves ⇒ gradually release of over-pressure




□ Complete revamping of the process of Cold-Box and CDS (JB + TL)

- ✓ To optimise the cool down & nominal operation ;
- ✓ To allow quasi-automated restarts and cope with short stops of the cryo-plant ;

□ Complete revamping of the CS interlocks to avoid unwanted stops

Cool down and commissioning in 2017 with 3 cryo-modules

- ❑ CM1 & 2 were cooled & filled in parallel ;
- ❑ CM3 probably also filled, but issues with level transmitters ⇒ confirmed a few days later (after repair)




Phases	2016 2 CMs	2017 3 CMs
300K → 5K	≈ 15 effective days	≈ 9 effective days
LHe Filling (stable/reg.)	5 effective days	4h for CM1&2 + 4h for CM3

➡ **Proof of improvements executed during the EYETS** ✓




❑ Static heat load tests of CM (derived from level drops)

✓ 2016 : ~11W, shield actively cooled



LEVEL DROPS 2016: CM1 & CM2

✓ 2017 : ~13W, shield stopped, but issue with CM2 (3 times higher, investigations on going)



LEVEL DROPS 2017: CM1 & CM2 & CM3

❑ Capacity test : stable operation tested with 100 W in each CM ✓



Conclusion


- ❑ Long series of issues due to lack of time to commission the cryo-plant and the CDS with the associated control logic;
- ❑ Endeavors performed to diagnose and overcome issues like CDS have been efficient;
- ❑ Static heat load of CM are within design specification
- ❑ In 2015 and 2016: 100% of cryo availability during physics run

Next milestones

- ❑ Restore full performance of the CDS ⇒ repair during next YETS 2017/2018
- ❑ Review of the control logic of the CDS ⇒ taking into account lessons learnt during the last cool down
- ❑ Improvements ⇒ pollution issue in the compressor station, overheating of the heater in the cold box
- ❑ Commissioning of the dewar



**Thank you for your attention.
Questions ?**



Nicolas Delruelle took the responsibility of the HIE ISOLDE cryogenics system
from 2010 to 2015;
A special thought is brought to him.