






# CLIC status and plans

## Outline:

- Project overview and background, resources
- Main technical activities
- Implementation issues
- Summary

Parameter	Unit	380 GeV	3 TeV
Centre-of-mass energy	TeV	0.38	3
Total luminosity	$10^{34}\text{cm}^{-2}\text{s}^{-1}$	1.5	5.9
Luminosity above 99% of $\nu_s$	$10^{34}\text{cm}^{-2}\text{s}^{-1}$	0.9	2.0
Repetition frequency	Hz	50	50
Number of bunches per train		352	312
Bunch separation	ns	0.5	0.5
Acceleration gradient	MV/m	72	100
Site length	km	11	50



## Key features:

- High gradient (energy/length)
- Small beams (luminosity)
- Repetition rates and bunch spacing (experimental conditions)

## European Strategy for Particle Physics

### High-priority large-scale scientific activities

After careful analysis of many possible large-scale scientific activities requiring significant resources, sizeable collaborations and sustained commitment, the following four activities have been identified as carrying the highest priority (the point below is the one relating to very high energy machines)


d) To stay at the forefront of particle physics, Europe needs to be in a position to propose an ambitious post-LHC accelerator project at CERN by the time of the next Strategy update, when physics results from the LHC running at 14 TeV will be available.

***CERN should undertake design studies for accelerator projects in a global context, with emphasis on proton-proton and electron-positron high energy frontier machines. These design studies should be coupled to a vigorous accelerator R&D programme, including high-field magnets and high-gradient accelerating structures, in collaboration with national institutes, laboratories and universities worldwide.***

**Goal for next strategy update (~2019): Present a CLIC project that is a “credible” option for CERN beyond LHC, a Project Implementation Plan.**

### Guidelines used internally:

- Adapt to physics results – LHC mostly - taking into account LHC at 13-14 TeV as results become available (be flexible)
- Physics no later than 2035, solid luminosities from Higgs/top at 380 GeV to 3 TeV (staging)
- Initial costs compatible with current CERN budget level (order LHC+50%) (staging)
- Upgradable in 2-3 stages over a 20-30y period, without major (max 3-4 years) operational breaks, and with upgrade costs also in reasonable agreement with current budget level.
- Cover accelerator, detector, physics




Accelerator collaboration with ~50 institutes  
 Detector collaboration operative with ~27 institutes




## MTP 2016:

- 27/29 MCHF Material/Personnel 2017-19 for Linear Colliders
- Covering accelerator (~80%)
- Detector & physics (~20%)



Many commitments related to Xband structure and testing, various technical developments, plus the CTF3 programme in the years 2015-2017


Covers personnel and hardware, exchange/test of equipment being built in the collaboration – at CERN or locally, and around 80 ph.d student (estimate in 2014)



R&D contracts, UK (4), Oslo, Helsinki, Spain (3), Karlsruhe, Zurich



MoU annexes (with MS and NMS collaborators)



Annex to Int. Coll. Agreements (KEK, India, Pakistan, etc.)




Techn. Transfer agreements, “Work for Others”, EU projects (Tulip, SLAC, Fermilab, EUCARD, AERIS, etc.)



## Project wide studies:

- Overall project planning
- Cost, power, schedule, staging
- Civil engineering, conventional systems



### Parameters and Design


Integrated Baseline Design and Parameters

- Integrated Modeling and Performance Studies
- Feedback Design, Background, Polarization
- Machine Protection & Operational Scenarios
- Electron and positron sources, Damping Rings, Ring-To-Main-Linac, Main Linac - two-Beam Acceleration, Beam Delivery System
- Machine-Detector Interface (MDI) activities
- Drive Beam Complex



### Experimental verification

- CTF3 Consolidation & Upgrades
- Drive Beam phase feed-forward and feedbacks
- Two-Beam module string, test with beam
- Drive-beam front end including modulator development and injector
- Modulator development, magnet converters
- Drive Beam Photo Injector
- Low emittance ring tests
- Accelerator Beam System Tests (ATF and FACET, others)




### X-band Technologies

- X-band Rf structure Design
- X-band Rf structure Production
- X band collaborations
- Novel RF unit developments (high efficiency)
- Installation and Operation of High power Testing Facilities
- Basic High Gradient R&D



### Technical Developments

- Damping Rings Superconducting Wiggler
- Survey & Alignment
- Quadrupole Stability
- Warm Magnet Prototypes
- Beam Instrumentation and Control
- Two-Beam module development
- Beam Intercepting Devices
- Controls
- Vacuum Systems
- Beam Transport Equipment




### Detector and Physics





- Physics studies and benchmarking
- Detector Optimisation
- Technical developments

## Combining high precision performance with beam conditions at CLIC


(adapted from original designs of ILC detectors)



30




- Contain updated general information similar to CLIC CDR volume 3 (2012)
- New reference plots for power, costs, luminosities, physics, etc
- [Yellow report](#)



arXiv:1608.07537v2 [physics.acc-ph] 29 Aug 2016

CERN-2016-004  
12 August 2016

ORGANISATION EUROPÉENNE POUR LA RECHERCHE NUCLÉAIRE  
**CERN** EUROPEAN ORGANIZATION FOR NUCLEAR RESEARCH






**UPDATED BASELINE FOR A STAGED  
COMPACT LINEAR COLLIDER**

GENEVA  
2016

## Structure production and test programme:

- Point to address: Baseline structure statistics, 380 GeV and FEL structures, “simplified” structures (halves and brazing vs bonding, other R&D), industry qualification, conditioning studies, etc
- Can tests ~30-40 structures over next 3 years, currently 7 ready for tests and 6 in production



**Xbox-1**  
 CPI 50MW 1.5us klystron  
 Scandinova Modulator  
 RepRate 50Hz  
 Beam test capabilities

**Previous tests:**  
 2013 TD24R05 (CTF2)  
 2013 TD26CC-N1 (CTF2)  
 2014-15 T24 (Dogleg)

**Ongoing test:**  
 Aug 2015- TD26CC-N1 (Dogleg)



**Xbox-2**  
 CPI 50MW 1.5us klystron  
 Scandinova Modulator  
 RepRate 50Hz

**Previous tests:**  
 2014-15 CLIC Crab Cavity

**Ongoing test:**  
 Sep 2015- T24 OPEN




**Xbox-3**  
 4x Toshiba 50MW 1.5us klystron  
 4x Scandinova Modulators  
 RepRate 100Hz  
**RedRate 100Hz**

Medium power tests (Xbox-3A)  
 2015 3D-printed Ti waveguide  
 2015 X-band RF valve


Major increase in testing capacity





## Ultra precision machining

VDL, NL  
Yvon Boyer, FR  
LT-Ultra, DE  
DMP, ES  
Mecachrome, FR



## Additive manufacturing

3T RPD, GB  
Concept Laser, Protoshape DE  
Initial, FR

## Ceramics


Andalo Gianni, IT  
Macropierre, FR  
Ceratec, Friatec, DE  
ESK Ceramincs, DE

## Surface treatment

Multivalent, NL  
Thermocompact, FR  
Covimag, FR


## Waveguides and components

CINEL, IT  
CECOM, IT  
VDL, CH  
KERN, DE  
Radiabeam, US



## Brazing and bonding

Bodycote, FR  
Reuter, DE  
TMD, GB



CERN	XBox-1 test stand	50 MW	Operational
	Xbox-2 test stand	50 MW	Operational
	XBox-3 test stand	4x6 MW	Commissioning
KEK	NEXTEF	2x50 MW	Operational, supported in part by CERN
SLAC	ASTA	50 MW	Operational, one structure test supported by CERN
	Design of high-efficiency X-band klystron	30 MW	Under discussion
Trieste	Linearizer for Fermi	50 MW	Operational
PSI	Linearizer for SwissFEL	50 MW	Operational
	Deflector for SwissFEL	50 MW	Planning
DESY	Deflector for FLASHforward	50 MW	Planning (note first two may share power unit)
	Deflector for FLASH2	50 MW	Planning
	Deflector for Sinbad	50 MW	Planning

**CERN X-band Test Stands Summary:**

- Xbox-1:** CPIS 0 MW, Susiklystron, Scandinova Modulator, RepRate 50 Hz, Beamtest capabilities. Previous tests: 2013 D24R05 (CTF2), 2013 D26CC-N1 (CTF2), 2014-15 D24 (Dogleg). Ongoing test: Aug 2015 D26CC-N1 (Dogleg).
- Xbox-2:** CPIS 0 MW, Susiklystron, Scandinova Modulator, RepRate 50 Hz. Previous tests: 2014-15 CLIC Crab Cavity. Ongoing test: Sep 2015 D24 OPEN.
- Xbox-3:** 4x Toshiba 6 MW, Susiklystron, 4x Scandinova Modulators, RepRate 100 Hz. Medium power tests (Xbox-3A), 2015 D-printed waveguide, 2015 X-band RF Valve. Major increase in testing capacity.

### X-band test stands at KEK and SLAC

**Nextef facilities at KEK:** A large industrial facility with complex machinery and piping.

**ASTA at SLAC:** Two researchers standing next to a large piece of equipment.

**Nextef facilities:** A 3D architectural rendering of the facility layout.



**SLAC: CLIC Structure Conditioning X-band Architecture:** A diagram showing the X-band structure and conditioning process.

**Status:**

- All computation functionality in place
- Operating at 25 MW, 75 Micron
- Pulse length 200ns

**Other facilities:** Tsinghua University and SINAP have both ordered 50 MW X-band klystrons.

Australia	Test stand	2x6 MW	Proposal, loan agreement from CERN
Eindhoven	Compact Compton source	6 MW	Proposal, request for loan from CERN
Uppsala	Test stand	50 MW	Proposal, request for loan of spare klystron from CERN
Tsinghua	Deflector for Compton source	50 MW	Ordered
	Linearizer for Compton source	6 MW	Planning
SINAP	Linearizer for soft X-ray FEL	6 MW	Ordered
	Deflectors for soft X-ray FEL	3x50 MW	Planning
Valencia	S-band test stand	2x10 MW	Under construction
STFC	Linearizer	6 MW	Under discussion
	Deflector	10 MW	Under discussion
	Accelerator	tbd	Under discussion







**Solid State Modulator**  
Scandinova, SE



**Klystron**  
CPI, US  
Toshiba, JP



**Pulse compressor**  
DMP, ES  
Thermo Fisher, FR



**RF instrumentation**  
Rohde & Schwarz, DE  
ETL Systems, GB  
MegaPhase, US  
Pentair, DE,FR

**Vacuum components**  
SAES, IT  
VACOM, DE  
VAT, CH






- X-band technology appears interesting for compact, relatively low cost FELs – new or extensions
  - Logical step after S-band and C-band
- Use of X-band in other projects will support industrialisation
  - They will be klystron-based, additional synergy with klystron-based first energy stage
- Use of X-band in FELs (FEL collaboration)
  - Australian Light Source, Turkish Accelerator Centre, Elettra, SINAP, Cockcroft Institute, TU Athens, U. Oslo, Uppsala University, CERN, TU Eindhoven ... more


**FEL collaboration** dedicated to the development of inexpensive and compact X-ray sources, [Compton scattering and XFEL](#), for national, university and industrial scale facilities.

**Exploit** recent developments of X-band and high-gradient technology to:

- increase short pulse and high repetition rate performance
- decrease size and cost of photon-science infrastructure.

**Submit** a design study in INFRADEV-01-2017.







CTF3 remains the most crucial facility, but to be closed at the end of 2016

Installed 2-beam acceleration module in CTF3 (according to latest CLIC design)  
First 2-beam tests stand reached 145 MV/m (2012)






Phase feed-forward experiment



Dogleg Beam loading experiment



Diagnostics R&D using CALIFES


Linac

TBTS


TBL



TBL deceleration




Two Beam Module and Wake-field monitors



## Accelerator Test Facility ATF2

- Test facility for future linear colliders located in KEK in Japan
- **World record of smallest vertical beam size: < 45 nm (design is 37 nm).**
- First Final Focus beam line using a local chromaticity correction scheme.



Damping ring studies (example ALBA) incl. extraction

FACET at SLAC: beam based alignment and emittance studies



ATF2 at KEK: final focus studies





Technical Developments are motivated by several possible reasons – and are now quite mature:

- Key components for system-tests (example magnets, instrumentation, modules)
- Critical for machine performance (example alignment, stabilization, damping ring studies)
- Aimed at cost or power reduction (example magnets, klystrons, modules)




# Information about some relevant suppliers and subcontractors participating to prototypes procurement for the CLIC Magnets R&D phase



Note: majority of coils and of other components manufacturing, magnet assembly, was done by CERN apart for the DBQ magnets (EM and PM versions).

1) Main Beam Quadrupoles. 4 prototypes procured: 3 Type1 (the shorter), 1 Type4 (the longer)



### Relevant procurements:

- Coils: TESLA Engineering LTD, Storrington, West Sussex - UK
- High Precision quadrants machining: DMP 20850 Mendara, Gipuzkoa - ES


2) Drive Beam Quadrupoles (EM version): 3 prototypes procured by Daresbury Laboratory



### Relevant manufacturers:


- Complete manufacturing: Danfysik A/S 2630 Taastrup, Denmark

3) Drive Beam Quadrupoles (PM version): 2 prototypes procured by Daresbury Laboratory



Relevant manufacturers:  
- Design: PM  
- High precision EDM machining: SEN  
- TSV  
- Mc

5) Final Focus Quadrupole QD0: 1 prototype procured



### Relevant manufacturers:

- PM blocks, Permendur EDM machining: Vacuumschmelze GmbH & Co. KG, Hanau - D

4) Main Beam Steering Dipoles: 2 prototypes procured




6) Final Focus Sextupoles SD0: (1 prototype procurement on-going)



### Relevant manufacturers:

- Permendur and PM blocks procurement: VDL Groep BV, Eindhoven - NL

7) Octupoles for ATF facility at KEK, Japan: 2 magnets procured



### Relevant manufacturers:

- Coils: S.E.F. Sarl, Labège - F
- Iron Yokes EDM Machining: Röttgers Værktøj A/S Odense - DK



## 2013 - 2019 Development Phase

Development of a Project Plan for a staged CLIC implementation in line with LHC results; technical developments with industry, performance studies for accelerator parts and systems, detector technology demonstrators

## 2020 - 2025 Preparation Phase

Finalisation of implementation parameters, preparation for industrial procurement, Drive Beam Facility and other system verifications, Technical Proposal of the experiment, site authorisation

## 2026 - 2034 Construction Phase

Construction of the first CLIC accelerator stage compatible with implementation of further stages; construction of the experiment; hardware commissioning



## 2019 - 2020 Decisions

Update of the European Strategy for Particle Physics; decision towards a next CERN project at the energy frontier (e.g. CLIC, FCC)

## 2025 Construction Start

Ready for construction; start of excavations



## 2035 First Beams

Getting ready for data taking by the time the LHC programme reaches completion




Beyond the parameter optimization there are other on-going developments (design/technical developments):

- Optimize drive beam accelerator klystron system ([Syratchev](#)) – also for power
- Electron pre-damping ring can be removed with good electron injector
- Dimension drive beam accelerator building and infrastructure are for 3 TeV, dimension to 1.5 TeV results in large saving
- Systematic optimization of injector complex linacs in preparation
- Module optimisation studies






## P<sub>AC</sub> versus E<sub>CM</sub>



Power/energy reductions are being looked at:


- Machine parameters and technical developments (structures, RF systems and magnets)
- Consider where the power is dissipated (distributed or central)
- Look at daily and yearly fluctuation – can one run in “low general demand” periods
- Understand and minimize the energy (consider also standby, MD, down periods, running)



- Radio-frequency
- Magnets
- Cooling
- Ventilation
- Instrumentation & Controls
- Interaction area & experiments




## CERN energy consumption 2012: 1.35 TWh



ECFA- Linear Collider Workshop 2016



## CLIC Multi-beam (6/10 beams) pulsed klystron power balance diagram



I. Syratchev, June 2016, Santander, Spain

For the RF power sources:

Toshiba, Japan:

6 MW, 5 usec pulsed X-band klystron (4 units in operation)  
20 MW 150 usec pulsed L-band MBK (successfully tested at factory).

CPI, USA:

50 MW, 1.5 usec pulsed X-band klystron (2 units in operation)

Thales, France

20 MW 150 usec pulsed L-band MBK (under test at factory).

*Development of new high efficiency RF power sources for accelerators. CERN/Thales NDA to be signed soon.*

Microwave Amplifiers Ltd, UK:

New solid state X-band 300 W pre-amplifiers (4 units in operation).

New solid state X-band 1200 W pre-amplifiers (2 units ordered).

VDBT, Russia:

6 MW, 5 usec pulsed low (50 kV) voltage S-band MBK with PPM focusing. The first demonstrator of new klystron technology for the high efficiency (in operation).

For the modulators:

ScandiNova, Sweden:

430 kV, 300 A solid state modulator (2 units in operation)

150 kV, 190 A solid state modulator (4 units in operation)

Specific contracts with Univ. Groups for drivebeam modulator development (Zurich, Laval)

The goals and plans for 2016-19 are well defined for CLIC, focusing on the high energy frontier capabilities – well aligned with current strategies – also preparing to align with LHC physics as it progresses in the coming years.

Collaboration agreements in place:

- Many commitments related to Xband structure and testing, technical developments, plus the CTF3 programme. These commitments are covered by numerous R&D contracts and MoU annexes covering personnel and hardware, exchange/test of equipment being built in the collaboration, including many Ph.D students

The use of X-band structures and RF-sources in smaller projects of significant help to develop industrial and technical momentum

Thanks:

Slides/figures/advice from CLIC collaboration members. Knowingly from A. Latina, K.Kubo and ATF colleagues, D.Schulte, R.Corsini, W.Wuensch and X-band team, , F.Tecker, T.Lefevre, M.Modena, N.Catalan, C.Garion, H.Mainaud Durant and PACMAN team, R.Tomas, S.Doebert, L.Linssen, H.Schmickler, I.Syratchev, Y.Papaphilippou, G.D'Auria - and several more unknowingly or indirectly