



# Sub-system integration for the VBOX

**César Blanch Gutiérrez**


*On behalf of the Group of Accelerator Physics (IFIC)*

# Outline

- Layout and integration
- Vacuum subsystem:
  - Vacuum equipment and system description
  - Vacuum simulations
  - Vacuum simulations: upgrade studies
- Cooling subsystem
  - Cooling plant
  - Demineralizer plant
  - Control system






# Layout and integration

- 3D view of the VBOX lab



# Layout and integration

- Changes in the dimensions of the modulators



# Vacuum subsystem

- Ultra high vacuum system
  - Expected pressure  $\sim 5 \times 10^{-8}$  mbar
- Turbo pumping group for primary pumping
  - Pfeiffer HiCube 80, Duo 3



## Technical data

Backing pump	Duo 3
Cooling method, standard	Air
Flange (in)	DN 63 CF-F
Flange (out)	G 1/2"
Fore-vacuum safety valve	-
Mains requirement	230 V AC, 50/60 Hz
Pumping speed backing pump	2.5 m <sup>3</sup> /h
Pumping speed backing pump at 50 Hz	2.5 m <sup>3</sup> /h
Pumping speed for N <sub>2</sub>	67 l/s
Turbopump	HiPace 80
Type	Turbo pumping station
Ultimate pressure	$< 5 \cdot 10^{-10}$ hPa   $< 3.75 \cdot 10^{-10}$ Torr   $< 5 \cdot 10^{-10}$ mbar
Weight	40.1 kg   88.4 lb

Pumping time does not contain run-up time and desorption.


- Ready for gas (N<sub>2</sub>) venting
- Ready for leak detector connection

# Vacuum subsystem

- Ultimate vacuum performed by ion pump + NEG cartridge
  - Nextorr D 100-5 pump
    - Extremely compact and light pump (2,2 Kg )
    - Ion pump and NEG cartridge in the same element
    - High pumping speed for all active gases
    - Pumping also noble gases and CH<sub>4</sub>



Initial pumping speed (l/s)	Gas	NEG activated	NEG saturated
	O <sub>2</sub>	100	4
	H <sub>2</sub>	100	6
	CO	70	5
	N <sub>2</sub>	40	4
	CH <sub>4</sub>	15	5
	Argon <sup>1</sup>	6	6





# Vacuum subsystem


- Vacuum monitoring by ion pumps measurement and vacuum gauges
  - Full range Pirani/Bayard-Alpert gauges
  - From  $1 \times 10^{-3}$  down to  $5 \times 10^{-10}$  mbar
  - DN 40 CF flange
- All metal valves for pumping group connection
- He leak detector for vacuum leak tests
  - Minimum detectable leak rate  $5 \times 10^{-12}$  mbar\*l/s
  - Backing pump capacity: 15 m<sup>3</sup>/h
  - Pumping speed for He: 2,5 l/s
  - Possible to work standalone or connected to the turbo pumping group



# Vacuum subsystem

- System description



- Not vacuum sectored
- 6 pumping ports
- 6 Nextorr pumps
- 6 Vacuum gauges





# Vacuum subsystem

- Vacuum simulations
  - Monte-carlo simulations performed with Molflow software
  - Simulations of effective vacuum pumping speed in the pumping port for  $H_2$ (dominant gas) at molecular flow




- DN35 diameter cross
- Effective pumping speed in pumping port : 38 l/s

# Vacuum subsystem

## Vacuum simulations

- Apply the obtained effective pumping speed into the pumping ports
- Estimated outgassing rate:  $3 \times 10^{-10}$  mbar\*l/s/cm<sup>2</sup>
- Pressure profile inside the wave guides obtained






- Max. pressure:  $4 \times 10^{-7}$  mbar
- Min. pressure:  $5 \times 10^{-8}$  mbar

# Vacuum subsystem

- Vacuum simulations
  - How can we get lower pressure if needed?
    - Adding pumps and therefore pumping ports (expensive)
    - Changing the current pumps for “bigger” ones (expensive)
    - Improving the effective pumping speed (“cheap”)
    - Reducing the outgassing (cleaner elements, bake-out, etc)

# Vacuum subsystem




- Vacuum simulations – “Bigger” pumps
  - Higher pumping speed pumps would make the effective pumping speed to increase too (not linealy)
  - Effective pumping speed: 100 l/s



- Some improvement in the vacuum level

# Vacuum subsystem




- Vacuum simulations - Pumps addition
  - Where to add the pump? Where the pressure is higher
  - Higher improvement in the vacuum level than using bigger pumps





# Vacuum subsystem

- Vacuum simulations – improving eff. Pumping speed
  - Increase  $S_{eff}$  by increasing the volume of the chamber where the pump is and therefore the conductance







# Vacuum subsystem

- Vacuum simulations – improving eff. Pumping speed


DN35 diameter cross.



DN63 diameter cross




DN100 diameter cross




- Simulations show a lower final pressure when using DN63 instead of DN35
- Less improvement from DN63 to DN100

# Vacuum subsystem


- Installation and vacuum tests
  - Installation in the lab already in progress
  - We found difficulties to leak tight the wave guides using the copper gaskets provided by Mega Industries
  - A later study showed us that the Mega gaskets are too hard and the flange cannot deform the gasket enough to make a good seal
  - A heat treatment (annealing) to the gaskets is missing
  - Mega Industries admitted the mistake during the production process and will provide us a new gaskets set with the annealing done



CERN gasket



Mega Industries gasket



# Vacuum subsystem

- Installation and vacuum tests

- While waiting for the new gaskets a 1/3 of the waveguides line is already installed using old gaskets
- Already under vacuum
- Pressure  $\sim 5 \times 10^{-8}$  mbar  $\rightarrow$  confirms the vacuum simulations




# Vacuum subsystem

- Summary

- Expected pressure  $\sim 10^{-8}$  mbar
- Pressure profile obtained and the higher pressure zone was localized
- Upgrade studies done in order to improve the vacuum level if needed
- Changing the pumping cross size is a cheap way to get higher effective pumping speed and improve the vacuum
- To change to bigger pumps doesn't seem to be the best option since the ratio price/improvement is not the best.
- Adding a new pumping port makes the highest improvement but it is more expensive
- We found a problem with the gaskets-> solution is on going
- 1/3 of a waveguide line already installed and under vacuum confirms the simulations


# Cooling subsystem

- Used to cold down modulators, klystron and RF water loads
- Cooling plant + water demineralizer plant
- Cooling plant
  - 165 KW max. cooling power machine
  - 2 water closed circuits + heat exchanger






- Cooling plant
  - Primary circuit
    - Cooling machine and pumps installed in the roof of the building
    - Chiller has 3 compression stages for better performance and power save.
    - Temperature range inlet-outlet in the cooling machine 12°C / 7°C
    - Runs normal network water
    - Temperatures and pressures monitored
    - Automated 3 ways valve to adjust the flow passing through the heat exchanger





# Cooling subsystem

- Cooling plant
  - Secondary circuit
    - Feeds independently both modulators+klystrons and the RF loads
    - Pumps and heat exchanger installed in the basement of the building
    - Temperature range inlet-outlet in the heat exchanger 28°C / 18°C
    - Runs demineralizer water
    - Temperatures, pressures, flows and water conductivity monitored
    - Automated valves adjust independently the flow of each modulator



# Cooling subsystem


- Cooling plant
  - Demineralizer plant
    - Integrated within the cooling system
    - Provides demineralized water to the secondary circuit
    - Klystrons need low conductivity water for cooling ( $0.1 - 1 \mu\text{S}/\text{cm}$ )
    - Water softener + reverse osmosis
    - Final ultra pure water with conductivity:  $0.1 \mu\text{S}/\text{cm}$



- Control system and operation
  - PC interface
  - Integrates and control both cooling circuits and demineralizer plant
  - Allows to adjust diary working schedule to automatically start/stop the system


- Primary circuit control

- Monitor the cooling machine
- Automatically fill up the circuit if it is necessary
- Allows to setup the pressures
- Controls the 3 ways valve in order to get the water temperature set up in the secondary at the exit of the heat exchanger



# Cooling subsystem

- Secondary circuit and demineralizer plant control
  - Monitor the water conductivity and recycle the water if it is over the limit
  - Automatically fill up the circuit if it is necessary
  - Controls the pump speed and allows to set up the modulators inlet pressure
  - Allows to set up independently the flow in each modulator
  - Monitor pressure and temperatures



# Cooling subsystem

- Summary
  - 2 closed circuits + heat exchanger
  - Demineralizer plant providing water with  $0.1 \mu\text{S}/\text{cm}$
  - Allows to monitor, set up and control pressures, temperatures and flows in both circuits
  - Controls the demineralizer plant
  - System is under commissioning right now
  - Tested without modulators
  - Still need to do test with modulators

**THANK YOU FOR  
YOUR ATTENTION**