

# Review of CLIC-ILC collaboration on technical subjects

### (accelerators)


### and ways to improve the collaboration

Jean-Pierre Delahaye, Marc Ross Nick Walker Akira Yamamoto

• • `		th strong synergy	
	Working Gro	oups & Convener	$CLIC \leftarrow CLIC \leftarrow $
1	<b>Civil Engineering &amp;</b> <b>Conventional Facilities</b>	C.Hauviller, J.Osborne.	J.Osborne, V.Kuchler
2	Cost & Schedule	K.Foraz, G. Riddone, P. Lebrun	J.Carwardine, P.Garbincius, T.Shidara
3	Beam Delivery System (BDS) & Machine Detector Interface (MDI)	D.Schulte, R.Tomas Garcia, Lau Gatignon	B.Parker, A.Seryi
4	<b>Positron Generation (new)</b>	L.Rinolfi	J.Clarke
5	Damping Rings (new)	Y.Papaphilipou	M.Palmer
6	Beam Dynamics	D.Schulte	A.Latina, K.Kubo, N.Walker
7 (	Physics & Detectors ERN, June 12, 2009	L.Linssen, D.Schlatter	F.Richard, S.Yamada



## Overview:



#### Top 2 WG: CES/CFS & C/S

- CLIC CES / ILC CFS
  - Events, activities, mandate, concerns
- Cost / Schedule
  - Mandates
  - Tools
  - Risk analysis
  - Schedule
  - Issues
  - Plans
  - Links

#### Four Accel WG:

• e+

- Events, activities, mandate, concerns
- BDS/MDI
  - ..
- DR
- Beam Dynamics

Conclusions and Recommendations


## **Outline of CLIC-ILC Activities**

### **Conventional Facilities: ILC-CFS & CLIC-CES**


- also cooperative activities with XFEL and Project X
- 3 D Modeling for Civil Engineering & Installation
- Transportation & Installation
   of Equipment
- Cooling and Ventilation
- Interaction Region Design
- Joint Safety Document
- Cost Estimating methodology CERN, June 12, 2009

#### Cost & Schedule WG:

- Goal: compare cost estimates by the end of 2010 using similar methods and metrics
- Gave ILC RDR cost estimate & backup info for BDS to CLIC
- Cost Templates & Tools similarities & differences
- Common Risk Document
- Common Scheduling Methods
- Common Conventional Magnet
   Estimating Methods




## ILC 3d modelling – CES/CFS




#### **CLIC-ILC-DESY** Cooperation

### **CES/CFS:** Tunnel Configuration Cooling, Ventilation, Installation



#### CLIC VENTILATION ALTERNATIVES


IL




Layouts developed for CLIC & ILC are mutually assisting design process for both projects

Common study on the single tunnel layout and the safety issue

## CLIC 3d layouts for turnaround regions




## **Draft** CLIC-ILC Cost & Schedule Working Group Mandate – May08




- Compare the **assumptions and methodology** adopted by both projects in matter of cost.
- Establish functionalities for cost data analysis:
  - Parametric cost models to define variation of costs as a function of the main parameters
  - Risk/uncertainty assessment.
- **Compare costs for certain items** (to be defined with the agreement of management) to better understand the difference subsystem by subsystem between the two technologies
- Develop *common approaches* to traceability, requirements, cost estimates, and the bases of estimates.
- Compare the basic assumptions and baseline units for schedule.

## Cost Estimating Tools & Methods



- ILC using Triad Project Management, Inc.
  - Developing ILC Cost Estimating Tool (ICET)
    - WBS- linked Excel Cost Estimating Modules (CEMs)
    - mySQL DataBase => Reports
    - Store CEMs and Reports in ILC EDMS at DESY
- Differences with CLIC approach:
  - CLIC has 3 TeV & 500 GeV estimates under each item
  - ILC does not include any scheduling information
    - Triad believes this is better done in scheduling tool such as MS Project or Primavera which link back to ICET CEMs
  - Under a given item's cost data, CLIC includes:
    - industrialization and tendering, procurement, reception, installation, and commissioning
    - ILC includes these as separate items

CERN, June 12, 2009



## **ICET Cost Estimate Module exam**

Type a

Microsoft Excel - Cryomodules Pormat Tools Data Window Help E File Edit View 🗋 📴 🚽 👌 🔄 🔕 🔇 🖤 🎎 | 🖌 📭 隆 + 🟈 🔊 - 🔍 - 🔗 🗞 5 - 21 👬 🙀 64% - - 🞯 🖕 Calibri • 12 • B I U 三 三 三 函 \$ % • 18 🔐 筆 筆 🖽 • 🖄 • 🗛 • A1 fx -BASIS OF ESTIMATE (Creomodules.zis) 2 3 Total Cost **Total Cost Vith Risk** Description: CM without Quad - 9C0Q (3/1: use for e+ 8C0Q to view more Material Material (US K Dollars) Eng (hrs) (US K Dollars) Reference Name Eng (hrs) details, click: RAND TOTA 6 077 587 0.00 6.089.742.30 0.00 Estimated by 6 Prepared by: Date of Estimate 8 <1.03.03.02 http://www-ilcdcb.fnal.gov/example 26march09-Construction.xls Code: 9 Tags 9 10 Diction 11 12 13 13 14 15 16 17 18 Basis Risk **Risk Factor** Risk Percentage Total Technical Cost Schedule 19 20 21 22 Line Items - can reference a 23 Comments 24 **Cost Component or a Part** 25 26

5


27

CERN, June 12, 2009

28															
29		Fized Cost incem			Total Cost			Total Cos							
							Ezchange								
				Unit of			Rate to			Material			Material		
30	Name	Qty	Risk %	Estimate	Material Cost (K)	Currency	dollars	Eng (hrs)		(US K Dollars)	Eng (hrs)		(US K Dollars)	Eng (hrs)	Entered By
31	Supporting Items and Systems														
32	Cavity Materials, Production, & Preparation (Yield)		20%							0.00	0.00	0.00 \$		0.00	
33	Niobium RRR300	9	20%		\$158,929	Dollars	1.00			1430358.75	0.00	0.00 \$	1,433,219.47	0.00	
34	Niobium RRR30 (Reactor Grade)	9	20%		\$7,763	Dollars	1.00			69862.50	0.00	0.00 \$	70,002.23	0.00	
35	Niobium Titanium	9	20%		\$2,076	Dollars	1.00			18680.63	0.00	0.00 \$	18,717.99	0.00	
36	Cryoperm	9	20*		\$5,434	Dollars	1.00			48903.75	0.00	0.00 \$	49,001.56	0.00	
37	Machining	9	20%		\$66,094	Dollars	1.00			594843.75	0.00	0.00 \$	596,033.44	0.00	
38	Assembly & Electron Beam Velding	9 4	20%		\$19,418	Dollars	1.00			174757.50	0.00	0.00 \$	175,107.02	0.00	
39	Cavity Preparation	9	20%		\$140,524	Dollars	1.00			1264713.75	0.00	0.00 \$	1,267,243.18	0.00	
40	Per Cavity (not dependent on Cavity Yield)									0.00		1	; -	0.00	
41	Titanium Vessel	9	20%		\$29,457	Dollars	1.00			265113.00	0.00	0.00 \$	265,643.23	0.00	
42	Magnetic Shielding	9	20%		\$1,917	Dollars	1.00			17253.00	0.00	0,00 \$	17,287.51	0.00	
43	HOM Coupler	9	20%		\$0	Dollars	1.00			0.00	0.0	💊 🍤.00 🛊		0.00	
44	Tuner Mechanics	9	20%		\$34,506	Dollars	1.00			310554.00		0.00 \$	311,175.11	0.00	
45	Tuner Electronics	9	20%		\$16,052	Dollars	1.00			144463.50		A0.000	144,752.43	0.00	
46	Piezo Tuner	9	20%		\$2,250	Dollars	1.00			20250.00	0.00	0.4	20,290.50	0.00	
47	Cavity String Assembly (pro-rate per cavit	9	20%		\$63,000	Dollars	1.00			567000 49	0.00	0.00 \$	568,134.00	0.00	
48	Power Coupler	9	20%		\$103,775	Dollars	1.00			922 71 40	0.00	0.00 \$	935,838.44	0.00	
49	Cavity Control	9	20%		\$7,979	Dollars	1.00			12 .50	.00	0.00 \$	71,950.11	0.00	
50	Cryostat									0.00		4		0.00	
51	Vacuum Vessel and Cold Mass	1	20%		\$118,397	Dollars	1.00			118397,09	0.00	0.00 \$	118,633.79	0.00	
52	Module Beam Pipe Connection	1	20%		\$22,241	Dollars	1.00			222 0.0	0.00	0.00 \$	22,284.98	0.00	
53	Module Instrumentation	1	20%		\$1,300	Dollars	1.00			00,00	0.00	0.00 \$	1,302.60	0.00	
54	Module Connection	1	20%		\$3,119	Dollars	1.00			3118.50	0.00	0.00 \$	3,124.74	0.00	
55	SC Magnet, Corrector, BPM Package	0	20%		\$0	Dollars	1.00			0.00	0.00	0.00 \$		0.00	
56										0.00		4		0.00	
57					1					0.00		4		0.00	
58					1					0.00		4		0.00	
14	K + > H\ Sheet1 / Sheet2 / Premiu() CM_9COQ / CM_8C1Q / CM_8C1Q / CM_6C6Q / Definitions / TEMPLATE /											· ·			
Manual Antional Antio															
Rea	Ready														


Cost Component sheet for a specific cryomodule type

## Common Scheduling Methodology MS Project => Primavera



- Martin Gastal (CERN) did construction schedule in ILC RDR
- Katy Foraz (CERN) applied LEP-LHC experience & Amberg underground construction added more details + installation
- Assumed unlimited resources (technically limited)
  - 9 TBMs 120 m/wk excavation, 400 m/wk outfitting
  - # crews: 24 electrician, 12 cool & ventilate, 12 installation
  - all components available for installation when scheduled
- *6 years* groundbreaking to installation complete
- more realistic manpower, e.g.  $\frac{1}{2}$  install crews => 8.5 years
- How can commissioning vs. construction be optimized?


CERN, June 12, 2009



9

10

## LC - Machine installation




#### Assumptions: unlimited resources !!!! In summary for 7 years installation 9 TBM, 24 electricians teams, 12 cooling and ventilation teams, 12 teams for machine installation

••••• Support installation and alignment (250m/wk)


Machine inst.: transport and interconnections (progress rate to be confirmed 100m/wk)

maybe more realistic: -4 TBM, 8 elec, 4 hvac, 2 mach inst => 8.5 yrs
 CERN, June 12, 2009

#### **CLIC Machine installation**







- V CLIC-ILC Cost & Schedule Working Group WEBEX Meetings 1400 GMT - 2<sup>nd</sup> Thursday of each month
- **V** Keep work towards cost estimate mutually transparent
- Profit by synergies
- V Understand and communicate unavoidable differences in the methodologies used for the two projects
- V Construction & installation schedules for CLIC & ILC w same methodology 6/09
- Common ILC/CLIC notes (for mid '09)
  - Tunnel safety underground compliance *defer to:* Fabio Corsenego - ILC-CFS and CLIC-CES groups
  - Standardization methods to estimate cost of warm magnets including cabling and power supplies – Braun & Garbincius gathering materials, but international magnet fabrication experts – *are just not available! - defer*
  - Description of cost risk assessment Lebrun, Riddone, Lehner, Garbincius reviewed other applications, started outlining this mgt – outline soon!

#### Undulator-based source

#### Listing of ongoing activities

Develop Geant4 model of collimator, target, capture optics, and capture RF assembly (with CI)

Positron target tests at CI

Optimise parameters wrt yield, polarisation (with ANL)

#### Compton source

Design of the Compton ring (with NSC KIPT) Optical stacking cavity (with LAL and KEK) Stacking simulations (at CERN)

#### Lithium lens capture

"ILC/CLIC e<sup>+</sup> generation" working group

Evaluate suitability for Undulator and Compton schemes (with KEK, BIPN and Cornell)

#### Conventional sources (Conventional targets and hybrid targets)

Simulations (Geant4) to optimize the unpolarized e+ yield with hybrid targets ( with LAL)

Simulations (FLUKA) to optimize the beam energy deposition in targets (with Ankara Uni.)

Tests of e+ target at ATF and KEKB

#### **Electron source**

Tracking studies (with SLAC) Preliminary HV tests for the DC gun at JLAB and SLAC Implementation of the polarized e- source to produce the nominal charge at SLAC CERN, June 12, 2009



The ILC study considers the Undulator option as the base line while the Compton schemes are alternative options. The CLIC study considers the Compton schemes as the base line while the Undulator is an alternative option. Additionally, both projects are interested in the development of conventional sources (ILC as an auxiliary source and CLIC as an alternative baseline).

The working group should:

- Develop the synergy between the ILC and CLIC e<sup>+</sup> studies.
- $\succ$  Evaluate the common technical issues related to both options for the production of polarized positrons.
- ➢ Prioritize R&D.
- $\succ$  Review the existing technical and tests facilities where further tests could be performed.
- > Evaluate where cost savings could be obtained.
- Promote common meetings and workshops.

# Beam Delivery System WG On-going activities

- Collimation review: performance, wakefields and secondary particles
- Final Focus system review: new optics, optimization and tuning performance
- ATF2 ultra-low beta: Optics design, optimization and tuning performance (new CERN PhD student)
   Post-collision line: background to the detector

# Beam Delivery System WG Ongoing Activities

- -- Ongoing visit of Alain Herve to SLAC to work on push-pull design, detector motion system and shielding system, which is a common issue with CLIC; It is planned to have also colleagues from DESY and FNAL to come to SLAC, to join the work on push-pull IR;
- -- plan to have working meeting at SLAC for beam dump, which can be considered a common activity with CLIC.
- -- CLIC colleagues evaluating longer L\* design and studying FFS tolerances, an optimized design need to be done;
- -- low beta optics for ATF2 further investigated, together with large aperture SC FD for ATF2;

## The major focus of report on ALCPG and CLIC09 will be IR design progress.

CERN, June 12, 2009

## -Current – Future Events

Mini-Workshop on the CesrTA Electron Cloud R&D Program for Linear Collider Damping Rings (CTA09), June 25-26 2009, Cornell

- □ Discussion on current and future experimental studies of common interest in Cesr-TA (e<sup>-</sup>-cloud, low-emittance stabilization)
- Extending the collaboration in other subjects
- 2009 Linear Collider Workshop of the Americas, September
   29-October 3 2009, Albuquerque, New Mexico
  - □ Session on damping rings
- CLIC workshop 2009
  - □ Session on damping rings

ILC/CLIC DR working group

Discussions for a CLIC-ILC damping rings' workshop beginning 2010 CERN, June 12, 2009



e<sup>-</sup>-cloud

- □ Cesr-TA vacuum chamber sent to CERN, coated with a-C and returned to Cornell
  - Beam measurements (SEY, PEY) expected end of July
- Simulation work using CERN codes for electron cloud built-up (ECLOUD) and instability dynamics (HEADTAIL)
- Stabilization
  - Mostly connected to LINAC activities but experimental methods and diagnostics (BBQ) useful for damping ring studies
- Wigglers
  - Discussions for installing super-conducting wiggler prototypes (e.g. the one built and currently measured at BINP) in Cesr-TA, ATF
- IntraBeam Scattering
  - Discussions for triggering IBS dominated beam conditions in Cesr-TA for experimental work

ILC/CLIC DR working group




Develop synergies and collaborate in beam dynamics and technical issues of common interest in damping ring design

Mandate

- Use common research approaches and studies when possible including numerical tools
- Take advantage of existing test facilities or storage rings and participate in a common experimental program
- Trigger communication, establish links between the two communities, share knowledge and document common work CERN, June 12, 2009

- Original mandate kept
- ILC and CLIC damping ring designs differ as driven from different main linac RF systems, **BUT**, majority of damping ring issues are generic
- Work more actively especially in experimental facilities (Cesr-TA)




- Workload for both ILC and CLIC damping ring activities does not much available manpower
- R&D experimental program of Cesr-TA extremely demanding for the 2-years' allocated time-scale
   Necessary to be extended to accommodate further experimental studies interesting for both CLIC and ILC

# Damping Ring Working Group

- Also formed in November 08
- Strong RD focus (Palmer)
  - Steady progress; alpha carbon chambers shipped from Cern to Cornell; simulation team started
  - Other topics weaker, but expect leverage-low emittance tuning, fast ion
- No regular meetings, but three face-face meetings planned:
  - CTA09 (late June at Cornell)
  - DR09 at ALCPG
  - Late Jan 2010
- TDP2 / CDR design work also has strong overlap resources needed to engage


## Some Ongoing Studies – Beam Dynamics WG



- **U** CLIC main linac has strong wakefield and dispersive effects
  - Excellent benchmarking case
  - Complements previous benchmarking on ILC linac
  - CLIC case presented in ILC beam dynamics meeting
  - Waiting for results
  - Machine modelling ٠
    - Pre-alignment and survey
      - Full model studies performend for ILC and CLIC, potential of synergy (common data format?) to be explored
      - Work on solenoid field impact for CLIC has potential synergy with ILC
  - PLACET is developed in common effort with contributions from both sides ٠
    - Used for ILC RTML
    - E.g. our halo generation modules are being extended to cover ILC like cavities
    - Benchmarking with ELEGANT
  - Discussion of RTML rational and performance for ILC and CLIC (started at CLIC08) ٠
    - Currently functional CLIC RTML design is being made
    - Comparison of system design, identification of common issues and differences, e.g. presentation in ILC meeting
    - An important common problem are stray fields
      - Address by common data collection and measurements




## Summary



- 1) Expanding the mandates of the working groups, including a general review of the success (or lack of success) of each over the last year and the plans for the meetings this fall. *We may choose to recommend the consideration or adoption of specific tasks*. It may prove useful to adopt more a formal management approach on key issues
  - discuss the general scope of the planned effort and the available resources esp. Cost & Schedule
  - propose a prioritization process so that if we wished to have a more inclusive mandate – there would be some direction and some mechanism for developing one.

## Summary (2)



- 2) Expanding the number of working groups, including groups which are not strictly balanced.
- 5 possible additional WGs:
  - Beam instrumentation,
  - Alignment & Stability,
  - Machine Protection system,
  - Klystrons (L band) & Modulators with long pulses and high efficiency,
  - Operational & reliability issues.