

Current Status of Experimental Facilities at RAON

Young Jin Kim

Rare Isotope Science Project (RISP)

Institute for Basic Science (IBS)

EMIS XVIII

September 16-21, 2018




Contents

- Overview
 - Rare Isotope Science
 - RAON Accelerator and RI Production System
 - RAON Experimental Facilities
 - Development Plan
- Current status
 - KOBRA
 - LAMPS
 - HPMMS
 - CLS
 - NDPS
 - μ SR
 - BIS
- Schedule
- Summary

Rare Isotope Science

Nuclear Physics




- Structure of exotic nuclei
- Properties of exotic nuclei: masses, radii, life-time etc.
- Search for super heavy elements
- Nuclear theory: nuclear force, nuclear model

Nuclear Astrophysics



- Stellar evolution
- Nucleosynthetic processes under stellar environments
- EoS of asymmetric nuclear matter such as neutron stars

Applications



- Bio-medicine & Breeding
- Material sciences
- Nuclear data for next generation nuclear power plant
- National security


• RISP = Rare Isotope Science Project (2011. December - 2021. December)

- Plan & build Rare Isotope accelerator and experimental facilities in Korea


• RAON = Rare isotope Accelerator complex for ON-line experiments

- Provide that one could access to unexplored regions of the nuclear chart
→ More exotic, More intense, and More various Rare Isotope Beams (RIBs)

RAON Accelerator & RI Production




RAON Experimental Facilities



- Budget
 - Total: 418.4M US\$
 - RI production system: 57.9M US\$
 - Experimental system: 22.4M US\$

Plan for Development of Experimental Systems



~ 2016	2017	2018	2019	2020	2021	2022	2023
Stage1 : ISOL, IF, KOBRA, LAMPS, HPMMS (MR-TOF)							
			Stage2 : CLS, μ SR, Bio-medical, Nuclear Data				
Staged Approach						Stage 3: upgrade, new facilities	



- KOBRA Collaboration
- LAMPS Collaboration
- MR-ToF-MS, Gamma Array (KEK)
- Detectors & DAQ (GET Collaboration, TRIUMF, etc.)
- UC_x target (KNF, ISOLDE)
- ISOL RH (TRIUMF & J-PARC)
- ISOL TIS (TRIUMF, ISOLDE)
- EBIS (BNL)
- IF target test (BINP)
- IF magnet (KERI)
- and more
- **Established**
- RAON User Liaison Center
- RAON Users Association
- They cooperate with RISP to develop experimental system, training students, looking for international collaborations

KOBRA (Korea Broad acceptance Recoil spectrometer and Apparatus)

Conceptual design 2011 ~ 2012	Prototype & Test ~ 2017.9	Manufacturing ~ 2019.4	Installation & Commissioning ~ 2020.12	Operation 2021.1 ~
----------------------------------	------------------------------	----------------------------------	---	-----------------------



PPAC

- We have two 10 x 10 cm², two 20 x 20 cm², one 40 x 20 cm² active area PPACs
- Position resolution: < about 0.7 mm in FWHM, (C₄H₁₀ gas, ²⁴¹Am)
- Four 10 x 10 cm² and one 40 x 20 cm² PPACs will be produced

SSD

- We have two 5 x 5 cm² active area, 50 μm-thick, 16 channel SSD
- Energy resolution ~ 0.7%, S/N ~ 272 for 5.486 MeV α in vacuum

Plastic scintillator detectors

- We have one 10 x 10 cm² active area, 100 μm thick both side readout plastic detector
- Time resolution < 42 ps for 5.486 MeV α in vacuum
- One 10 x 10 cm² active area, 100 μm thick one side readout plastic will be produced



HPGe gamma ray detectors

- 32 segmented HPGe detectors (6set)
- Compton suppressor BGO crystals (6set)
- Complete set of TIGRESS electronics

• Multi-purpose experimental instrument using stable or rare isotope (RI) beams for nuclear structure and nuclear astrophysics Studies


- RI beam productions using stable or rare isotope (RI) beams
- Recoil mass separator
- High-resolution spectrometer, and so on

- The first part of stage 1 (stage 1 part 1) has been contracted with foreign and domestic companies in April 2018, and production is ongoing
- The present design of the second part of stage 1 (stage 1 part 2) was finally decided among the various design options in June 2018 by consultation with domestic potential users, and now bidding is ongoing
- Stage 1 will be installed in Low Energy Experimental room (E1) until the end of June 2020
- The commissioning of Stage 1 will be started from beginning of 2021 with stable ion beam

LAMPS (Large Acceptance Multi-Purpose Spectrometer)


Conceptual design 2011 ~ 2012	Prototype & Test ~ 2018.12	Manufacturing ~ 2020.12	Installation ~ 2021.7	Commissioning ~ 2021.12	Operation 2022 ~
----------------------------------	--	----------------------------	--------------------------	----------------------------	---------------------

- Nuclear matter and nuclear reaction studies with intermediate energy stable and rare isotope beams, especially nuclear symmetry energy at supra-saturation density via heavy-ion collision (e.g. measure n/p ratio & collective flow at the same time in the combination of $^{106,112,124,130,132}\text{Sn} + ^{112,118,124}\text{Sn}$)




- **Beam Energy: up to 250 MeV/u for ^{132}Sn ($\leq 10^8$ pps)**
- **Solenoid Spectrometer**
 - Max. 1T solenoid magnet
 - TPC ($\sim 3\pi$ sr acceptance, charged particle tracking)
 - Scintillation counter (trigger & ToF)
- **Neutron Wall (neutron tracking)**
- All of LAMPS system will be ready by 2020
- Start installation from 2021 then standalone commissioning during 2021

Solenoid Magnet



- Almost completed design of cylindrical superconducting magnet
 - 3200 mm (D) x 3320 (L)
 - Coil-turn starts from 850 mm in radius
 - Max. B-field ~ 1 T, Operation B-field = 0.5 T
 - $\Delta B/B \sim 1.87\%$, current 131.2 A
- Procurement will be started next year

Time Projection Chamber



- Test with prototype of TPC completed
 - Fulfill the requirement of TPC
- Based on test results, change TPC design
 - Both side readout \rightarrow one side readout
 - P-10 gas \rightarrow P-20 gas
- Construction and tested from 2019 to 2020

Forward Neutron Detector Array



- Completed all R&D processes
- Detector production in progress
 - 2 veto detectors (total: 20)
 - 148 neutron detectors (total: 160)
- Array frames are in house
- Finish integration & test by the middle of 2019

High Precision Mass Measurement System (MR-ToF)

Conceptual design

Manufacturing & Test

Installation

Commissioning

Operation

2011 ~ 2012



~ 2019.12

~ 2020.12


~ 2021.12

2022 ~


- Multiple Reflection ToF Mass spectrograph, chosen for mass measurement of unstable nuclei with short life time of < 100 ms and with sufficient precision of better than 10^{-6}



A picture of MR-ToF-MS system and others at RISP-KEK/WNSC




Gas cell (catcher)



MR-ToF (analyzer)


MR-ToF-MS construction under the collaboration

- R&D work, led by WNSC MR-ToF group (Leader : Prof. Wada)
- Additional beam line to the MR-ToF-MS, already constructed (2017)
- Differential pumping system, gas cell (or catcher), Trap system, and MR-ToF analyzer have been assembled, waiting for offline ion source test
- Test of the differential pumping system with the gas cell filled with 1 mbar helium gas, performed : 3.4×10^{-4} Pa upstream side
- Optimizing the beam transmission through the ϕ 2-mm gas cell hole, performed : 72% efficiency, but will be improved by additional beam steerer





Trap system

CLS (Collinear Laser Spectroscopy)




Measurement of the electron energy levels of rare isotopes produced in RAON

- Tool to acquire information on nuclear charge distribution, nuclear spins, nuclear shape, etc.
- Study the nuclear structure or verify the accuracy of nuclear models



• Components

- Optical sources and spectroscopy system
- CLS beam line: Deflector, Neutralizer, Fluorescence detector




• Main Specifications

- Resolution: ~ 10MHz @ E=40keV and ΔE=1 eV
- Wavelength range: UV, VIS, IR
- CLS beam line including 10°-deflector, neutralizer, and reionizer etc.

- Laser system is already procured
- Conceptual design of the CLS beam line is finished
- Resume development works from 2019


NDPS (Nuclear Data Production System)



- **Fast neutron nuclear data production system for developing next-generation nuclear power plant**
 - fast neutron production system
 - fast neutron ToF and Fission cross-section detection system

• Main Specification

- n-ToF system: 5 m and 20 m (Extendable ~ 70 m)
- Neutron beam: ≤ 53 MeV pulsed beam (white)
- Repetition rate: 300 kHz ~ 1 MHz
- Beam intensity: 2×10^{12} neutron/sr/ μ C
- Beam width: 1 ~ 2 ns (need single bunch selector)
- Beam line for deuteron & neutron
- Collimator and dump
- Fission cross-section uncertainty: $< 10\%$



Target System for White Neutron Production

Carbon target

Deuteron

Fast Neutron

1 MHz, 12.3 μ A
Max. Temp. : 528 °C

Single Bunch Selector

Length : 35 cm , OD : 47 cm, ID : 26cm

- Emittance : 0.3 π mm mrad,
- d energy : 1 MeV
- Radius : 2 mm , angle : 0.027°
- Total length for SBS : 2.1 m
- RF field : 1550V, magnetic field: 45 gauss

Nuclear Data Measurement (FIC for fission CX)

Chamber

Neutron Beam

Sample

Chamber dimension	10 cm x 10 cm x gap
Gap	variable
Gas composition	Ar (90%) + CF ₄ (10%)
Gas pressure	variable
Sample	U235
Sample dimension	1 cm x 1 cm x thick.
Sample thickness	variable
Source	variable

Radiation Safety

저에너지실험동

TOF실

중성자빔입구

평면도

단면도

Building design of NDPS

White : C (d,n)





Mono : Li (p,n)

Dose map due to prompt neutrons

μSR (Muon Spin Rotation/Relaxation/Resonance)

Conceptual design 2011 ~ 2012	R&D Pause ~ 2018.12	R&D, Manufacturing ~ 2020.12	Installation ~ 2021.12	Commissioning 2021.12 ~	Operation After Commissioning
----------------------------------	------------------------	---------------------------------	---------------------------	----------------------------	----------------------------------

- Facility for studying characteristics of new materials (e.g. high temperature SC, semiconductor, etc.)
 - production of polarized muon beams
 - high sensitive X & γ ray detections
 - **Main Specification**
 - μ⁺ (surface muon, >10⁵ pps, CW)
 - 600 MeV proton with an intensity up to 400 μA
- Conceptual design of μSR is finished
- Some of R&D for target, spectrometer, muon transport line completed
- Resume development works from 2019



BIS (Beam Irradiation System)

Conceptual design

R&D Pause

R&D, Manufacturing

Installation

Commissioning

Operation After Commissioning

2011 ~ 2012

~ 2018.12

~ 2020.12

~ 2021.12

2021.12 ~

After Commissioning

Bio-medical beam irradiation system for biomedical R&D

- Passive scanning system including magnet and magnet power supply can be enabled in active scanning system
- Uniform irradiation system with large area




- Studies of the response of cancer cell and normal cell to various heavy ions including RIBs
- Studies of useful genetic resources using high LET heavy ion beams and developments of new variety

Main Specification

- $E_{\text{beam}} = 310 \text{ MeV/u}$ with $> 50 \text{ ppA}$ for ^{12}C
- Irradiation rate: $> 2 \text{ Gy/min}$
- Irradiation area: $>$ the diameter of 20 cm
- Non-uniformity: $< 5\%$
- SOBP: $< 4 \text{ cm}$ because of the limited acceleration energy
- Available LET: $\sim 10 \text{ keV/mm}$


Uniform beam irradiation system

- Wobbling magnet, W scatter, ripple and ridge filter, MLC
- Use of both passive ($\phi < 200 \text{ mm}$) and active beam ($\phi < 80 \text{ mm}$)



- Conceptual design of the BIS beam line is finished
- Resume development works from 2019

RAON Schedule



Summary

- RAON is Rare Isotope Beam Accelerator and Experimental Facilities in Korea
- Staged approach for development of experimental facilities
 - HPMMS, KOBRA, and LAMPS are being developed with priority
 - R&D and production of other experimental facilities will be resumed from next year
 - Installation start from 2019 year, experiment start on 2021
- Status
 - KOBRA: Manufacturing of Stage 1 is ongoing, Stage 2 will be developed by user community
Installation will be started from the middle of 2019
 - LAMPS: Manufacturing of solenoid R&D magnet and TPC from 2019
Complete integration & test of forward neutron array by the middle of 2019
 - MR-ToF-MS: Under development with KEK-KISS group as HPMMS
 - CLS, NDPS, μ SR, BIS: Detailed design is under discussion with RAON User Liaison Center and user community

Thanks for your attention !