



Superconducting Combined Function Magnet System for J-PARC Neutrino Beam Line




Toru Ogitsu, Yasuhiro Makida, Ken-ichi Sasaki,
Tatsushi Nakamoto, Hirokatsu Ohata, Nobuhiro Kimura,
Takahiro Okamura, Akio Terashima, Yasuo Ajima,
Norio Higashi, Takayuki Tomaru, Masahis Iida,
Kenichi Tanaka, Osamu Araoka, Shoji Suzuki, Akira
Yamamoto, Takashi Kobayashi, Atsuko Ichikawa,
Takeshi Nakadaira, Ken Sakashita, Takuya Hasegawa,
Yoshiaki Fujii, Hidekazu Kakuno

Contents

- **Introduction**
 - Superconducting Combined Function Magnet
 - Prototype Development
 - Mass Production
 - System Overview and Cryogenics
 - Commissioning
 - Hardware Commissioning
 - Beam Commissioning
 - Conclusion
- 

Tokai-to-Kamioka (T2K) long baseline neutrino oscillation experiment




Super-Kamiokande
(ICRR, Univ. Tokyo)




J-PARC Main Ring
(KEK-JAEA, Tokai)



ν_e appearance (θ_{13})



- Goal
 - Discover ν_e app.
 - ν_μ disapp. meas.
- Intense narrow spectrum ν_μ beam from J-PARC MR
 - Off-axis w/ 2~2.5deg
 - Tuned at osci. max.
- SK: largest, high PID performance



**J-PARC Facility
(KEK/JAEA)**

South to North

Linac
180 → 400 MeV

3 GeV RCS
3 GeV, 25 Hz, 1 MW

**Neutrino Beams
(to Kamioka)**

**Materials and Life
Experimental
Facility**

**Main ring: 30 GeV,
0.3 Hz, 0.75 MW → 1.66 MW**

**Hadron Exp.
Facility**

- JFY2007 Beams
- JFY2008 Beams
- JFY2009 Beams


Bird's eye photo in January of 2008

Neutrino beamline


Neutrino monitor build.



Electromagnetic horn



Graphite target




Primary proton beam line



Target station




Decay volume



Beam dump



UA1 magnet




Primary Beam-line

Assumed Beam Loss

750W@Prep.

250W@FF.

(1W/m @ ARC)




But they are expensive and also takes time... I don't like it...

We need SUPERCONDUCTING MAGNET system to bend 50 GeV proton with 100m R for future multi-MW option.




20D+20Q > 28 SCFM
Optimize Cost & Schedule




Contents

- Introduction
 - **Superconducting Combined Function Magnet**
 - Prototype Development
 - Mass Production
 - System Overview and Cryogenics
 - Commissioning
 - Hardware Commissioning
 - Beam Commissioning
 - Conclusion
- 

Combined Function Magnet Concept






Current Distribution



2002 Spring
Proposed by BNL
RHIC DX +
Direct winding coil

OR



2002 Summer
Proposed by T.O.
L-R Asymmetry Coil
Based on FFAG SCM

SC Combined Function Magnet

E.M. Design:
Single layer
CFM

Mech. Design:
Plastic Spacer,
Keyed Yoke,
SUS304L Shell

SC Busbar

Iron Yoke



Stainless Steel Shell
(SHe Vessel)

Lock Key

Yoke Stack Tube


L/R Asymmetric
Coil

Plastic Collar



S.C. Cable for LHC-Dipole-Outer (strand: LHC left
w/ MQXA Insulation)

Specification



Coil ID.: 173.4mm Op. Current: 7345 A
 Mag. Length: 3300 mm Op. Margin: 72%
 Mech. Length: 3630 mm Inductance: 14
 Tmax: < 5.0K Stored Energy: 386 kJ
 (Supercritical Helium Cooling) # of Magnet: 28
 Dipole Field: 2.59 T SC Cable: NbTi/Cu
 Quad. Field: 18.6 T/m Rutherford Type Cable
 Field Error: < 10⁻³ @ for LHC Dipole Outer-L
 50mm

	3D-SS	3D-LE	3D-RE	3D-Integral
Lmag(m)	194	078	058	33
B1(T)	2591	2602	2603	2601
b2(uni)	3628	3567	3517	3581
b3(uni)	-093	-581	-105	-337
b4(uni)	501	-111	-235	-23
b5(uni)	207	-89	-160	-35
b6(uni)	-636	-79	-98	-72
b7(uni)	-116	-35	-53	-24
b8(uni)	-395	-29	-36	-37
b9(uni)	-886	-77	-79	-84
b10(uni)	-025	03	03	-00
b11(uni)	-310	-27	-26	-29
b12(uni)	207	17	16	19

- Peak field at conductor in straight section is 4.6 T at 50 GeV.
- Load line ratios at 5 K for 40 & 50 GeV are 58 % & 72 %, respectively.
- Field quality within a tolerance of 10⁻³ is acceptable.

Good

Not So

Good
Enough


Contents



- Introduction
- **Superconducting Combined Function Magnet**
 - **Prototype Development**
 - Mass Production
- System Overview and Cryogenics
- Commissioning
 - Hardware Commissioning
 - Beam Commissioning
- Conclusion

Coil & Collar

- Off-center magnetic pole ⇒ Left-right asymmetry
- Different thickness of wedges for both sides ⇒ Asymmetric mech. property
- Cured with wedges and the pole spacer ⇒ No collar insertion



For excitation : ~30 MPa



For cool down : ~20 MPa → 50 MPa required

⇒ Pre-stress of 80 MPa given by Yoking

Process

Coil over-size of 0.7 mm & 1.0 mm

GFRP Wedges and Spacers




- End spacers: G10 (CNC file)



- Ramp box: G10

Verified by practice coil winding and mechanical short model study



- Wedges: G11

Size Tolerance

Target: < 0.05 mm

Actual: 0.1 mm

*Coil Pre-stress tolerance after yoking:

Coil Winding Tool

Cable Tensioner

Coil Stopper (radial and azimuthal)

Mandrel

Turning Table






Insertion
of end
spacer




Alignment of pole
spacer by key

Coil Winding for Prototype Magnet





Mirror-symmetry Top & Bottom coils of the prototype





- Coil with pre-pregnant Epoxy resin cured at 400K for 5 hours.
- Asymmetric coil oversize determined by 2 sets of shims.

Coil Size Measurement




Cured bottom coil on the mandrel. Several sets of strain gauges are installed on the press-bars in both sides to measure coil stress during the coil size measurement.

Coil Size Measurement



Cured bottom coil on the mandrel. Several sets of strain gauges are installed on the press-bars in both sides to measure coil stress during the coil size measurement.


Coil Size Measurement



Cured bottom coil on the mandrel. Several sets of strain gauges are installed on the press-bars in both sides to measure coil stress during the coil size measurement.

Expected pre-stress of 60-80 MPa after magnet assembly is similar to the design value of 80 MPa.

Plastic Collar



Compression
Molding
@430 K, 10 min.
&
Post-curing w/
Forming Jig
@ 450K, 10hrs



Glass-reinforced Phenolic Thermosets
Rin=102 mm, t=20 mm, L= 100 mm
*PM9640 supplied by Sumitomo
Bakelite, and fabricated by Arisawa

Size control is very important!!




R&D to search the most
appropriate condition needs 18
months.




Molding jig was designed with
taking into acco the
consistent deformation.

• **Maximum Deformation: 0.1-**



Yoking -Coil Installation-



Yoking -Top Assembly Installation-

Top Collar Installation




Top Yoke Installation



Top lead Collar Installation




Top Yoke Installation Complete



Yoking -Press-

Press Bar Installation



Top Hat Installation



er

Yoking -Keying-



Key pushing




Key Insertion




Complete

Shell Welding

Longitudinal shell welding by a set of two automated welding machines.



Final Assembly



End-ring welding



Installation of the alignment target




Leads connection by soldering.

Excitation Test of the 1st Prototype

$I_{op} = 7345 \text{ A @ } 50 \text{ GeV}$ (and $I_{max} = 7,700 \text{ A}$) reached with no quench, on March 4,


2005

Installation into
cryostat,




Participating member

Participating members



	Measurement	Computation
Current (A)	7460	7345
B ₁ (T•m)	8.906	8.712
B ₂ (T•m)	3.127	3.120
B ₃ (T•m)	-220.6*10 ⁻⁴	-293.6*10 ⁻⁴
B ₄ (T•m)	-5.9*10 ⁻⁴	-20.1*10 ⁻⁴
B ₅ (T•m)	-51.9*10 ⁻⁴	-30.6*10 ⁻⁴
B ₆ (T•m)	-75.2*10 ⁻⁴	-62.8*10 ⁻⁴
B ₇ (T•m)	-44.6*10 ⁻⁴	-20.9*10 ⁻⁴
B ₈ (T•m)	-74.5*10 ⁻⁴	-32.0*10 ⁻⁴
B ₉ (T•m)	-79.9*10 ⁻⁴	-73.4*10 ⁻⁴
B ₁₀ (T•m)	-13.8*10 ⁻⁴	-0.3*10 ⁻⁴

Field Measurement Result



Record of
Excitation
current


Contents






- Introduction
- **Superconducting Combined Function Magnet**
 - Prototype Development
 - **Mass Production**
- System Overview and Cryogenics
- Commissioning
 - Hardware Commissioning
 - Beam Commissioning
- Conclusion

Magnet Mass Production

- Mass production
 - bidding won by Mitsubishi Electric
 - Built to Print Contract
- Major Monitoring Data
 - Coil Length, **Prestress**
 - Yoke size
 - Shell size
 - **Warm Field Quality**
- Cold Test at KEK
 - Presented by Okamura (Wednesday Poster)



Warm Field Measurement



$R_{ref} = 50 \text{ mm}$

Coil Prestress Measurement Results

Average: ~90 Mpa

Standard Deviation: ~7 Mpa

Equivalent Coil Size Deviation



High Field Side: 0.07 mm (0.13 mrad)

Low Field Side: 0.14 mm (0.26 mrad)


MQXA (LHC IRQ)

Inner Coil Size Deviation: 0.022 mm (0.1 mrad)

Influence to Field Quality by Coil Prestress



B1



B1 Standard Deviation:
22.56E-4 Tm/kA
= ΔX 0.3 mm
Acceptable




WMFM Results


R_{ref} = 50 mm

A1

A1 Average: -42.22e-4 Tm/kA
= ΔY 0.5 mm
A1 Standard Deviation:
17.25E-4 Tm/kA
= Δ 0.2 mm
Acceptable



A2 Standard Deviation:
2.57E-4 Tm/kA
= Δθ 0.5 mrad
Angle Standard Deviation:
= Δθ 0.7 mrad
Acceptable




Higher Harmonics

		Opera 3D			Measured					
B_n		7345 A	5830 A	4400 A	7345A		5830 A		4400 A	
n	Unit	calculated	calculated	calculated	average	standard deviation	average	standard deviation	average	standard deviation
B3int	1×10^{-4} T·m	293.45	236.56	179.18	218.99	6.50	181.74	5.38	138.44	3.81
B4int	1×10^{-4} T·m	-20.33	-64.83	-52.10	-7.55	4.55	-62.67	3.82	-53.71	2.74
B5int	1×10^{-4} T·m	30.68	41.02	32.12	47.77	3.31	53.79	2.45	40.52	1.74
B3	UNIT	1.62	1.91	1.21	5.12	0.84	3.86	0.78	3.48	0.76
B4	UNIT	-9.04	0.26	2.30	-9.19	0.42	-0.64	0.43	-0.77	0.41
B5	UNIT	2.51	-0.93	-1.47	0.50	0.31	-1.89	0.29	-1.90	0.28
B6	UNIT	6.28	5.98	5.82	6.72	0.15	6.22	0.12	5.94	0.11
A3	UNIT	0	0	0	0.12	1.05	0.22	1.05	0.24	1.07
A4	UNIT	0	0	0	-0.11	0.19	-0.04	0.21	-0.02	0.20
A5	UNIT	0	0	0	0.08	0.36	0.07	0.34	0.06	0.31


$R_{\text{ref}} = 50 \text{ mm}$

Higher Order Mutipoles: Acceptable

Contents

- Introduction
 - Superconducting Combined Function Magnet
 - Prototype Development
 - Mass Production
 - **System Overview and Cryogenics**
 - Commissioning
 - Hardware Commissioning
 - Beam Commissioning
 - Conclusion
- 

System Overview



- 14 Doublets
- 13 Interconnets
- 4 Profile Monitors
- 5 Position Monitors
- 3 Steering Magnets
- 4 Quench Valves




LHC&J-PARC Neutrino SC System

■ Comparison

- Size 27km vs 150m
- Number of Magnets ~5000? Vs 28
- Inductance and Stored Energy
 - LHC (1 sector) : 15.1H, 1.2GJ
 - J-PARC: 0.4H, 10MJ(50GeV), 5MJ(30GeV)
- Helium Inventory
 - LHC(overall) : 56万Nm³
 - J-PARC: 4000Nm³



ostat




cryostat: Reduce Cost and Risk


- Common Parts → advantage of LHC mass production



Interconnects



Corrector Interconnect




Quench Relief Valve

Corrector Production

Manufactured and Tested at BNL
Direct Winding on Copper


Bobbinn

Cold test for Quench Performance



Parameter	Average Value	Std. Dev.
B1 Integral	2.34 Tm/kA	$22.4 \cdot 10^{-4}$ Tm/kA
A1 Integral	2.32 Tm/kA	$32.3 \cdot 10^{-4}$ Tm/kA
B1-A1 angle	-1.4 mrad	2.2 mrad

Refrigeration System






Installation Completed by Dec. 2008

Contents

- Introduction
 - Superconducting Combined Function Magnet
 - Prototype Development
 - Mass Production
 - System Overview and Cryogenics
 - **Commissioning**
 - **Hardware Commissioning**
 - Beam Commissioning
 - Conclusion
- 


Pressure Drop

--steady state mode (230 g/sec ~ 330 g/sec)--




- Pressures at Cernox sensors can be obtained from above figure.
- Wall Friction Coefficient, λ , is treated as adjustable parameter.

Heat Load





- Magnet String
 - 140 W
- Transfer Line
 - 50 W
- Current Lead
 - 60 W @ 0 flow
 - 0 W @ 70 L/min
 - 100 L/min @ 4kA



Quench Protection Test

- Performance test of quench protection system
 - Heater Induced Quench
 - Quench Recovery






- **Quench Protection Heater**
 - Powered by Capacitors




- **Cold Diode**
 - Turn On Voltage: 6V
 - Forward Voltage: 1V



8kA 30V



- **Dump Circuit**
 - Protect Cold Diodes and SC Bus Bars
 - Time Constant: 20



Quench Protection Test


Cold Diode

- Influence of Neutron to Cold Diode
 - Intensively studied at CERN by D. Hagedorn
 - Change Forward Voltage
 - Using LHC Arc Quad Assembly
 - 7.5kA Operation
 - Limit; $2 \cdot 10^{14}$ n/cm²



Courtesy D.Hagdo

Bypass Diode Test



Cool Down after Quench

- Quench Test at 4400A (30GeV nominal)
 - Normal case (4 magnets) : ~2 hour to recover

Good noise reduction by MSS




No false quench detection by system shut down



Avoid extra magnet to quench



Save time for quench recovery



Contents



- Introduction
- Superconducting Combined Function Magnet
 - Prototype Development
 - Mass Production
- System Overview and Cryogenics
- **Commissioning**
 - Hardware Commissioning
 - **Beam Commissioning**
- Conclusion



T2K beamline started operation!

FIRST SHOT after turning on SC magnets at 19:09, Apr.23, 2009


Beam profile monitor signal



First observation of muons produced in neutrino beamline


T2K beamline started operation!

MR intensity




After ~10 shots for tuning, proton beam hit around target center


Muon monitor signal




Proton beam profile monitor along nu beamline



OTR detector just in front of target (fluorescence plate)




Muon monitor profile




Horn

Optics Study


- SC Magnet current dependence
 - Beam induced quench eventually



Beam Size X



Beam Size Y





Beam Induce

Partial beam loss observed at 4200


- At around SCR2~SCR4

Full beam loss observed at 4160 A


- Beam loss in between SCR2 ~ SCR4
- Quench at SCR3F
- No damage observed



Contents

- Introduction
 - Superconducting Combined Function Magnet
 - Prototype Development
 - Mass Production
 - System Overview and Cryogenics
 - Commissioning
 - Hardware Commissioning
 - Beam Commissioning
 - **Conclusion**
- 

Conclusion

- A SCFM with Single Layer Coil Winding is Developed
 - Good Cost & Time Saving with Optimum Condition
 - Half Cell = one SCFM; Dipole > Quadrupole
 - Draw back
 - D/Q ratio fixed → It appears to be OK
 - International Collaboration
 - BNL, Saclay, CERN
 - Construction Completed on Schedule
 - Commissioning
 - No major problem with hardware commissioning
 - Minor problem associate with corrector current lead
 - scheduled to be fixed in this summer
 - Beam Commissioning went smoothly
 - Beam went through SC arc with the first attempt
 - Beam behaved as expected (almost)
 - Beam induced quench > quench protection works OK
- 

Application of SCFM 1

- **Good Cost & Time Saving with Optimum Condition**

- **Half Cell = one SCFM**
- Dipole > Quadrupole

- **For Beam Line**


- Already good enough?
 - So far so good.

- **For Accelerator Ring**

- Needs more study on field quality
 - Neutrino production magnets show good reproducibility = there are some hope

- **Special Accelerator**

- Muon Acceleration FFAG?



Application of SCFM 2

- **Good Cost & Time Saving with Optimum Condition**

- Half Cell = one SCFM
- **Dipole > Quadrupole**

- For Beam Line


- Already good enough?
 - So far so good

- For Accelerator Ring

- Needs more study on field quality
 - Neutrino production magnets show good reproducibility = there are some hope


- Special Accelerator

- Muon Acceleration FFAG?



Application of SCFM 3

- A SCFM with Single Layer Coil Winding is Developed
- Good Cost & Time Saving with Optimum Condition
 - Half Cell = one SCFM
 - Dipole > Quadrupole
- **For Beam Line**
 - **Already good enough?**
 - So far so good
- **For Accelerator Ring**
 - Needs more study on field quality
 - Neutrino production magnets show good reproducibility
 - = there are some hope
- **Special Accelerator**
 - Muon Acceleration FFAG?




New
Idea

Risk

Acknowledgment



**Thank you very
much
for your listening**



Acknowledgment




Acknowledgment




JFY 2001 : 10 Cell FODO


20 Dipole + 20 Quads = 40 Magnets



Ichikawa w/ help Doornbos




Dipole: 4T*3m




Quadrupole: 36T/m*0.9m

Optics with 14 Doublets



コリメータ



- Arc Section Optics
 - 14 doublets; 28 SCFM
- Optimized Collimator in Prep. Sec.
 - Minimize risk to Arc Section

Ichikawa, Iwamoto, Tanabe
w/ help Doornbos, Noumi, Oide