
ProtoDUNE dual-phase / 3x1x1 update

Dario Autiero (IPNL Lyon)

LBNC Meeting


March 24, 2017

WA105
Dual-Phase ProtoDUNE





History of Dual-Phase ProtoDUNE / WA105



CERN, Geneva, Switzerland

K. Loo, J. Maalampi, W.H. Trzaska, and S. Vihonen Department of Physics, University of Jyväskylä, Finl SPSC-SR-206

EUROPEAN ORGANIZATION FOR NUCLEAR RESEARCH

CERN-SR-XXX March 21, 2017

Yearly progress report on WA105/ProtoDUNE dual-phase (2017)

The ProtoDUNE Dual Phase Collaboration

Abstract


WA105/ProtoDUNE dual-phase aims at fully demonstrating the concept of a very large dual-phase LAr TPC and calibrating it with a charged particles test beam, in view of the application of this detector design for the construction of DUNE 10% as far detector modules. In this document we report the general progress of the dual-phase experimental activities at CERN since the last SPSC yearly report.

GERN-STSC-2017-011 / STSC-SR-206 21/08/2017

One year of progress documented in the report submitted to the SPSC 2017 annual review: https://cds.cern.ch/record/2256436


3x1x1 catalyzing progress on 6x6x6 m³:

- Membrane vessel design and procurement
- Cryogenics
- Charge Readout Plane (CRP) detectors
- CRP structure and hanging system
- Feedthroughs
- HV and field cage
- Charge readout FE electronics + digital electronics
- Light readout system + electronics
- DAQ and online processing
- Slow Control
- ✓ Fully engineered versions of many detector components with preproduction and direct implementation (installation details and ancillary services)
- ✓ First overview of the complete system integration: set up full chains for QA, construction, installation, commissioning
- ✓ Anticipate legal and practical aspects related to procurement, costs and schedule verification
- ✓ Retirement of several risks for PD-DP thanks to (1) identification of critical components (2) early detection of potential problems



For many items huge benefit from immediate application of a smaller 3x1 prototype LAr-proto (minimal size of RO unit in 6x6x6)





May-June 2016:

- CRP cryogenic test and installation under the top-cap
- Installation of drift cage
- Cabling of all inside sensors (high voltage, LEMs, temperature, ...)
- Signal feedthrough wiring, insertion and testing with first analogue front end
- Cabling and test of PMTs
- Complete testing (HV leakage currents, signal continuities, cable mapping, voltage divider,..)

→ July 4th top-cap with detector lifted and inserted in the cryostat

July-August 2016:

- Multiple visual inspections by entering the cryostat through manhole.
- Gas system to purge cryostat insulation installed
- Cabling of slow control system
- Some slow control sensors up and running, data-base setup.
- Light readout electronics installed
- Very high voltage feedthrough successfully inserted and tested
- Installation of online computing farm with 256 cores and 200 TB storage

September 2016:

- · Cosmic ray trackers installed
- Installation of cryogenic front-end electronics in the signal chimneys, all channels tested with charge injection in the anode strips
- Completion of cabling
- Installation of cryogenic system be DEMACO 19/9-9/10

October 2016:

- Completion of cryogenics
- Final grounding checks and installation of digital electronics
- Warm gas piping, cabling of cryo controls




- October 2016: due to delay in warm gas piping installation and interference with Christmas CERN stop filling postponed to January
- December 19th closure of man-hole, leak tests, identified major leak in liquid argon pump tower due to a broken bellow. Bellow likely damaged during transport or installation (pump tower tested successfully at CrioTEC/Italy) → repair of pump tower
- January 24th -February 7th: open loop purge, 1.5 ppm O₂ reached
- February 8th February 15th : closed loop purge, 80 volumes 0.2 ppm O₂ reached
- February 15th attempt to cool-down, problems due to the formation of gas pockets on the LN2 line

 → modification of the LN2 line needed by adding a purging valve at the input of the condenser (1.5 weeks of delay added on the commissioning schedule of the cryogenic system.
- Cryostat cool-down started on February 27th → March 3rd
- March 3rd observation of a cold spot with ice in a corner of the cryostat exoskeleton → LAr T not reached, warming up for inspection
- March 14th access possible, visual inspection shown no damages to membrane, March 14th -March 18th Negative leak searches with helium
- March 21st, drilling of point corresponding to cold spot on external steel plates: shown the presence of an empty corridor without insulation








26-12 27-00 27-12 28-00 28-12 01-00 01-12 02-00 02-12 03-00 03-12 time [day-hour]

Gas purity evolution during purging (open and closed loop) and cool-down:


→ oxygen, nitrogen and moisture under control; no evidence for large outgassing or leaks





Scintillation light (slow component) in pure argon gas

Detector-Cryostat integration




→ Finalization by the end of November 2016 of executive design of: CRPs, field-cage and cathode

Charge Readout Planes


Field Cage (common structural elements with SP)

Cathode

Full 3D electrostatic simulations completed for HV feedthrough, field-cage, cathode, ground grid




The Dual-Phase ProtoDUNE/WA105 6x6x6 m³ detector is built out of the same **3x3m² Charge Readout Plane units (CRP)** foreseen for the 10 kton Dual-Phase DUNE Far Detector (same QA/QC and installation chains)




3x3 m² CRPs integrating the LEM-anode sandwiches (50x50 cm²) and their suspension feedthroughs (CRP specific to dual-phase technology: critical item)


→ Invar frame + decoupling mechanisms in assembly in order to ensure planarity conditions +-0.5 mm (gravity, temperature gradient) over the 3x3 m² surface which incorporates composite materials and ensure minimal dead space in between CRPs



CRP mechanical structure design:

→ campaign of cold bath tests + photogrammetry on differential effects in thermal contraction, design of decoupling mechanism





Thermal decoupling supports of G10 frame on invar frame

Module 2


Invar frame

G10 frame (glass fiber)

Integration of the grid of submerged extraction wires in the frame minimizing dead space in between CRPs. Tests for the wires system design

Module 1






Field cage shares common basic structural elements (extruded profiles and FRP beams) with the single-phase ProtoDUNE

Assembled in 8 vertical modules of 6238x3017 mm (2 modules per detector face).

Each module is assembled out of 3 sub-modules

→ 98 profiles/module with 60 mm pitch



Subampelala 33 profiles - Cultoria Subampelala 33 profiles - Cultoria 34 profiles - Cultoria 35 profiles - Cultoria 36 profiles - Cultoria 37 profiles - Cultori

Continuity at center and borders (bent at 45 degrees) with clipping profiles

Test setup at CERN for clips and electrical elements

Adaptation from SP beam plug design being finalized

Detailed electrostatic simulations performed for profiles/clips


<u>Transparent cathode with ITO</u> (Indium-Tin-Oxyde) <u>resistive</u> <u>coating</u> on two sides of PMMA plates + TPB deposition at the top side:

- R&D and conceptual design for plates integration in cathode structure completed
- Infrastructure set up for TPB evaporation coating
- Tested ITO coated PMMA plates up to 850x600 mm² (produced by industry) → chosen size 650x650x10 mm³


LBNC meeting of October 2016: PMMA cathode, despite all successful R&D, introduces many elements of novelty in the 6x6x6 design and possibly some risks which will not be retired by the 3x1x1 operation

- → decided to reactivate the baseline design of the cathode, based on a mesh of pipes (extensively studied in the LAGUNA-LBNO DS and WA105 TDR)
- → Minimal changes to the structure made for PMMA inserting 20 mm SS pipes with 105 cm pitch, completion of executive design, full simulations showing E<30 kV/cm</p>

Ground grid above the PMTs, 2mm wires embedded in a SS frame 40/20 mm pipes, assembled in 4 modules




modules



Cathode HV system:


- HV power supply for 300 kV already available Heinzinger
- HV feedthrough deployed on 3x1x1 but designed to work up to 300 kV (300 kV milestone achieved in September in dedicated test setup, article: C. Cantini et al 2017 JINST 12 P03021.)




Preparation for PMTs installation:

- 40 PMTs procured in December 2016
- Calibration/characterization system at warm/cold
- TPB coating at CERN (Icarus facility)

Cryostat for test in batches of 10 PMTs (April 2017)



Mechanical supports for installation on the cryostat floor in between corrugations (arrangement compatible with cryo-piping)








Slide from LBNC review in October

- Extension of North Area completed!
- Cryostat construction started → Available for WA105 installation in April 2015








- exoskeleton cryostat installation completed
- insulation panels installation started to be completed by the end of May



- Clean Room in hall 185, used so far by Icarus, is going to be freed by April 11th in order to host the CRP assembly activities
- Cryostat + clean room buffer should become available in June to start the detector installation activities
- Assembly/procurement activities started


Schedule revision including:

- information from the availability of the infrastructure
- detector executive design (CRP, field cage, cathode) related to a more precise definition of the construction and assembly procedures
- refinements related to experience from the 3x1x1
- → end of detector installation in February 2018



- Access to clean room in Hall 185: 11/4/2017
- \bullet Access to cryostat/clean room buffer in EHN1 to start the detector installation: 1/6/2017
- First CRP installed: 8/8/2017
- All CRPs installed and cabled: 8/11/2017
- End of readout electronics installation 1/12/2018
- End of drift cage and cathode installation: 15/1/2018
- End of PMTs installation: 5/2/2018
- End of beam-plug installation: 14/2/2018
- Detector fully installed and cabled, ready to seal TCO: 19/2/2018

H2-VLE beamline



Tertiary beam on H2 beamline:

1-12 GeV/c, momentum bite 5% (can be reduced to 1% with integrated spectrometer measurements)

- Mixed hadrons beam 1-12 GeV/c: pions, kaons, protons + electrons contamination at low energies
- Pure electron beams
- Parasitic muon halo

→ O(100 M beam triggers to be acquired in 2018 in 120 days of beam operation)

Beam instrumentation well defined by B.I. WG (beam profile monitors and trigger tiles TOF, 2 Cerenkov)

Beam line with all instrumentation integrated



Integration of beam-line DAQ within WA105 White-Rabbit time distribution system


Construction started → looking forward to commissioning

WA105 Accessible cold front-end electronics and uTCA DAQ system 7680 ch

Full accessibility provided by the double-phase charge readout at the top of the detector

- Cryogenic ASIC amplifiers (CMOS 0.35um) Digital electronics at warm on the tank deck: Architecture based on uTCA standard 16ch externally accessible:
- 1 crate/signal chimney, 640 channels/crate Working at 110K at the bottom of the signal → 12 uTCA crates, 10 AMC cards/crate, 64 ch/card
 - Cards fixed to a plug accessible from outside

chimneys



Cost effective and fully accessible cold front-end electronics and DAQ


Ongoing R&D since 2006→ in production for 6x6x6 (7680 readout channels)

ASIC (CMOS 0.35 um) 16 ch. amplifiers working at ~110 K to profit from minimal noise conditions:


- FE electronics inside chimneys, cards fixed to a plug accessible from outside
- Distance cards-CRP<50 cm
- Dynamic range 40 mips, (1200 fC) (LEM gain =20)
- 1300 e- ENC @250 pF, <100 keV sensitivity
- Single and double-slope versions
- Power consumption <18 mW/ch
- Produced at the end of 2015 in 700 units (entire 6x6x6)
- 1280 channels installed on 3x1x1


DAQ in warm zone on the tank deck:

- Architecture based on uTCA standard
- Local processors replaced by virtual processors emulated in low cost FPGAs (NIOS)
- Integration of the time distribution chain (improved PTP
- Bittware S5-PCIe-HQ 10 Gbe backend with OPENCL and high computing power in FPGAs
- Production of uTCA cards started at the end of 2015, pre-batch already deployed on 3x1x1
- → Large scalability (150k channels for 10kton) at low costs









- Full production 700 chips of cryogenic ASIC amplifiers procured at the beginning of 2016
- 64 channels FE cards with 4 cryogenic ASIC amplifiers designed and tested in the spring 2016
- First batch of 20 cards (1280 channels) produced for the 3x1x1 operation, operational

uTCA 64 channels AMC digitization cards (2.5-25 MHz, 12 bits output, 10 GbE connectivity

- 20 cards produced by September 2016 to equip the 3x1x1, operational
- Cards production going to be completed with the 2017 budget of remaining 100 FE and uTCA cards for 6x6x6 (main components purchased last year ADCs,FPGAs,IDT memories ...)





Global uTCA DAQ architecture

integrated with « White Rabbit » (WR) Time and Trigger distribution network


+ White Rabbit slaves nodes in uTCA crates +

WR system (time source, GM, trigger system, slaves)





White Rabbit trigger time-stamping PC (SPEC + FMC-DIO) White Rabbit Grand-Master GPS unit



White Rabbit uTCA slave node based on WRLEN developed and produced for entire 6x6x6

Other components of the chain (GPS receiver, WR grandmaster, SPEC+ FMC-DIO + 13 WRLEN) available commercially



6x6x6: 12 uTCA crates (120 AMCs, 7680 readout channels)


→ 3x1x1: 4 uTCA crates (20 AMCs, 1280 readout channels)




Event builder, network, GPS/White Rabbit GM, WR Trigger PC


Signal Chimneys and uTCA crates

How a crates was looking like before VHDCI signals cabling to the warm flange






- Several campaigns of checking of the grounding conditions/noise measurements since June 2016.
- Good noise conditions with some residual small issues related to slow-control/HV grounding and cabling
- → Average RMS noise 1.7 ADC counts (0.82 mV) at warm with all systems active and cabled 1.5 ADC counts with slow control/HV cables disconnected from flanges



The grounding scheme for the 6x6x6 is more sophisticated with the cryostat, FE electronics and slow control completely insulated from external environment and only referred to cryostat ground.

Online processing and storage facility: internal bandwidth 20 GB/s, 1 PB storage, 384 cores: key element for online analysis (removal of cosmics, purity, gain, events filtering)



■First design of online storage/processing DAQ back-end farm performed in 2016 (1PB, 300 cores, 20Gb/s data flow),

DELL-based solution : configuration

storage servers :

- * 15 R730XD (storage servers) including :
- * 16 disks 6To
- * 32Go RAM
- * 2 disks system RAID 1, 300 Go 10k
- * 1 network card Intel X540 double port 10 GB
- * 4 years extended guarantee (D+1 intervention)
- * 2 processors Intel Xeon E5-2609 v3
- * raid H730P
- * Rails with management arm
- * double power supply

metadata servers (MDS) :

- * 2 R630 (metadata servers), including :
- * 2 disks 200 Go SSD SAS Mix Use MLC 12Gb/s
- * 2 processors Intel Xeon E5-2630 v3
- * 32Go DDR4
- * RAID H730p
- * network : Intel X540 2 ports 10 Gb
- * 4 years extended guarantee (D+1 intervention)
- * Rails with management arm
- * double power supply

configuration server :

- * 1 R430 (configuration server)
- * 1 processor E5-2603 v3
- * RAID H730
- * 2 hard disks 500 Go Nearline SAS 6 Gbps 7,2k
- * 16 Go DDR4
- * Rails with management arm
- * double power supply

Offline computing farm: 16*24 = 384 cores

- * 1 blade center PowerEdge M1000e with 16 ames M630, each including
- * 128Go DDR4
- * 2 processors Intel Xeon E5-2670 v3
- * 4 years extended guarantee (D+1 intervention)
- * 2 hard disks 500 Go SATA 7200 Tpm
- * netwok Intel X540 10 Gb

Switch Force10, S4820T (see next slide):

- * 48 x 10GbaseT ports
- * 4 x 40G QSFP+ ports
- * 1 x AC PSU
- * 2 fans
- ■Smaller test scale system already installed and operative for 3x1x1
- Tests to finalize the architecture of final online storage/processing facility.




Conclusions:

- The 3x1x1 pilot detector has been extremely useful in order to reach an advanced state of prototyping and costs assessment of most of the components for the 6x6x6 and to anticipate legal and procurement problems. The 3x1x1 assembly was completed in the fall 2016. The operation with liquid argon of the 3x1x1 has unfortunately not started yet due to delay in the cryogenic system and a recent problem with the cryostat.
- Experience gained so far with 3x1x1 construction, slow control operation, gas purge and purity measurements, FE electronics, noise and grounding, smooth operation of the DAQ system and online storage and processing commissioning has been conformal to expectations and very fruitful. The 3x1x1 activities have allowed retiring and/or reducing risks for PD-DP through (1) identification of potential critical components (2) early detection of potential problems. Most have been already taken into account in the 6x6x6 design.
- The executive design of the remaining aspects of the 6x6x6 CRPs, Field Cage, cathode, was completed by the end of November 2016. The schedule has been revised by taking into account final design and precise operation sequences, availability of infrastructure (clean room in 185 and cryostat + clean room buffer) and experience from 3x1x1 assembly. Production and construction activities started. FE and DAQ electronics, Slow Control, PMTs, HV, Cosmic Ray Triggers were already in production phase. The beamline + instrumentation design was completed as well and installation started.
- A global picture of the progress during the last year is described in the CERN SPSC 2017 yearly report
- ➤ The DP ProtoDUNE construction is in an advanced state and largely benefited of the preparation activities with the 3x1x1. We are looking forward to the completion of the DP ProtoDUNE detector assembly in the cryostat and the exploitation with the beamline in 2018 with the collection of about 100M triggers!


Double-phase readout:

Long drift, high S/N: extraction of electrons from the liquid and multiplication with avalanches in pure argon with micro-pattern detectors like LEM (Large Electron Multipliers)




Dual-phase 10 kton FD module

- 80 CRP units
- 60 field shaping rings
- 240 signal FT chimneys
- 240 suspension chimneys
- 180 PMTs
- 153600 readout channels



Active LAr mass:12.096 kton, fid mass:10.643 kton, N. of channels: 153600




Advantages of double-phase design:


- Anode with 2 collection (X, Y) views (no induction views), no ambiguities
- Strips pitch 3.125 mm, 3 m length
- Tunable gain in gas phase (20-100), high S/N ratio for m.i.p. > 100, <100 KeV threshold, min. purity requirement 3ms → operative margins vs purity, noise
- Long drift projective geometry: reduced number of readout channels
- No materials in the active volume
- Accessible and replaceable cryogenic FE electronics, high bandwidth low cost external uTCA digital electronics

Dual phase liquid argon TPC 6x6x6 m³ active volume


→ Event size: drift window of7680 channels x 10000 samples ⇒ 146.8 MB



Detector installation in EHN1



TCO = Temporary Construction Opening




Clean room hatch matched to TCO

- Feedthroughs are installed first
- The material for detector installation is brought to a clean room buffer and then via TCO into the cryostat
- CRPs will be pre-assembled at CERN, packed in a protective case, and then brought in vertically via TCO
- All elements (CRP+field cage panels + cathode submodules in basic units of similar standard sizes)
 - → Installation sequence same as for 10kt DUNE
- CRP assembly at CERN in clean room in Bld 185 (4 CRP assembly in parallel)

Momentum [GeV/c]	anti-p	e-	e+	К-	K+	mu-	mu+	р	pi-	pi+
0.4	0.00%	0.00%	97.61%	0.00%	0.00%	0.00%	0.00%	0.48%	0.00%	1.91%
1	0.00%	0.00%	74.20%	0.00%	0.00%	0.00%	0.00%	14.94%	0.00%	10.86%
2	0.00%	0.00%	45.83%	0.00%	0.67%	0.00%	0.96%	20.04%	0.00%	32.50%
3	0.00%	0.00%	68.29%	0.00%	0.64%	0.00%	0.42%	7.72%	0.00%	22.94%
4	0.00%	0.00%	53.72%	0.00%	1.46%	0.00%	0.65%	7.56%	0.00%	36.61%
5	0.00%	0.00%	42.38%	0.00%	2.47%	0.00%	0.83%	9.18%	0.00%	45.14%
6	0.00%	0.00%	31.42%	0.00%	3.83%	0.00%	0.73%	10.10%	0.00%	53.92%
7	0.00%	0.00%	24.70%	0.00%	4.08%	0.00%	0.85%	9.92%	0.00%	60.46%
8	0.00%	0.00%	19.36%	0.00%	5.11%	0.00%	0.97%	11.33%	0.00%	63.24%
9	0.00%	0.00%	15.12%	0.00%	5.67%	0.00%	0.82%	11.10%	0.00%	67.29%
10	0.00%	0.00%	12.36%	0.00%	6.02%	0.00%	0.71%	12.25%	0.00%	68.66%
11	0.00%	0.00%	10.46%	0.00%	6.95%	0.00%	0.82%	13.57%	0.00%	68.20%
12	0.00%	0.00%	8.90%	0.00%	6.89%	0.00%	0.66%	14.26%	0.00%	69.30%

Tertiary Beam composition for secondary beam +80 GeV/c



Final PID scheme:

- TOF with BPROF's distance ~32 m
- 1 "low pressure" XCET < 3bar pressure ("C1")
- 1 "high pressure" XCET ≥ 15 bar pressure ("C2")


BPROF's 1 mm fibers pitch 2 mm thick scintillator tiles

Momentum (GeV/c) / Particle	e 🔻	π 🔻	K	р
0.4 - 3.0	C1 CO2 @ 1bar	TOF	0	TOF
3.0 - 5	C1 CO2 @ 1bar	C2 CO2 @ 3.5 bar	No C2	No C2
5.0 - 12.0		C1 CO2 @ 1bar	C2 CO2 @ <= 14bar	r No C1 No C2

Baseline: No K/p separation between 3 - 5 GeV No e- tagging in the 'high energy' regime 5-12 GeV

DP Expressions of Interest

- Single-Phase Eols launched in January
 - Start defining responsibilities that can be taken to Funding Agencies
 - Five areas (consortia) under a FD-SP TB



Dual-Phase Eols

- Deferred launch of DP EoIs at request of WA105 IB
 - There were valid concerns about value of EoIs without a firmer "commitment" to pursuing DP as the second FD module
 - Without a stronger commitment, it would be hard to engage with FAs
- We should try to move forward





Planning for second FD module

- No quick answer needed to follow due process
 - Also wished to have 2nd Co-Spokesperson in place
- Detailed discussion of 2nd FD module will happen as part of DUNE strategy update
 - Major topic of Face-to-Face EC meeting on 27th March
 - Will also include discussion of decision-making process for first two FD modules
 - applies equally to Single-Phase dual-phase
- However, we have already moved to a more symmetric treatment of SP and DP
 - Committed to producing SP and DP TDRs on same timeline as options for the FD
- Committed to further symmetrization





Planning for second FD module

So what can we say today?

- Co-spokespersons support idea of planning for DP to be 2nd FD mod.
 - MT and EB discussed this topic last week and are of similar opinions
 - Discussed at EC meetings (during last collab. mtg. and on Monday)
 - General EC consensus, but still need a full discussion
- The EC needs to agree on precise wording (also applies to SP)
 - "DUNE is basing its planning on the assumption that ..."
- Need to define the decision process/timetable for 1st & 2nd FD module
 - e.g. PD-SP & PD-DP performance and how funding folds in

Timeline (assuming consensus)

- Agreement in principle at the EC meeting on 27/3/2017
 - Drafting of strategy statement and sign off in a few weeks
- Ideally launch DP Eols in parallel with the EC discussion



