

# **Beam commissioning of the high intensity proton source developed at INFN-LNS for ESS**

*L. Celona, L. Neri, S. Gammino, O. Leonardi, A. Miraglia, G. Torrisi,  
F. Chines, G. Castro, D. Mascali, G. Calabrese, G. Manno, M. Mazzaglia*

***Istituto Nazionale di Fisica Nucleare  
Laboratori Nazionali del Sud***



## **17th International Conference on Ion Sources**

October 15-20 2017

CERN - CIGG - Geneva





# Journey to deliver the world's leading facility for research using neutrons



**Proton source and LEBT:  
Ready For Installation**  
03/11/2017

**2025**  
ESS construction  
complete

**2014**  
Construction work  
starts on the site

**2023**  
ESS starts  
user program

**2009**  
Decision: ESS will  
be built in Lund


**2019**  
First beam on  
Target

**2012**  
ESS Design Update  
phase complete

**2003**  
First European design  
effort of ESS completed

## Italian In-Kind Contribution:

Proton Source, LEBT	INFN-LNS
DTL	INFN-LNL
T-REX, VESPA	CNR
RF systems, Magnets&PS, diagnostics	Elettra




## Partners for proton source and LEBT:

INFN-LNS	WP leader, Overall design, Construction, Commissioning, Installation
ESS	Vacuum, Controls, Beam diagnostics
CEA	Controls, Beam diagnostics




# Ion Source and LEBT

Source




Phases 1 and 2



Activity	Start	End
Phase 1: IS with FC and DSM	03/10/16	31/10/16
Phase 2: + EMU	02/11/16	30/04/17
Phase 3: Full LEBT	01/05/17	29/09/17
Packaging and shipping	02/10/17	31/10/17
Ready for Installation	03/11/17	

Phases 3 and 4




Ready for dismantling


# INFN-LNS background




TRIPS (2001)



VIS (2008)



PS-ESS (2016)



Performance	Value
Beam energy	80 Kev
Proton beam current	55 mA
Proton fraction	≈80%
RF frequency	2.45 GHz
RF power	Up to 1 kW
Axial magnetic field	875-1000 G
Duty factor	100 % (DC)
Extraction aperture	6 mm
Reliability	99.8% @ 35 mA
Transverse emittance ( $\sigma$ )	0.07 pi.mm.mrad @ 35 mA
Start-up after maintenance	32 hours

+ 25%

from dc to pulsed

High stability


Low emittance

Easy maintenance

Requirement	Value
Beam energy	$75 \pm 5$ keV
Energy adjustment	$\pm 0.01$ keV
Total beam current	$> 90$ mA
Proton beam current	74 mA
Proton beam current range	6.7 - 74 mA
Resolution	1.6 mA
Proton fraction	$> 75\%$
Pulse length	6 ms
Pulse flat top	3 ms
Repetition rate	14 Hz
Pulse to pulse stability	$\pm 3.5\%$
Flat top stability	$\pm 2\%$
Transverse emittance (99%)	1.8 pi.mm.mrad
Beam divergence (99%)	$< 80$ mrad
Start-up after maintenance	$< 32$ hours




# Proton Source and LEBT at INFN-LNS




# Plasma modeling


## Electron Energy Distribution Function



## RF energy adsorption





## Ion formation



$E_{th} = 9.2 \text{ eV},$   
 $E_{th} = 15.42 \text{ eV},$   
 $E_{th} = 18.15 \text{ eV},$   
 $E_{th} = 12 \text{ eV},$   
 $E_{th} = 15.2 \text{ eV},$   
 $E_{th} = 13.6 \text{ eV},$   
 $E_{th} = 10.2 \text{ eV},$   
 $E_{th} = 10.2 \text{ eV},$   
 $E_{th} = 3.4 \text{ eV},$   
 $E_{th} = 0 \text{ eV},$

## Generation maps




# Microwave to plasma coupling




3D full wave e-m simulation  
in presence of the electron  
plasma density and strong  
magnetic field has driven the  
design of **the matching  
transformer**

Empty cavity




Cold tensor plasma  
approximation




*G. Torrasi et al. "Full-wave FEM simulations of electromagnetic waves in strongly magnetized non-homogeneous plasma", JEWA 2014 vol. 20, no. 9, 1085-1099*


Low measured reflected  
power



High measured stability of  
forward and reflected power



Measured forward and  
reflected pulsed power



*G. Torrasi et al. "Microwave injection and coupling optimization in ECR and MDIS ion sources", Proc. of IPAC'17*



# Beam extraction system



Axcel 2D beam input parameters:

Some simulation parameters:

Mesh = 1096 x 1424

$I_p = 10$

N°particles = 21920

kTe = 15 eV

kTi = 0.25 eV



pot. Plasma = 20 V

$I_{tot} = 0.0925$  A

$I_{protoni} = 0.074$  A

$I_{H2} = 0.0185$  A

Simulations to optimized for larger current and minimize beam emittance





To increase flexibility an interchangeable geometry was designed and different type of electrodes were manufactured

Emit [99%]=1.492 (**< 1.8**) Pi.mm.mrad [Norm]  
Max Divergence= 55 (**< 80**) mrad

# Extraction column design

- Minimization off-axis electric field
- Electric field minimization at triple point ( $< 6.4$  kV/cm)

- X Ray protection
- Single alumina to minimize the electric field on the external surface ( $< 6.6$  kV/cm)




State-of-art sparks immunity during beam operation at 75 kV.  
Extraction column tested up to 90 kV.



# Increase electronics strength against discharge

Wide use of optical fibers

Shielded sub-rack on the HV platform



Grounding grid



FC voltage protection




Shielded sub-rack at ground



# Magnetic system control interface




Very high magnetic flexibility required a dedicated interface developed at INFN that enable direct control and high reproducibility





# Semi-automatic characterization tool




From the 23/01/2017 the source is extracting beam seamless, more than 300'000 tested configurations, no stops due to sparks.

**Plasma modelling → parameters range to be tested:**

Field @ 0 mm ==> 835:20:975 Gauss  
 Field @ 35 mm ==> 795:40:1395 Gauss  
 Field @ 84 mm ==> 675:40:1995 Gauss  
 H2 flow ==> 2:1:5 SCCM  
 RF power ==> 600:200:1200 Watt


**40192 configurations**

# Commissioning setup phases 1 and 2






# Semi-automatic characterization



In the graphical interface: **average**, **maximum** and **minimum** are evaluated and the trend showed for the beam pulse between 2.9 ms and 5.9 ms .


In the semi-automatic characterization code 26 parameters and two wave forms (@1Ms/s) are saved for each pulse produced at nominal repulsion rate of 14Hz.

# Data analysis of thousands of different configurations





# Fraction of beam current collected the Faraday Cup




Courtesy of O. Midttun (*University of Bergen*)

Increasing the plasma density increase the meniscus concavity and the divergence of the extracted beam.

**Simulation done with IBSimu** shows good agreement with experimental data.


# Data analysis of thousands of different configurations



# Doppler shift measurement beam characterization



Proton fraction > 75% SATISFIED





# ESS stable configurations versus injected $H_2$ gas flux and microwave power




Total current = 100 mA SATISFIED

Increasing the injected microwave power increase the energy transfer and consequently the plasma density

Each point is a large operative range (20 Gauss x 40 Gauss x 40 Gauss x 1 SCCM x 200 Watt)

Lower current (2-5 sccm)

High current (2-4 sccm)




# ESS nominal configuration




109 A coil1; 67 A coil2; 228 A coil3; 3 SCCM H<sub>2</sub>



Intra-pulse stability <  $\pm 2\%$  SATISFIED






Pulse to pulse stability <  $\pm 3.5\%$  SATISFIED



Minimum proton current range 67-74 mA SATISFIED



# Chopping performances






# Chopping performances



Rise time: 430ns



Fall time: 519 ns




Beam pulse shape measured with the ACCT located at the end of the LEBT

# Beam emittance at the center of the LEBT

A parallel beam is obtained between the two solenoids


Emittance (99%):  $1.43 \pi \text{ mm.mrad}$



# Beam emittance at RFQ location



Emittance file: emittanceHorizontal\_2017-9-12\_12-19.dat




Emittance measured after  
100 mm of the RFQ beam  
lattice interface.

Back tracing simulation under  
going to evaluate twiss  
parameters at LEBT-RFQ beam  
lattice interface

Transverse emittance **SATISFIED**

Emit [rms] < 0.25 Pi.mm.mrad

Emit [99%] < 2.25 Pi.mm.mrad



Beam extraction and Transport simulations in O. Midttun et al., T7\_We\_24



# Site Acceptance Review



	Name
Authors	Øystein Midttun
	Lorenzo Neri
	Cyrille Thomas

- ✓ Requirement achieved
- ✗ Requirement not achieved
- Requirement not possible to verify because of reduced commissioning time or missing beam instrumentation

## ION SOURCE PERFORMANCE AT THE END OF COMMISSIONING PHASE 2

Requirement	Value	Status
Nominal beam current	74 mA	✓
Maximum beam current	> 90 mA	✓
Proton beam current range	67 – 74 mA	✓
Proton fraction	> 75 %	✓
Pulse length	6 ms	✓
Flat top stability	± 2 %	✓
Pulse to pulse stability	± 3.5 %	✓
Beam energy	75 keV	✓
Beam energy fluctuation	± 0.01 keV	✓
Transverse emittance (99%)	1.8 $\pi$ .mm.mrad	■
Start-up after maintenance	< 32 hours	✓





Stable EMU was not provided in time

## ION SOURCE AND LEPT PERFORMANCE AT THE END OF COMMISSIONING PHASE 4


Requirement	Value	Status
Nominal beam current	70 mA	✓
Transmission	> 95 %	✓
Beam current range	6 – 70 mA	✓
Beam current precision	1 mA	✓
Vacuum pressure	< 6e-5 mbar	✓
Beam pulse flat-top length	0.05 - 2.86 ms	✓
Beam pulse rise/fall time	< 1 $\mu$ s	✓
Transverse emittance (99%)	1.25 $\pi$ .mm.mrad	✓
Twiss parameter $\alpha$	1.02 ± 20 %	■
Twiss parameter $\beta$	1.02 ± 20 %	■

Back tracing simulation under going

# Ready for ....




# Time line





# OES measurements





The Optical fiber is connected to the gas tube, via a quartz window and an adapter;

OES cone of view intercepts the plasma extraction region;



# From plasma to beam parameters



**PLASMA**  
parameters  
by OES



**BEAM**  
parameters  
Measured by  
ACCT and  
Doppler shift



# Conclusion & Perspectives

- The source works flawless since beginning of the year, some minor troubles typical of the commissioning phase have been met and solved.
- The source performance fully satisfy the ESS requirements
- Fast characterization procedure and data analysis have been the key points to speed up the commissioning phases, exploring source performance in a wide operational range
- First documentation has been provided to ESS (Drawings, Diagrams, FAT, ... )
- Second source procurement ongoing



*Thanks for your attention*



*Comments are welcome*

Thanks to all INFN-LNS staff to valuable support provided during all the phases of the project.

The collaboration with ESS and CEA was intense, profitable, always solution oriented.



**17th International Conference on Ion Sources**

October 15-20 2017

CERN - CICG - Geneva



# ECRIS 2018

## 23<sup>rd</sup> International Workshop on ECR ion sources



10-14 September 2018 *Catania, Diocesan Museum*  
Europe/Rome timezone



### Overview

Scientific Programme

Important Dates

Committees

Venue & Accommodation

Visa

GELLER Prize

Industry Exhibition

First Announcement



Istituto Nazionale di Fisica Nucleare  
Laboratori Nazionali del Sud

<http://ecris18.lns.infn.it>

STAY TUNED!