



# CMS HCAL Phase-I & II Upgrade Test Beam

A. Belloni

University of Maryland

B. Bilki

University of Iowa

A. Mohammadi

Kansas State University

N. Strobbe

FNAL




# Executive Summary



- Primary goal: test of FE electronics and photosensors for CMS HCAL Phase-I upgrade
  - Pion energy scans; 30-50-80-100-150-200-250-300GeV; about 100kevents/run; multiple FE configurations; selected  $\eta$ - $\phi$  towers served by SiPM photosensors (Phase-I upgrade) and HPD photosensors (legacy system)
  - Electron energy scans; 30-50-80-120-200GeV; about 2-4kevents/run; selected  $\eta$ - $\phi$  tower served by SiPM
  - Muon runs for MIP calibration
- Secondary goal: test of plastic scintillators for CMS HCAL Phase-II upgrade
  - 6.7Mevents; muons from 200GeV pion beam
    - About 50% more than in 2015 test beam
  - Muons and pions on SiPM-on-tile setup: O(10M)events


# A quick peek at the data



HCAL HB

## H2 Setup


J. Potarf  
Baylor University



HCAL  
HE

50GeV Pions

80GeV Electrons




HCAL HB

HCAL  
HE

## H2 Setup

Animations:  
[http://cmskam06.cern.ch/tb2017/detector\\_view/](http://cmskam06.cern.ch/tb2017/detector_view/)



200GeV Muons



- Efficiency vs. hit position
  - Fraction of events with integrated charge above pedestal
- Measurement of interest: map of efficiency and light yield vs. position
  - From left to right: EJ-200 irradiated at Goddard Space Flight Center (0.3Mrad); SCSN-81 (current CMS HCAL scintillator) irradiated next to LHC (2Mrad), square and rectangular tiles

# More Phase-II materials

150GeV Muons



Scintillator-X  
3x3cm<sup>2</sup> sample  
SiPM-on-tile

B. Bilki  
University of Iowa



Three 2.5x2.5x0.5cm<sup>3</sup>  
blue scintillator tiles

Silicon-based WLS fiber:  
2.5mm OD 1mm ID  
capillary with 3HF-doped  
silicon gel core





# Summary



- Start of test beam unusually smooth
  - One board broke on day-1; cooked up working system immediately (offering lower event rate), installed replacement within day-4 (back to full speed)
- Completed plan of measurements
  - Aggressively planned for more data, more configuration variants, but happy with collected sample
- Happy to acknowledge the support we received
  - Thanks to Henric, Nikos and Yiota, Laza, Beam Inst. Group (thanks for the wire chambers!), David J., Alexandre, the machine department