



PROJECT

# HPTPC

## PROTOTYPE PROGRESS



DATE

21<sup>ST</sup> MAY 2017


MARK WARD




# Overview

- \* Field Cage
- \* Pressure Vessel design
- \* Readout
- \* Hardware delivery
- \* 6 month plan










**Delrin  
Mechanical Support**

**Field Cage  
(Copper Rings)**

**Cathode**





**Delrin  
Mechanical Support**


**Anode  
(Amplification Region)**

**Cathode**




# TPC Field Cage

- \* 15 x 1cm wide copper rings provide field uniformity
- \* 1.2m diameter, 0.6m long cylindrical volume
- \* Volume  $0.65\text{m}^3$
- \* High-voltage supplied by CAEN 1470 and 1470A PSUs
- \* 150V/cm drift field, for optimal diffusion.
- \* Optical X/Y amplification plane readout
- \* Quadrant current readout via CAEN 6730






# TPC Commissioning




- \* Prior commissioning inside low pressure vessel
- \* CCD+Current readout of Anode successfully demonstrated at MIT.
- \* low pressure vessel and all equipment shipped to RHUL - Arrival in March






# TPC Commissioning




- \* Prior commissioning inside low pressure vessel
- \* CCD+Current readout of Anode successfully demonstrated at MIT.
- \* low pressure vessel and all equipment shipped to RHUL - Arrival in March





# High Pressure Vessel




- \* Fabricated by Cryovac S.L.
- \* Category IV pressure vessel
- \* Internal volume  $\sim 2\text{m}^3$
- \* Maximum rated pressure 7 BarG , 4.75 BarG (operating)
- \* Delivery at RHUL soon



# High Pressure Vessel


>1.2MN on 8 clamps  
at Max pressure



- \* Double o-ring compression seal
- \* TPC is mounted via 3 Delrin support structures
- \* 10 cm stand-off between TPC and vessel structure
- \* Mobile stand with adjustable height



# Vessel services





- \* 4 Quadrant Camera ports
- \* 2 End to End Camera ports
- \* Beam Window
- \* Gas Inlet
- \* Vacuum  
Agilent Triscrol 800
- \* 2 pressure safety routes  
(Fike 95% operating ratio Burst Disks)
- \* Vacuum Gauge  
Inficon PCG55x
- \* Pressure Gauge  
Wika A-10
- \* Electrical Feedthroughs  
Cathode Supply  
Anode Supply  
Anode Digitizer



# Beam Window


- \* Designed for use with a highly collimated beam
  - \* Custom Aluminium flange
  - \* 10.0 x 0.5 cm cross section
  - \* 0.2 cm thickness
- 
- \* If beam cannot be collimated, opposite side of vessel is blank, 1cm thickness






# Camera Ports

- \* Optics and CCD mounted to end flange
- \* Fairchild CCD486  
4096x4097 pixels (0.15 $\mu$ m pitch)  
61.44x61.45mm  
0.02 e/pix/sec dark count (at -60C)  
Low readout noise (<10e at 1MHz)  
Vacuum Cooled to -60 to 90C
- \* Commercial optics 50mm f/0.95 - f/1.2 lens  
(As fast as possible!)
- \*  $<0.07\text{mm}^2$  / pixel mapped to Anode  
(vixel size,  $\sim 270\mu\text{m} \times 270\mu\text{m}$ )
- \* 6cm thick Quartz window separates internal volume from CCD hardware.
- \* Allows readout to be serviced without opening the vessel





# Gas System Design




- \* Gas Sources - Scientific Grade CF<sub>4</sub>, Ar, N<sub>2</sub>, CO<sub>2</sub>
- \* Maintain <1ppm Purity gain and drift stability
- \* Check valve protected inputs
- \* Bellows sealed Valves used throughout.
- \* Gas actuated valves for remote operation.
- \* Option to add flow control
- \* Twin Safety relief paths



# Lab Status

- \* Lab space and services have been completed
- \* Soft-wall clean tent has been installed
- \* Taken delivery of low pressure vessel and all readout hardware
- \* Recommission TPC using low pressure vessel.
- \* Transfer operations to high pressure vessel





# 6 Month outlook

April Complete Lab and services at RHUL ✓

May Commission low pressure vessel (in progress)

June Delivery of high pressure vessel, complete safety inspections

July Install and commission TPC in high pressure vessel

August Full operation of DAQ and TPC in high pressure vessel

September Source runs and calibration

**Target 2018 CERN Test Beam**



# Summary

- \* TPC and Supporting hardware proven with low pressure vessel at MIT
- \* Low pressure vessel and supporting hardware arrived at RHUL late March
- \* High Pressure vessel due end of May
- \* Target full TPC operation by September