

New Intermediate BCTs for PSB Injection Watchdog

BI Day 2017

Sébastien Thoulet BE-BI-PI








- > INTRODUCTION
- > SPECIFICATIONS
- > SOLUTIONS USED
- > DISMANTLING OF OLD MONITORS
- > LABORATORY MEASUREMENTS OF TOROIDS
- > INSTALLATION OF MONITORS IN PSB
- > NEW ELECTRONICS DESIGN
- > FIRST TESTS ON PSB RING 3
- > STATUS AND PLANS



Measurement of injection efficiency after Linac 4 connection in LS2:

- ➤ Intensity comparison between 4 ring BCTs (BRi.BCTI*) in sector 8L1 and 4 BCTs (BIi.BCT20) in the injection lines.
- ➤ PSB Injection Watchdog stops beam if losses are too high.













SPECIFICATIONS

Indicative value. Depends of Linac 4 current source.

Beam	average current / train	# charges / μbunch	# μbunches / turn	train duration / turn	# charges / turn	# turns injected	# charges / ring	average current / train (at the end of the injection) (BCTI)
	[A]	[-]	[-]	[s]	[-]	[-]	[-]	[A]
LHC pilot	3.00E-02	5.32E+08	18	5.11E-08	9.57E+09	1	9.57E+09	3.00E-02
Linac 4 commisionning (1/10 optimum)	3.00E-03	5.32E+07	18	5.11E-08	9.57E+08	1	9.57E+08	3.00E-03
Linac 4 commisionning (optimum)	3.00E-02	5.32E+08	176	5.00E-07	9.36E+10	1	9.36E+10	3.00E-02
Nominal	3.00E-02	5.32E+08	222	6.30E-07	1.18E+11	64	7.55E+12	1.92E+00
Ultimate	3.00E-02	5.32E+08	222	6.30E-07	1.18E+11	150	1.77E+13	4.50E+00
	Linac 4 & injection line					PSB ring		

Many parameters to take into account:

• Large Intensity range in PSB (64 db):

- Min : 3 mA

- Max : 4.5 A


Number of Charges / µbunch.

Variable number of µbunches (train duration 50 ns to 630 ns).

Variable Turns number (up to 150 turns).


PSB Injection Watchdog:

- Comparison *per ring* between 4 BIi.BCT20 and 4 BRi.BCTI after 150 turns (max).
- Detect losses with an accuracy of 2 % rms at the end of the last injection.





SOLUTIONS USED



- Used four existing monitors BRi.BCTI (old BRi.TMD with 1 per Ring) after some modifications:
- Change the number of turns on the toroids.
- BCTs signal delivery on 4 ranges.
- TRIC card for Acquisition.
- FESA classes:
 - TRIC FESA for intensity measurements.
 - Correct range must be selected before injection.
 - WD FESA to measure losses and to trigger the CIBU:

BIi.BCT20 - BRi.BCTI > Threshold

- Watchdog card with CIBU interface :
- Interlock to stop the Beam.



DISMANTLING OF OLD MONITORS

- Removing 4 old monitors (110 Kg/pcs) in the PSB 16 December 2016 with the help of BI-ML section, vacuum group and transport service.
- Dismantle BCTs in tunnel.







> Transport to radioactive Lab. in B.867 to order to change the number of turns on the toroids.








DISMANTLING OF OLD MONITORS

Removed carefully the vacuum chambers inside the monitors:






Vacuum Chamber

Removed sensors from the magnetic shielding:





BRi.TFA.8L1 (Fast BCT)


BRi.TSW.8L1 (Slow BCT)

BRi.TMD.8L1 (Intermediate BCT)



LABORATORY MEASUREMENTS OF TOROIDS

- ➤ Old toroids were kept but we have changed the windings to comply with new specifications.
- > Replaced old coaxial cables.






LABORATORY MEASUREMENTS OF TOROIDS

Last check before replacing monitors:

- Signal polarity (correct winding direction).
- Signal amplitude (correct numbers of turns and load resistor).
- Time constant.

All Test are $OK \implies$ Replace monitors in PSB.












INSTALLATION OF MONITORS IN PSB

➤ Monitors replaced in PSB 10 March 2017.



IMPACT n° 85382

15/12/16 to 17/03/17

Estimated collective dose

Real collective 48 μSν

Real collective dose received








NEW ELECTRONICS DESIGN

General Layout:



Tunnel:


- Head Amplifier with calibration control.

> Surface:

- <u>BOR 747</u>: Distribution Amplifier in NIM Crate (x2 / BCT).
- BOR 771 :
- TRICs Card Acquisition (200 MHz) in same VME Crate BIi.BCT20 (x1 / BCT for 2 Ranges).
- Watchdog Card to trigger the CIBU.

> Software Interface:

FESA Class to be defined.






NEW ELECTRONICS DESIGN


Test bench in the Lab

Frequency Response Test bench + BCTI.8L1










	Analog Distribution to OASIS, local scope, $(50\Omega$									
	input)									
Range	SF	FS	FS	LF Cut off	HF Cut off					
	[A/V]	[A]	[V]	[Hz]	[MHz]					
Range 1	5.00E+00	2.50E+01	5	18	38					
Range 2	1.00E+00	5.00E+00	5	18	38					
Range 3	2.00E-01	1.00E+00	5	18	38					
Range 4	4.00E-02	2.00E-01	5	18	38					

<u>Head Amplifier</u> <u>output signal for Range 1</u>





FIRST TESTS ON PSB RING 3

Electronics Installations and Cabling on Ring 3:

Tunnel 8L1










BOR 747




Distribution amplifier





FIRST TEST ON PSB RING 3

> First Beam Measurements with LINAC II





STATUS

- First Beam seen on Ring 3.
- NIM Crate is ready to receive Electronics modules.
- All Head Amplifiers are assembled.
 - Test in progress.
- Distribution Amplifier PCBs are being assembled.

<u>PLAN</u>

- Continue the Global test bench on the Lab : ⇒ BIi.BCT20 and BRi.BCTI.
- Install Head Amplifiers (Ring 1,2,4) (TS in July).
- Install all Distribution Amplifiers.
- Install TRIC cards (x4) and Watchdog card.
- Pull cables for :
 - Distribution Amplifiers (BOR 747) to TRIC cards (BOR 771).
 - OASIS.
- Define WD FESA Class together with OP.
- Calibrate the monitors.
- Test the watchdog if losses are detected.



> Thanks to:

- PI Section : Patrick Odier, Romain Ruffieux, Juan Carlos Allica, Lars Soby, Celine Delevaux.
- ML Section: Morad Hamani, Benjamin Moser, William Andreazza.
- SW Section : Lars Jensen, Athanasios Topaloudis.
- OP-PSB: Bettina Mikulec.
- Vacuum Group : Paul Demarest.
- Transport Services.