



Interconnection boxes : DFX

International Review of the Conceptual Design of the Cold Powering System for
the HL-LHC Superconducting Magnets : 3-4 July 2017

Outline

- Context : DFH-SCLink-DFX cryostat
- Planning and milestones
- DFX design
 - Conceptual layouts
 - Detailed design overview
 - Identified key technical challenges
- Next steps

Note: 3D models are illustrative, the detailed design of the DFX is not started yet.

Context

- Each IP1 and IP5 sides equipped with 2 cold powering chains of cryostats
 - Triplet insertion : **DFH – SC Link (DSH) – DFX**
 - Matching sections : **DFH – SC Link - DFM**
- DFX basic functions:
 - Electrical interface** between SC Link and triplets string (Q1-D1) through D1 cryostat
 - Supply cryogenics** to the SLink






Illustration of the position of the DFX
(not latest version for details)


Planning – DFX & DFH cryostats key dates

- Strategy: Design of DFX-DFH cryostats series
 - In parallel with demonstrator to validate choices
 - Prototypes to be tested in string




DFX concept

- Key concepts:
 - Main boundary conditions for the design:
 - Future **maintenance** carried out in an **activated zone** → to be limited and optimised
 - Interferences with the beam tube shall be minimised
 - Mechanically independent from the beam tube and the SC link.
 - No perturbation to beam alignment (∇ vacuum loads, thermal contraction loads, SC link loads, cryogenic pressure fluctuations)
 - No constraints from beam specs.
 - Electrical continuity



Insulation vacuum layout

- DFX insulation vacuum shared with triplet insulation vacuum
- SCLink has independent vacuum volume and equipment.
- Figures:
 - Target value : 1.10^{-5} mbar
 - Design pressure of vacuum vessels PS < 1.5 bara
- Objective :
 - adapt conductance at D1-DFX to avoid additional pumping equipment (and associated maintenance).
 - Dedicated relief pressure protection




Cryogenics layout

General layout : see Serge Claudet's talk

- Thermal shielding :
 - Conduction cooled from triplets circuit : $T_{max} < 95 \text{ K}$
 - Line for SCLink thermal shield active cooling 20 K
- T_{max} of superconductors in DFX:
 - $T(\text{Nb-Ti}) < 5.5 \text{ K}$
 - $T(\text{MgB}_2) < 20 \text{ K}$
- Superfluid helium volume from triplets
- Saturated helium bath @ 1.3 bara
 - Vapor produced to match current leads needs (heaters to produce up to 10 g/s)

- Principle:
 - Heaters (designed up to 200W) vaporizes liquid forcing the gaseous mass flow through the SCLink
- Key technical challenges :
 - Plug between SFHe and LHe (replaceable)
 - Lhe-Ghe interface
 - Interfaces to D1, to SCLink
 - Instrumentation redundancy policy
 - Heaters technology
 - Splice resistivity definition



Heat loads preliminary estimations

To the 40-60K Triplets TS circuit : $\approx 20\text{ W}$


- Radiative heat exchange : Thermal shield equipped with MLI : $\dot{Q}_{rad} \approx 10\text{ W}$
- Conduction heat exchange : supports : $\dot{Q}_{cond} \approx 10\text{ W}$

To the 4.5 K saturated bath:

- Dynamic loads :
 - Nb-Ti/Nb-Ti : LHC experience $R < 1.5\text{ n}\Omega$ @ 3σ
 - $\text{MgB}_2/\text{Nb-Ti}$: $R \approx 10\text{ n}\Omega$ starting point, studies on-going
 - \rightarrow Total splices heat dissipation $< 10\text{ W}$ (Iult)


To the 4.5 K saturated bath:

- Static loads : $< 20\text{ W}$
 - Supports + services : $\dot{Q}_{cond} < 20\text{ W}$
 - Through plug : few Watts to 1.9 K volume



Mechanical layout


- Fixed points
 - Vacuum envelopes :
 - SC Link, DFX, independent from D1-Beam tube
 - Helium vessels
 - SC Link, DFX, independent from D1-Beam tube
 - Cables fixed points :
 - SC Link, Plug
- Thermal contraction
 - MgB₂ cables in SC Link (see P. Retz' presentation)
 - DFX cables : locally
 - D1 interface cables: to be studied
- Challenges
 - Interface D1
 - Installation (see V. Parma's presentation)



Electrical layout

- Clear configurations at both ends
- Key challenges for the DFX
 - Integrate splices for accesses, maintenance
 - Prepare SCLink end before installation
 - New cables to be developed → new splices, new tooling, new integration

See K. Konstantopoulou and A. Ballarino's talks




D1 circuit : 2 x 13 kA cables

Trims: 3 x 18 kA cables (new to be developed)
Triplet circuit : 2 x 18 kA


MCBXF: 12 x 2 kA cables (new to be developed)
Correctors: 18 x 0.6 kA cables

See E Todesco's talk




Maintainability

- Instrumentation → redundancy being evaluated
 - T-sensors
 - V-taps
 - Level gauges
 - Heaters
- Safety devices → access optimised
- Vacuum equipment (valves + pumps), leak detection access if required : to be studied
- Plug is foreseen replaceable
- Access to Nb-Ti/Nb-Ti solders optimised
- Maintenance of MgB_2 -NbTi solders may require :
 - Disconnection of Nb-Ti solders
 - Disassembly of SCLink-DFX
 - No spare MgB_2 cables
- All maintenance operations to be performed in radioactive environment




Installation sequence

- D1 and electrical connection up to plug pre-installed
- Installation DFX + SCLink (see V. Parma's presentation)
- Welding Helium volumes DFX-SCLink
- Insulation vacuum interface DFX-SCLink
- Electrical connection Nb-Ti / Nb-Ti
- Closure Helium volume
- Thermal shield
- Vacuum vessel sleeve



DFX design : 3D Model



Note: illustrative 3D model

Identified key challenges

Work on identified technical challenges



- Plug : **activity starting** (resources available from October)
 - State of the art studied
 - Dedicated lab being set-up
 - Be able to reproduce existing plugs used in LHC
 - → **Adapt to new cables, new specifications**
- Heaters technology : **well advanced**
 - Specs. of needs and state of the art studied → report soon in EDMS (I. Falorio)
 - Technical solution based on CERN cryogenic group's experience
- LHe-Ghe barrier : **being studied**
- Splices resistivity:
 - NbTi-NbTi : based on LHC measurements campaign measure as basis (March 2012)
 - MgB2-Nb-Ti : **studies on going**
- Splices integration : **in progress**
 - Mock-up in SMI2 for real visualisation and future access testing
 - 3D study in parallel
 - → **define overall integration**
 - → **define conductance with D1 and pumping equipment needs**
- Mechanical interfaces with D1 : **being studied**
 - D1 : cryogenic integration, fixed points for piping, cables.
- Mechanical interfaces with SCLink : **studies in progress**
 - Installation (see V. Parma's presentation), detailed design,

→ **Focusing resources on technical challenges**

DFX plug laboratory (SMI2)




LHC experience



Conceptual 3D modelling

Splices layout mock-up



Conclusions

- The DFX design is well advanced within limits of today's knowledge
 - Needs are clear and detailed specs are in progress (first-order values defined)
 - Engineering concepts defined and feasible (most from LHC experience)
 - Key challenges identified (e.g. plugs, splices) and *ad-hoc* actions being implemented
 - Several technical challenges ahead but no showstoppers identified
 - The engineering and detailed design workload remaining is heavy, especially considering parallelism on various working fronts
- Forthcoming activities:
 - Design of SC link extremity and integration of SC link cable (MgB₂-NbTi extensions geometry)
 - Design/construction of a DFX demonstrator (DDFX), a focused prototype to validate the DFX main concepts for a system test from April 2018
 - The DFH: start conceptual design, aiming at an overall concept towards end 2017
 - 2018 should be dedicated to detailed design and drawings for procurement of DFX and DFH prototypes for a procurement to start in Q4 2018