

Presentation of vertical test cryostat, main interfaces, common mechanical adaptation

H. BAJAS TE-MSC-TF



SM18, 07-06-2017, D2 Short model Cryogenic test interface meeting #01

SM18, 07-06-2017, D2 Short model Cryogenic test interface meeting #01


Outlines

- Vertical test benches at SM18
- Cryostat and Insert
- Mechanical interface: Insert / Magnet
- Power connection: Leads / Magnet
- Electrical interface: Insert / Probes
- Data Acquisition Systems





Vertical test benches at SM18




OPERATION


HILUM

- I= 0.12 kA-30 kA
- T = 1.9 K to 70 K He
- withstanding U = up to 3 kV

Vertical test benches at SM18




D2 magnet




1553 lenght (without support)






Cryostat and Insert Cluster D



- Current leads
- CLIQ lead
- Quench heater
- Instrumentation
 - Connection box
- Magnetic measurement

Magnetic measurement

3x MRU Passage (Motor Rotating Unit) – ø40



Mechanical interface: Insert / Magnet






Mechanical interface: Insert / Magnet

Agreement on:

- Rods / Intermediate Plate / Magnet
 - Drilled holes on the plate (adaptable)
 - Holes on magnet structure (handling)





 λ plate


Holding plate



Power connection: Leads / Magnet

Agreement on:

- Magnet NbTi leads path
- Copper stabilization
- Cable dimension for clamp









Electrical interface: Insert / Probes


Types of sensor


- Vtaps
- Strain gauges
- Fiber Optic Sensor
- CERNOX

Types of connector

- λ-plate / Magnet
 - Burndy (Vtaps, QH)
 - M3 flat connector (SG)
 - Optic interconnect
- Connection box
 - Fisher (40 ou 8 pins)











Electrical interface: Insert / Probes



Data Acquisition Systems



Data Acquisition Systems



DAQ SPECIFIED PARAMETERS

Input channels: Nr of HF channels: HF frequency: HF,MF,LF resolution: HF,MF,LF accuracy: MF frequency: Nr of LF channels: LF frequency: Timing:

+/- 10 V ar 200 differential 200 kHz on: 16 bit resolution cy: 1mV 50 kHz : 144 1kHz GMT synchronization

NI PXIe-6358

Simultaneous X Series Data Acquisition



Zoom/Alternate Images

Example of HF system

Starting at \$6,086 \$5,355.68 (view pricing options)

View Data Sheet

- 16 simultaneous analog inputs at 1.25 MS/s/ch with 16-bit resolution; 20 MS/s total Al throughput
- Four analog outputs, 3.33 MS/s, 16-bit resolution, ±10 V
- · 48 digital I/O lines (32 hardware-timed up to 10 MHz)
- · Four 32-bit counter/timers for PWM, encoder, frequency, event counting, and more
- Analog and digital triggering and advanced timing with NI-STC3 technology
- Support for Windows 7/Vista/XP/2000



Data Analysis with DIADEM






Discussion

- Need to agree on:
 - Cryostats: HFM or Cluster D would host D2.
 - Technical drawings for CAD integration (Insert / magnet / magnetic shaft)
 - Instrumention number and connector cabling
 - Magnet integrity checks (High Voltage test requirement, quench protection strategy)
 - Test plan details (standard procedure to be adapted to D2)
 - Planning for 2018 (delivery at SM18, test due date)



Thank you for your attention





🗅 Can't reach 🗐 Cern Authe 🗅 Demande c 🖨 Minutes_m 🖨 50 Bowery \Sigma MTF Applic 🔕 D2 Shc × 🖨 INFN_D2_sl 🖨 LHCQDTF_C 🖨 0953-2048_ +	– 0 ×
$\leftarrow \rightarrow \circlearrowright$ \triangle indico.cern.ch/event/645011	
09:30 \rightarrow 09:50 Magnetic measurement requirements, (INFN) discussion on hardware adaptation, actions (CERN)	③ 20m
09:50 \rightarrow 10:05 Presentation of vertical test cryostat, main interfaces, common mechanical adaptation, (CERN TF)	③ 15m
10:05 \rightarrow 10:20 Instrumentation table by INFN, discussions (all)	③ 15m
10:20 → 10:40 Discussion on DAQ instrumentation interface : connectors types (QHs, VTs, SG, TS) , leads lengths, number of channels (CERN TF, EN-MME M Guinchard)	O 20m
INFN_D2_short Mod	
10:40 \rightarrow 10:50 Optical strain fiber experience on MQX, discussion coil OF sensing proposal (A. Chiuchiolo)	③ 10m
10:50 \rightarrow 11:10 Discussion on interface preparation of coils, cryostat (structure preload, splices on leads, Cryostat interface flange,) (INFN, CERN)	O 20m
11:10 \rightarrow 11:25 QA Hi-Voltage test before transport (INFN), at reception and after CD test (CERN)	③ 15m
11:25 \rightarrow 11:40 Quench protection test interface, Common Test scenario plan proposal (CERN, MSC TF,LMF), discussion all.	③ 15m
11:40 \rightarrow 11:50 Overall updated SM coil Schedule (INFN)	③ 10m
🕂 Search the web and Windows 🦻 📄 🖄 🥼 🔕 😵 📴 🦻 💶 🖬 🖬 🔂 🕞 🗈	c∱



SM18, 07-06-2017, D2 Short model Cryogenic test interface meeting #01

Cluster D : on going upgrade

