



LHC Injectors Upgrade





LHC Injectors Upgrade

Status of the PSB SEM grids for injection matching

Jocelyn TAN, BE-BI

On behalf of C. Vuitton, G.J. Focker, F. Roncarolo, R. Veness, B. Riffaud



Outline

- Motivations
- Specifications
- Status
- Summary



Motivations

- **Why?** Measure the transverse matching and the emittance of the beam injected from Linac4
- **How?** see [Engineering specification](#): Inject $\frac{1}{2}$ PSB turn (ie ~ 500 ns long pulse) and acquire up to 20-30 circulating profiles of the circulating beam with a SEM.
- **When?** Installation during YETS17-18 for beam commissioning in 2018.



Dedicated operation mode

- Beam parameters


Beam kinetic energy	160 MeV
Beam intensity	5×10^9 to 2×10^{11} protons
Beam pulse length	50 to 500 ns
ϵ_{rms} of incoming beam	0.5 μm
Beam size (H/V)	1.1 to 2.4 mm (rms)
Beam size resolution	<2%

- A pair of monitors (H+V) in one ring is sufficient: ring3.
- Permanent implementation for setting up new beams and MDs.
- Protection of fragile wires
 - Not PPM for reliability reasons
 - External condition interlock to prevent injection of more than 1 turn while the monitor is in.
- Beam dumped after ~ 100 turns: set BT line for extraction at 160MeV.



Scattering angles and energy loss with graphite

Compact monitor
Grid size : 25.2 mm
64 graphite wires



wire spacing 0.4 mm
Diameter $\varnothing = 33 \mu\text{m}$

Density ρ	radiation length X_0	wire spacing w	wire radius r
2.265 g/cm ²	18.8 cm	0.4 mm	17 μm

➤ Average values for average (effective) thickness $d = r^2 \pi/w = 2.1 \mu\text{m}$

➤ Rms scattering angle $J_{rms,max} = \frac{13.6 \text{ MeV}}{b_r^2 g_r E_r} \sqrt{\frac{d}{X_0}} = 0.15 \text{ mrad}$

➤ With logarithmic correction : $\mathcal{G} = 0.09 \text{ mrad}$

➤ Energy loss $DE_{av} = -2.2 \text{ keV}$ corresponding to $\frac{Dp}{p} = \frac{1}{b_r^2} \frac{DE_{av}}{E_{kin} + E_r} = -0.0075 \cdot 10^{-3}$

➤ Blow-up (phys. rms emittance) due to interaction with monitor: **0.06 $\mu\text{m}/\text{turn}$**

⇒ **Blow-up per turn due to monitor almost one order of magnitude lower than the expected emittance of 0.5 μm (rms)**

⇒ **Measurement can be envisaged**

Remarks:


- Expect significant tails, which may lead difficulties with profiles widths estimates (systematic errors)
- Thick frame ($\pm 15 \text{ mm}$) for stopping scattered protons



Other considerations

Electronics: still under development

- Beam interaction : ~ **10 μ A max** in the graphite wire
- Tungsten would yield ~3x larger signal but proton scattering is also larger
- Amplifier Type Linear, Integrator in the ADC module
- Input impedance 93 Ω
- Bandwidth >5MHz
- Sampling rate 1 MHz
- Cable length the shorter the better (max ~25 m)
- 2018: Commissioning with a prototype



10 μ A max

Concerns on ageing

- Sensibility of central wires seeing more beam reduced w.r.t. outer wires

Cabling: plan #10071



- Budget charged by EN/EL in 2016

ECR

- It will be done when the integration work is complete.



Mechanics: integration in 4L1




YETS17-18 : installation on a temporary support structure

LS2: The final support system (in blue) will be installed with the series of wire scanners


Courtesy: B. Riffaud



Mechanics: grids actuation



- No bellow
- Actuation by magnetic motors:
 - translation for H plane
 - rotation for V plane
- Animation example below: PS SEM grid
- Wiring in vacuum: use of extruded kapton
- First tests of grid assembly: **end of June**





Planning and budget

	June	July	August	September	October	November	December	January	February	March
3D drawing & approval process	Yellow bar									
tank & support prod + cleaning				Blue bar						
Grid & monitor assembly + VSC		Orange bar								
Aqn chain	Green bar									
ECR		Grey bar								
Installation								Red bar		
Commissioning										Green bar

- Tight mechanic production schedule
- It should be supported as a priority in MME by the LIU project

2016

- Cabling+electronics 57 kCHF

2017: 65% committed

- Design office 15 kCHF
- Acq chain+actuators 45 kCHF
- Monitor production 20 kCHF

2018

- Installation 4 kCHF



Summary

- Mechanical design nearly completed
- No below for enhanced reliability
- Monitor should be installed in YETS 17-18, but...
- We need LIU support to set Tank production as high priority for EN-MME in Q3-2017
- Beam commissioning will likely take place with a prototype board.



LHC Injectors Upgrade

THANK YOU FOR YOUR ATTENTION!

