



R&D for the Short-Baseline Near Detector (SBND) at FNAL

Jo Pater

The University of Manchester (UK)


On behalf of the SBND Collaboration

NNN17 – Warwick, UK – 26-28 October 2017


The SBND Collaboration



190 collaborators
from 35 institutes
in 4 countries



Fermilab's Short-Baseline Neutrino Programme




Booster Neutrino Beam

5×10^{12} protons/spill, max spill rate 5 Hz

Three detectors (liquid-argon TPCs):

	distance from target (m)	TPC active volume (tons)
SBND	110	112
MicroBooNE	470	80
Icarus T600	600	600

SBND's Experimental Programme




- Physics goals:
 - measure un-oscillated ν content of BNB to enable oscillation measurements as near detector
 - sterile ν search
 - study ν -nucleus interactions in argon
 - detection of supernova ν , dark matter searches, etc.
- Prototype for long-baseline programme (DUNE)

The SBND Detector



Main components:



- Liquid Argon Time Projection Chamber
 - 112-ton (active volume)
 - Cold and warm readout electronics
 - Light Detection System
- Cryostat
 - stainless-steel membrane, passive foam insulation
 - TPC is supported from cryostat lid
- Cosmic Ray Tagger
 - background rejection
 - scintillating bars + SiPMs
 - $\sim 4\pi$ coverage



SBND TPC Design




- Central cathode plane
- Anode planes at sides
- Dimensions:
 - 5m long (beam direction)
 - 4m wide, 4m high
- Surrounded by field cage
 - roll-formed stainless steel profiles (lower drawing)
 - drift field 500 V/cm



Anode Plane Assemblies



- Two linked frames at each side of TPC
 - 2.5 x 4.0 m² each frame
 - Stainless steel rectangular hollow section, welded
 - precision-drilled fixation holes
 - flatness ($\pm 0.5\text{mm}$) achieved with shimmed levelling plates.
 - Laser survey determines required shim thicknesses.
- 3 of 4 frames delivered to wiring sites





Anode Wires



3 wire planes:

- vertical, $\pm 60^\circ$
 - 832 + 1568 + 1568 wires per frame
- 150 μm diameter Cu-Be wire
 - ~same CTE as stainless steel
- soldered and epoxied to PCBs (G10) fixed to APA
 - 3mm wire pitch
 - 3mm wire plane spacing
- angled wires are jumpered between adjacent frames
 - continuous readout across width of the anode plane
- read out at top and sides



APA Wiring Techniques




Two techniques being trialled - both could be scaled to any size frame.

Wire-by-wire "robot"


semi-automated wiring head travels
on beam above frame

→ automatic wire positioning,
tensioning



Multi-wire "shuttle"

up to 50 wires tensioned and
positioned at once




APA Wiring Status



Both wiring stations are operational on small test frames (~1/4 size).


Wire-by-wire robot



APA Wiring Status, cont'd



Multi-wire shuttle



Wiring of full-size frames to being very soon.

Wire Quality Control



- All QC is per-wire and performed before the next layer of wires is added:
 - electrical continuity
 - electrical isolation from nearest neighbors and frame
 - acceptably low bias current
 - tension: checked by measuring fundamental oscillation frequency of wire: $f \propto \sqrt{T}$
- Repeat (some of) the above
 - after a cold cycle
 - after transport

APA Cold Testing



- Finished APAs will be cooled to ~ 100 K to verify that wires are robust:
 - no breakages
 - no significant change in electrical performance
 - no significant change in wire tension
- cool-down rate is important
 - 50-60 K/hour
 - lets frame (larger thermal mass) shrinkage 'catch up' with wires
- avoid condensation on warmup




APA Cold Testing, cont'd




J. Pater - R&D for SBND at FNAL

NNN17 - 26-28 October 2017



Preparing for cold test early
October 2017


Partially-wired test frame and
full-size (unwired) frame



Cathode Plane




- Made of 2 rectangular frames:
 - welded tubular steel construction
 - electropolished – no sharp edges
 - each frame holds 8 wire-mesh panels
 - held at -100 kV
- HV feedthrough at top
- Construction nearing completion



Light Detection System






- Scintillation light:
 - trigger, t_0
 - background rejection
 - calorimetry, particle ID
- Mounted on anode planes:
 - PhotoMultiplier Tubes
 - Scintillating bars read out with SiPMs
 - both PMTs and bars are coated with wavelength shifter (WLS)
- Possible additions (currently in R&D phase):
 - WLS-coated reflector foils on cathode plane could improve performance
 - photon trapping boxes on anode plane to boost efficiency



Readout Electronics






- Front-end:
 - FE ASIC: amplification, shaping
 - ADC
 - Multiplexing
 - On anode planes – cold!
Careful testing needed at temperature.
- Feed-through → warm interface on top of cryostat
- Readout and trigger in surface building



Synergies SBND-DUNE



- Same:
 - cryostat technology
 - TPC construction and support concepts
 - APA wire bonding design (stacked PC boards)
 - CPA design concept
 - Front-end electronics
- Similar:
 - APA frame design
 - APA wiring concept
 - field cage design
- Test-bed for future light detection system elements




Schedule / Summary



J. Pater - R&D for SBND at FNAL

NNN17 - 26-28 October 2017



Anne Schukraft, June 2017

On schedule for installation in 2018,
commissioning in 2019




Backup slides

How a TPC Works



J.Pater - R&D for SBND at FNAL

NNN17 - 26-28 October 2017



Tension Measurement



Wire tension is checked by measuring fundamental oscillation frequency of wire ($f \propto \sqrt{T}$). 2 methods:

- laser / photodiode / spectrum analysis
 - wire by wire, topmost layer only
- purely electrical method
 - faster (measure many wires at once)
 - works on lower layers (connection through wiring PCBs)
 - compatibility with electronics being investigated
 - not compatible with short (corner) wires

