


Extra Low ENergy Antiproton ring ELENA



C. Carli on behalf of the AD/ELENA team(s)

LEAP 2018, 12th March 2018



- Introduction
- Selected Features and Challenges
- Status of ELENA Ring Commissioning
- Status of Electron Cooler
- Plans for 2018
- Summary and Outlook

Introduction




- Controlled deceleration of 5.3 MeV Antiprotons from AD down to 100 keV and electron cooling
- Improved capture efficiency of (typical) existing experiments and new types of experiments (GBAR)
- Magnetic ring and injection line, electrostatic ejection lines (effective at low energies)
- Challenges related to low energy (e.g. magnetic field quality) and intensity

Injection with magnetic septum and kicker

Magnetic Pick-up
(Schottky diagnostics for intensity, LLRF..)

Extraction towards new experimental zone (GBAR) - fast deflector followed by el.-static transfer lines



Electron Cooler after 1st installation in December,


Transfer line from AD

Extraction towards existing experiments

Scraper to measure emittance

Wideband RF cavities (very similar to new PSB cavities)

Introduction



- ELENA in AD hall with existing (AD experiments) and new experimental area
 - Seen from the door to the new small annex building (for kicker generators and storage)
 - Cost effective with short transfer line from AD and no relocation of existing experiments

Selected Features and Challenges



■ Energy Range

- Machine operated at an unusually low energy for a synchrotron (down to 100 keV!)
- Challenges mainly a consequence of the low energy

■ Electron cooling


- Essential ingredient of concept
- Cooling at intermediate plateau to reduce losses and the final energy 100 keV to provide dense bunches
- Bunched beam cooling at 100 keV to reduce momentum spread of short bunches
- Perturbations of magnetic system on circulating beam difficult to assess
- See dedicated slides on status

■ Intra Beam Scattering IBS

- Coulomb scattering between beam particles
- Emittance blow-up due to transfer of heat (unordered motion) between phase spaces (long. & transverse)

■ Characteristics of beam sent to experiments given by the equilibrium between


- Electron cooling
- IBS increasing emittances



Selected Features and Challenges



- Direct space charge effect
 - Coulomb force between beam particles generate non-linear defocusing force
 - Initial reason to split available intensity into 4 bunches
 - Sensitivity to magnetic stray fields
 - Magnets operated with very low fields
 - Possible imperfections due to hysteresis
 - “Thinning” (mixing of stainless steel and magnetic laminations) had been foreseen initially and expected to improve
 - Careful magnetic measurement with pre-series quadrupoles showed smallest remanence with conventional yoke (no thinning)
 - Observation confirmed with bending magnet prototype and understood now
- ⇒ Magnet thinning does NOT improve field quality at low fields, but rather increases remanence effects
- ⇒ ELENA bending magnets, quadrupoles and sextupoles made with conventional yokes
- (Corrector magnets without yokes)



Prototype quadrupole to investigate magnet “thinning” on the measurement bench

Selected Features and Challenges



- Rest gas interactions and vacuum system
 - $3 \cdot 10^{-12}$ Torr nominal pressure - fully baked machine with NEGs wherever possible (technical problems as peel-off with NEG coating of stainless steel chambers)
 - Interactions of beam with rest gas to be evaluated with care, not the dominant limitation
- Beam diagnostics with very low intensities and energy
 - E.g.: beam currents down to well below $1 \mu\text{A}$ far beyond reach standard slow BCTs
 - ➔ Intensity of coasting beam measured with Schottky diagnostics (observing noise generated by coasting beam on a pick-up, special pick-ups design to limit background noise)
- Electrostatic transfer lines to experiments
 - Cost effective at very low energies
 - Many quadrupoles allow a design with small “betatron functions” and large “betatron phase advance” (small beam sizes) limiting impact from stray fields
 - Easier for shielding against magnetic stray fields
- RF system with modest voltages, but very large dynamic range
- H^- and proton source (and electrostatic acceleration to 100 keV) for commissioning
 - ELENA commissioning independent of AD, precious antiprotons kept as much as possible for experiments
 - Higher repetition rate but start commissioning at the difficult low energy part of the cycle
 - Antiprotons needed to complete ELENA ring commissioning

ELENA Beam Parameters

Present best guess combining different Sources



Step in cycle	ε_L (meVs)	σ_p/p (10^{-3})	σ_E (keV)	σ_T (ns)	$\varepsilon_{H,rms}$ (μm)	$\varepsilon_{V,rms}$ (μm)
Injection ^{+,a)}	3.5	0.25	2.8	98	0.5	0.3
Start 1 st ramp ^{+,b)}	3.5	0.49	5	53	0.5	0.3
End 1 st ramp ^{c)}	3.5	1.4	1.8	150	1.8	1.1
Start plateau 35 MeV/c ^{d)}	5.2	0.46	0.6	coasting	1.8	1.1
End plateau 35 MeV/c ^{e)}	1.7	0.15	0.20	coasting	0.45	0.42
Start 2 nd ramp ^{d)}	2.5	0.84	1.1	180	0.45	0.42
End 2 nd ramp ^{c)}	2.4	2.1	0.42	455	2.2	2.5
Start plateau 100 keV ^{d)}	3.6	0.81	.16	coasting	2.2	2.5
Cooled coasting 100 keV ^{e)}	1.1	0.25	.050	coasting	0.3	0.2
Cooled bunched 100 keV ^{f)}	4 x 0.12	0.60	.120	75	1.2	0.75

$\varepsilon_{rms} = \sigma_p^2/\beta_T$ with σ_p the rms betatron beam size and β_T the Twiss betatron function

+) difficult to determine due to (i) dense core and long tails, (ii) variations with time

a) Typical values measured with AD – some reduction of long. Emittance with bunched beam cooling


b) Increase of voltage from 16 V at transfer to 100 V on ramp

c) Simulations of IBS on ramp


d) Debunching/bunching with 50% blow-up (bunched with LHC def. $\varepsilon_L = 4\pi \sigma_E \sigma_T$, coasting $\varepsilon_L = 4 (2/\pi)^{1/2} \sigma_E T_{rev}$)

e) From ELENA technical meetings with presentations by G.Tranquille and P. Beloshitsky

Results from ELENA Commissioning – Ion Source and Line from Source to Ring



- Technical issues despite serious preparations and early testing
- Energy lowered from 100 keV to 85 keV for 2017
- Quadrupole scan to measure beam characteristics:
Variation of the setting of (two) quadrupoles and observation of beam sizes with a monitor (TV screen between septum and kicker)
- Reconstructed characteristics at the reference location
Hor.: $\epsilon_{x,rms} = 4.71 \mu\text{m}$, $\beta_x = 1.4151 \text{ m}$ and $\alpha_x = -3.0061$
Vert.: $\epsilon_{y,rms} = 5.08 \mu\text{m}$, $\beta_y = 0.8381 \text{ m}$ and $\alpha_y = -2.6142$
- Improved setting of line not (yet) tested




Ratio between measured beam size and beam sizes from reconstruction

Results from ELENA Commissioning – with H⁻ Beams from Source





- Beam energy 85 keV instead of 100 keV because of problems with the source isolation transformer
- Few 100 ms life-time observed with RF (very basic functionalities) since spring
- Successful commissioning of orbit system, orbit correction, partly tune system, scraper ..
=> confidence in “lattice” with working point and orbit correction behaving about as expected
- Issues during summer: poor reproducibility (shot-to-shot fluctuation and long term drift) of H⁻ injection, sometimes technical problems with source, more time than expected to install GBAR line
- Improved reproducibility of injection from around September (Why? Just careful tuning?)
- Two long bunches with about $1 \cdot 10^6$ to $2 \cdot 10^6$ H⁻ ions each after 140 ms
 - Improved reproducibility (similar bunches for several cycle), but still low intensity
 - With RF capture after filamentation (injection with RF off)



Results from ELENA Commissioning – with H⁻ Beams from Source




- H⁻ extraction into LNE50 line towards GBAR
 - Aim: preparation of first beam for an experiment – transfer to GBAR now planned for April
 - Modification of timings system: revolution train generated by the Low Level RF system (LLRF) to trigger source and fast deflector for extraction
 - Possible to inject with RF on (into “buckets”) to keep small longitudinal emittances and short bunches (had not been foreseen initially)
 - Fast deflector for extraction synchronized with RF
 - Signals clearly due to beam on monitors in line, but impossible to interpret in terms of beam position and width




Results from ELENA Commissioning – with H⁻ Beams from Source



- Results from the very end of beam time in 2017
 - Improved life-time with phase loop of RF system
 - Allowed further increase of life-time to > 1s by adjustments of quadrupole currents
 - Small amount of beam accelerated (was not aim at that time)




- RF System
 - Issues with noise on magnetic pick-up and low intensity
 - ⇒ RF system uses sum signal of position pick-up to detect beam phase
 - Phase and radial loop operational
 - Indications for improved life-time with phase loop
 - Sometimes sudden jumps of frequency from “B-train” excite synchrotron oscillations




Results from ELENA Commissioning – with Antiprotons from the AD



- With Antiprotons from the AD (typically one or two 8hr-shifts per week)
 - Successful transfer from the AD, injection with bunch-to-bucket transfer, correction of injection oscillations tested, tests of instrumentation
 - Some antiprotons (fraction of injected beam) decelerated until end of ramp without electron cooling (lost at 100 keV arriving at the low energy plateau)




Beam in machine during ~6.5 s until end of 2nd ramp
(not yet nominal cycle, longer plateaus)



Test of the “Q-meter”:


- vertical plane excited
- horizontal tune seen without excitation
- verification of excitation required to have final version for restart 2018

Results from ELENA Commissioning – with Antiprotons from the AD



- Evolution of bunch shape after “bunch to bucket” transfer – RF in ELENA and synchronized w.r.t. AD
 - “Phase loop” damps synchrotron oscillations

Proper transfer between the two machines
Good conditions to work seriously on deceleration once beam is back




- Transverse pick-up signals before and after correction of mis-steering
 - Use pick-up sum and difference signals to detect turn-by-turn positions
 - Quantification and correction of injection mis-steering

Status of Electron Cooler



- Coordination and first design by CERN
 - Vacuum system constructed by CERN workshop
 - Magnetic system from company (including design and measurements)
 - Many correction circuits to compensate for imperfections and to obtain straight field lines
 - Issue with magnetic – very challenging – measurements and unexpected behavior around “toroids”
 - Cooler was mounted in autumn 2017 and installed a first time in December



Magnetic system during “acceptance tests”



Electron cooler mounting

Status of Electron Cooler



- Installed a first time in December, vacuum leak after first first bake-out in January
- Cooler taken out and dismantled to access and repair leak
- Re-installation last week, about four weeks for bake-out and other preparations
- Restart of ELENA Commissioning delayed by about 1½ months to beginning of April



Plans for 2018



- Consolidation of injection line and injection into ring
 - Increase of H^- injection efficiency and consolidation of improved reproducibility
 - Injection matching and empirical improvements
 - Setting up of proton injection and cycle: expect similar issues than for H^-
- Acceleration of H^- and possibly proton beams
 - For machine studies without taking precious antiprotons
- Commissioning of electron cooling
 - Behavior of 100 keV beam with magnetic system of cooler on?
 - Observe cooling preferably with beams from the source
 - Probably cooling studies to be done with protons (short H^- life-time due to stripping)
- Further consolidation of instrumentation and corrections (orbit, tune)
 - Final version of profile monitors in transfer lines!
- New isolation transformer for source and 100 keV H^- and proton beams in spring
- Setting up of complete antiproton cycle to complete ELENA commissioning
... highest priority to gain confidence before the installation of the new lines!
- First beams to GBAR
 - Coordination with cooling studies using protons and inversed polarity
 - H^- beams in spring, antiprotons probably later

Summary and Outlook



- ELENA ring installed and commissioning started
 - Progress H⁻ with beams from source and antiprotons from the AD, setting-up and testing of most systems – no showstopper
 - Less progress than expected at the beginning of the year due to various problems (e.g. poor reproducibility of the injection)
 - Electron available at the end of the year, but not yet for commissioning
- Aim for 2018
 - Completion of ELENA ring commissioning with cooler from April on
 - Get confidence that machine works properly by having an operational antiproton cycle with deceleration, cooling and extraction
 - First beams for GBAR
- Plans for after 2018
 - Installation and commissioning of electrostatic lines to old experimental area during CERN Long Shutdown 2 (LS2 scheduled in 2019 and 2020 mainly for LHC)
 - 100 keV antiprotons for all experiments after LS2 from 2021 on

Contributors to the ELENA Project

