



Science & Technology Facilities Council

**ASTeC**

*Accelerators in a new light*

# **VELA- Photoinjector Facility and CLARA- FEL test facility at Daresbury Laboratory**

Deepa Angal-Kalinin


XXV ESLS Workshop, 21<sup>st</sup>-22<sup>nd</sup> November 2017, Dortmund, Germany

# Timeline

<b>September'11</b>	Construction of VELA - Initiated following the capital investment announcement of 2.5M£ in DSIC from BIS.
<b>April'13</b>	<b>First electrons (ALPHA-X gun on loan from Strathclyde)</b>
<b>July'13-Nov'14</b>	Industrial and academic user experiments. Number of changes to the machine. Machine Development and characterisation.
<b>Dec'14-March'15</b>	<b>VELA shutdown for re-configuration of shielding for CLARA Front End.</b>
<b>April'15-Oct'15</b>	Machine Development and characterisation. Industrial and academic user experiments.
<b>Nov'15-March'17</b>	<b>VELA shutdown for CLARA Front End installation. 10 Hz gun on CLARA line and 400 Hz gun on VELA line.</b>
<b>March'17-Nov'17</b>	Resolved number of issues. Pulse stretcher on PI laser. <b>Accelerated beam from CLARA Phase 1 last week.</b>

# VELA

Versatile Electron Linear Accelerator (VELA) is a high performance, S-band RF photoinjector facility capable of delivering a high quality electron beam to two beam areas. It is located in the old outer hall of SRS at Daresbury Laboratory.





# Location





# VELA

## VELA Specification

Beam Energy	4 - 6 MeV
Bunch Charge	10 - 250 pC
Bunch length ( $\sigma_{t,rms}$ )	1 - 10 ps
Normalised emittance	1 - 4 $\mu\text{m}$
Beam size ( $\sigma_{x,y,rms}$ )	0.5 - 5 mm
Energy spread ( $\sigma_{e,rms}$ )	1 - 5 %
Bunch repetition rate	1 - 10 Hz

\*Not all parameters achievable simultaneously

### Notes:

1. VELA gun is from Strathclyde (ALPHA-X)
2. Max rep rate is 10 Hz but laser and RF capable of 400 Hz
3. 400 Hz gun will be commissioned in 2018.



# CLARA

*Compact Linear Accelerator for Research and Applications*

*An upgrade of the existing VELA Photoinjector Facility at Daresbury Laboratory to a 250MeV Free-Electron Laser Test Facility*


*Proof-of-principle demonstrations of novel FEL concepts and development of future accelerator technologies*

*Emphasis on Stability, Synchronisation and Ultra-short Pulse Generation*




# CLARA

- CLARA is a purpose built dedicated flexible FEL Test Facility
- CLARA is a scaled down version of an X-ray FEL containing all of the key technical components, where all lessons learnt can be directly applied to any future UK XFEL.
- The key objectives are:
  - To develop new methods for improving the quality of the light output from FELs
  - Prove new technologies
  - Develop the UK skill base
  - Lower the total cost of a UK XFEL
  - Lower the risks associated with UK XFEL.



# CLARA Schematic & Project Phases

CLARA assumes S-band acceleration and deflecting cavities and X-band linearization. Simulations show that Linac 4 could be swapped for X-band - would be excellent demonstration for FEL community.






# CLARA Layout

We would like to replace Linac 4 with **X-band** linac as test bed for CLIC technology on FELs – collaboration with CERN

High Energy Electron Beam



Linac 1 is 2m long **S-band**.

Linacs 2 to 4 are 4m long **S-band** devices previously installed on SwissFEL Injector Test Facility.


# Summary of Operating Modes

<i>MODE</i>	<i>FLAT – Seeded HG</i>	<i>ULTRASHORT – SSS</i>	<i>SHORT – HB-SASE</i>	<i>LONG – ML</i>
<b>Energy</b>	240 MeV	240 MeV	150— <b>240 MeV</b>	<b>150</b> – 240 MeV
<b>Pulse Duration</b>	250fs flat region	<b>50 —35 fs FWHM</b>	585 fs FWHM	<b>1.875 ps FWHM</b>
<b>Charge</b>	250 pC	<b>25—50 pC</b>	<b>250 pC</b>	250 pC
<b>Peak Current</b>	400 A	500 — <b>1500 A</b>	400 A	125 A
<b>Norm Emittance (mm-mrad)</b>	0.5 (Target) 1.0 (Max)	1.0 (Target) 1.5 (Max)	<b>0.5 (Target)</b> 1.0 (Max)	0.5 (Target) 0.8 (Max)
<b>RMS Energy Spread (keV)</b>	25 (Target) 100 (Max)	100 (Target) 150 (Max)	<b>25 (Target)</b> 120 (Max)	25 (Target) 75 (Max)
<b>Purpose</b>	<ul style="list-style-type: none"> <li>800nm Seeding and Harmonic Generation</li> </ul>	<ul style="list-style-type: none"> <li>Single Spike SASE (+ mode-locked single spike SASE)</li> </ul>	<ul style="list-style-type: none"> <li>100nm saturation</li> <li>Schemes only requiring spectral characterisation,</li> <li>Highest harmonic upconversion potential</li> <li>Shortest pulse durations in absolute terms.</li> </ul>	<ul style="list-style-type: none"> <li>266nm schemes requiring long wavelength modulation of the pulse energy (Mode-Locking, Mode-Locked Afterburner, Slice + Taper).</li> </ul>

# What will CLARA be able to do?

- **Example 1: Reducing the FEL output bandwidth**
- Prove that a new idea called **HB-SASE** actually works
  - Could then build it in from the start of the UK XFEL


Will work at any wavelength and any repetition rate, no fancy optics required!






# What will CLARA be able to do?

- Example 2: Generate few cycle pulses
- Prove that a new idea called **Mode-locked Afterburner** actually works
  - Could then build it in from the start of the UK XFEL
  - Able to probe ever faster processes (down to *sub-attosecond*)




# What will CLARA be able to do?

- **Example 3: Prove performance of 400 Hz Photoinjector Prototype**
- 1.5 cell S-band gun with RF probe
- Maximum gradient of 120 MV/m @100 Hz, or 100 MV/m @400 Hz
- 10kW cooling capacity
- Vacuum load lock system for easy replacement of cathode (e.g. Cu, CsTe, ...)
- **RF conditioning and beam characterisation with different cathodes planned in 2018.**






# CLARA Phase 1







VELA and CLARA



400 Hz S-band RF gun with photocathode exchange system installed on VELA line





# The Electron Hall

- CLARA is cited within the Electron Hall at Daresbury Laboratory
- The Electron Hall was not fit for purpose so has been completely refurbished
  - For beam stability we need the temperature of the facility to be very stable
  - Previously the temperature within the building varied by at least 15 °C over the year
  - Now the measured variation is less than  $\pm 1$  °C within the building
  - Within the shielded enclosure we have measured better than  $\pm 0.05$  °C, as required





# CLARA Status

- ***Phase 1, 50 MeV***
  - Installation complete.
  - Commissioning of 10 Hz gun and Linac1 underway.
  - First accelerated beam ( $\sim 50$  MeV) from CLARA Front End last week.
  - Beam characterisation, machine development and exploitation planned in 2018.
  - HRRG gun conditioning and characterisation on VELA line planned.
- ***Phase 2, 250 MeV***
  - Procurement of equipment is ongoing.
  - Assembly offline of all modules during 17/18.
  - All shielding assembled by Spring 2018.
- ***Phase 3, 100nm FEL Test Facility***
  - Detailed design stage now.
  - Undulator tender documents being prepared.

# Lessons Learnt

- Photoinjector
  - RF power meter measurements  $\leftrightarrow$  beam momentum
  - Dark current  $\leftrightarrow$  surface finish and processing of photocathode
  - Short Laser Pulse (control over longitudinal and transverse profiles was part of the long term development programme for CLARA)  $\rightarrow$  damage to laser transport optics components
    - Pulse stretcher installed
    - Presently using Gaussian profile in longitudinal and transverse, will need flat top to reach CLARA emittance target  $<0.5 \mu\text{m}$  (1  $\mu\text{m}$  max).
  - Precision on cathode dimensions
- Delays in procurement and delivery of some critical components.
- Not meeting technical specifications of few components.
- Unexpected issues, e.g. screwing of IR detectors after completion of waveguide assembly.

# Summary

- CLARA is a purpose built dedicated flexible FEL Test Facility at the heart of the FEL R&D programme
  - To develop new methods for improving the quality of the light output from FELs
  - Prove new technologies
  - Develop the UK skill base
  - Lower the financial and technical risks associated with UK XFEL.
  - We are keen to work with international partners on all aspects of accelerator and FEL technology
- CLARA Status
  - Phase 1 now being commissioned
  - Procurement of remaining items for CLARA is ongoing
  - Electron Hall refurbishment is complete
  - First lasing in 2021 (subject to funding timeline)



# Thanks to everyone who is contributing to the CLARA project



# INTELLIGENT CONTROLS FOR PARTICLE ACCELERATORS

30-31 JAN 2018

DARESBUURY LABORATORY



Where does the UK accelerator community want  
to be in 5-10 years in terms of controls?

To achieve their ultimate performance, the next generation of particle accelerators require advances in controls systems and feedback. Proposed techniques to realise this include; machine learning through neural networks, genetic algorithms, artificial intelligence, and adaptive controls. This workshop aims to discuss the state of the art and explore promising approaches for future development.

#### Organising Committee

James Henderson, Lancaster University.  
Peter Williams, STFC.  
Duncan Scott, STFC.

[WWW.COCKCROFT.AC.UK/EVENTS/ICPA](http://WWW.COCKCROFT.AC.UK/EVENTS/ICPA)