

# Overcoming the Challenges of the ITER Magnets



**Neil Mitchell**

**ITER Organization, on behalf of the ITER, Domestic Agency and  
Supplier Magnet Teams**

with particular thanks to Arnaud Devred, Sandro Bonito-Oliva, Nori  
Koizumi, Nick Clayton

EUCAS

1

*The views and opinions expressed herein do not necessarily reflect those of the ITER Organization*

# CONTENTS



1. Progress on Site Construction

2. Status of ITER Magnets

3. The three main challenges

I. Conductor Issue. Degradation of large Nb<sub>3</sub>Sn  
CICC

II. Structural Issue. Tolerances on structures

III. Electrical Issue. High voltage insulation

# Progress on the Site Construction

# ITER Site Construction – 1 (June 2013)


4



**Tokamak Building  
Pit and Foundation  
(17 m deep; 120 x 90 m)**




**PF Coil Winding  
Building  
(17 m high; 252 x 45 m)**



**ITER TKM  
Pit**

**ITER Headquarter Building  
(4 story; 16,000 m<sup>2</sup>)**





# ITER Site Construction – 2 (April 2015)

5



**Cryostat  
Assy Building  
(5,500 m<sup>2</sup>)**



**Plexiglass Formwork for  
Bioshield Construction  
(3.2 m thick walls)**



**TKM Assy Hall  
(60 m high; to be outfitted  
with 2 x 750 t cranes)**

**ITER TKM  
Pit**





# ITER Site Construction – 3 (April 2016)

6



Assembly Hall  
with 2 x 750 t  
cranes

Transformers

400 kV Switchyard

Cryoplant Bldg.


Service Bldg.

ITER TKM  
Pit

Water Detritiation Tanks  
(4 x 20 m<sup>3</sup> and 2 x 100 m<sup>3</sup>)



# ITER Site Construction – 4 (July 2017)






# Status of Magnets



# Overall Magnet System

9







# Superconducting Magnet In-Cryostat Environment

10


Magnets and Cryostat



Magnets,  
Cryostat and  
Thermal  
Shield




Magnets,  
Cryostat and  
VV





# ITER Magnet System – 1

11




- The ITER magnet system is made up of
  - **18 Nb<sub>3</sub>Sn Toroidal Field (TF) Coils,**
  - **a 6-module Nb<sub>3</sub>Sn Central Solenoid (CS),**
  - **6 Nb–Ti Poloidal Field (PF) Coils,**
  - **9 Nb–Ti pairs of Correction Coils (CCs).**



## ITER Magnet System



Pair of  
TF Coils




CS  
Coil



# ITER Magnet System – 2

12


- ITER magnets are supplied with current/cryogenic fluids by **31 Feeders**.



**ITER Feeder System**



- The magnet Feeders include
  - **Nb–Ti CICC busbars (MB & CB),**
  - **Ag-Au(5.4%) BiSCCO 2223 HTS current leads.**



**Detail of CC Feeder**



**68 kA Trial Lead Developed by ASIPP**



# ITER Conductor Supply

13


## $\text{Nb}_3\text{Sn}$

88 km, 825 t  
215 kIUA  
(334 M€)

## TF Conductors



43 km, 745 t  
90 kIUA  
(140 M€)



## CS Conductor



## PF Conductors



## MB Conductor




65 km, 1224 t  
81 kIUA  
(126 M€)

## Nb-Ti

10.7 km (CC)  
3.7 km (MB+CB)  
2.13 kIUA (3.3 M€)



## CC Conductor



## CB Conductor




# ITER Conductor Manufacture




**Strand  
Production**




**Jacket  
Production**



**Compaction**



**Spooling**



**Final  
Tests**




# ITER Strand Status (31 May 2017)

15


- **Nb<sub>3</sub>Sn** for **TF**: ~100% complete.

TF Strands Production Dashboard




- **Nb<sub>3</sub>Sn** for **CS**: ~100% complete.


CS Strands Production Dashboard



PF1&6 Strands Production Dashboard



PF2-5 Strands Production Dashboard



CC and Feeder Strands Production Dashboard



- **Nb–Ti Type 1** for **PF1&6**:  
100% complete since Aug. 2014.

- **Nb–Ti Type 2** for **PF2-5**:  
~92% complete.

- **Nb–Ti Type 2** for **CC & Feeder**:  
100% complete since Jul. 2013.


- Pre-ITER world production of Nb<sub>3</sub>Sn was ~15 t/year; it has been scaled up to ~100 t/year for the last 4 years.

Data compiled by D. Kaverin (ITER-CT)


# Main Features of ITER TF Coils

16


- The TF coil is made up of a winding pack (**WP**) inserted inside a thick **coil case** made of welded, stainless steel **segments**.



TF Coil Structure



Pair of TF Coils



TF Coil Winding Pack

- Each **winding pack (WP)** comprises **7 double pancakes (DPs)**, made up of a **radial plate** with precisely machined grooves into which the **CICC** is transferred upon heat treatment completion.





# ITER TF DP Manufacture – 1


17



**Conductor Spool**




**DP Winding (12 m x 9 m)**



**Elec. Terminal**




**He Inlet**





**DP Heat Treatment**



**Radial Plate Section Welding**



**Radial Plate Assembly**



**Transfer of HTd DP into  
Radial Plate**

**Courtesy of A. Bonito-Oliva (F4E)**



# ITER TF DP Manufacture – 2

18



**DP Turn Insulation  
inside Radial Plate**



**Cover Plate Welding**



**DP Ground Insulation**



**Hi-Post Test on  
Impregnated DP**



**Impregnated DP**



**DP Loading into Vacuum  
Impregnation Mold  
(radiation-hard cyanate  
ester resin)**

**Courtesy of A. Bonito-Oliva (F4E) and N. Koizumi (QST)**

# TF Coil Production Status (August 2017)

19



	EU	JA
DP Winding	70	31
DP Heat Treatment	67	29
DP Transfer, Turn Insulation, Welded	49	17
DP Completed	44	14
WP Insulation	4	1
WP Impregnated	2	0
WP Terminal Region Assembled	1	0

**18 +1 WPs**  
**1 WP = 7 DPs**  
**133 DPs**  
**(70 EU, 63 JA)**


1<sup>st</sup> and 2<sup>nd</sup> complete WPs



- 4<sup>th</sup> production DP being transferred
- 3<sup>rd</sup> production DP transferred and being insulated
- 2<sup>nd</sup> production DP being transferred and being insulated.
- 1<sup>st</sup> production DP transferred and being insulated

Courtesy of  
F4E and ASG

**Assembly Line at ASG**





# Magnet Supports

20



1<sup>st</sup> TF  
Gravity  
Support

(below) thermal cycle and pressure test



PF3, 4, 5  
U shaped  
clamps



PF 3- PF 4  
strut under  
welding




courtesy Zhang Bo and HTXL



# PF1 Coil Status (April 2017)

21

- **RFDA** has completed winding of **two** (out of 8) **PF1 Double Pancake**.



**1<sup>st</sup> PF1 DP Winding** (September 2016)



**1<sup>st</sup> PF1 DP VPI** (April 2017)



**2<sup>nd</sup> PF1 DP Winding** (April 2017)

**Courtesy RFDA & Efremov Institute**



# PF2-6 Coil Status

22

- **EU** suppliers have completed winding of dummy double pancakes for PF5 & PF6 and have started winding of first production Double Pancakes.



**PF5 Dummy DP Winding** (February 2017)

Courtesy F4E & B.-S. Lim (ITER-CT)

**1st PF6 DP Winding** (Apr 2017)



**2nd PF6 DP Winding**(underway)  
8<sup>th</sup> DP now complete





2.1 m



**1st CS Module**



Assembly platform  
during final inspection  
at Robatel  
Technologies

Commissioning  
turn over station  
with dummy  
module



**Courtesy USIPO & GA**


- **USIPO supplier** has completed stacking and heat treatment of **first** (out of 7) **CS Coil Module** and is proceeding with turn insulation (each module is made up of 6 hexapancakes and 1 quadropancake).
- Winding of **2<sup>nd</sup> module** is completed; winding of **3<sup>rd</sup> module** has started.

# ITER Magnet Feeder Layout

24



- **The magnet feeders** are deeply integrated into to the tokamak.






# PF4 Cryostat Feed-Through

25


**First magnet component** to be installed in tokamak pit will be **PF4 Cryostat Feed Through (CFT)**, which is a captive component.



# PF4 Cryostat Feed-Through (Aug-Sep 2017)


26

- Manufacture is completed at ASIPP and shipping to IO is underway



**PF4 CFT**

Thermal Shields ready  
for Assembly



Complete



Containment Duct Assembly



Horizontal Vacuum Duct  
Machining




Internal  
Pipes





# Main Challenges of the Coil Procurement (2001-2017)

- ❑ Conductor Degradation
  - ❑ Tolerances on TF Coil Geometry
  - ❑ High Voltage Insulation
- 

# Conductor Issue. Degradation of large Nb<sub>3</sub>Sn CICC


28

## The Design Challenge

- ❑ Nb<sub>3</sub>Sn is a brittle compound that easily fractures under tension
- ❑ Form cable from wires then heat treat to make Nb<sub>3</sub>Sn.
- ❑ Wires separated to allow Helium at 5K to flow and block AC losses
- ❑ Wires must be strongly supported mechanically

=> Challenge is to avoid filament cracks

Nb<sub>3</sub>Sn filament cracks






# Demonstrating the degradation can be overcome


- ❑ Short (~3m) conductor lengths tested for all 8 strand types
- ❑ Tests of “insert coils” with a conductor length of ~50m, a diameter of about 1.5m and a height of about 2m.
- ❑ ‘inserted’ into the bore of a very large superconducting coil
- Close synchronisation with the industrial development of Nb<sub>3</sub>Sn wire and cable
- Coil tests, in 2000-2002, led to adjustments in the wire and conductor design.
- Coil tests in 2014-2017 have confirmed the performance of the Central Solenoid conductor *but leave open some issues on the Toroidal Field (TF) conductor.*



**CS Insert test results confirm stable behavior as a function of EM and thermal cycling**




SULTAN facility with open end cap showing conductor sample hanging vertically in front



# Latest TF Insert Results

- ❑ TF conductor successfully resists the magnetic forces, with an acceptable level of performance loss
- ❑ Triggering of repeated WUCD degradation by EM cycles in the TFI is more persistent than expected
- ❑ Anticipated fracture of Nb<sub>3</sub>Sn material, conductors *were designed with margin*.
- ❑ TFI tested under much more severe set of conditions than in ITER

- Conservative extrapolation of results to ITER itself shows *sufficient margin*
- Higher level of degradation than foreseen, EM triggers extra WUCD degradation.



## Steps to manage degradation through better understanding

- Extension of the present TF insert test
- Extra programme of conductor testing
- Thresholds exist for EM-WUCD interaction: use tests to identify, adjust operation to reduce number of 'triggers'
- If needed, new insert coil to exactly replicate the TF conductor operating life.



# Structural Issue. Tolerances on structures

31


Where dimensional errors have an impact

- Fitting of components during assembly so that load paths still match design intention
- Inability to place component in available space
- Field errors

What drives tolerances

- Manufacturing requirements/capability
- Installation requirements/capability
- Measurement errors and component deformations under gravity
- Cumulative build up during manufacturing & assembly.... tolerances depend on other components

*TF coils & structures are the core which drive the rest*



TF coil interfaces (green)

# Structural Build-up of TF Coils

Key is manufacturing of accurate radial plates to hold the conductor


- Decouple geometric uncertainties of conventional bonded WP due to insulation from WP final geometry
- Eventual solution (after many trials) is to assemble plates from sections, with squared ends, and then local machine groove continuation

Below: radial plate section

Right: assembly of sections



*Courtesy of F4E*




Completed radial plate



**Accuracy <1mm in flatness and inner/outer profiles**






- TF structure calls for mass production of ~ **4500 tons** of large, high-strength, **316LN steel** components.
- Components are made of TIG welded assemblies of **forged plates up to 200 mm** and require **tight deformation control** to achieve final shape.
- Three suppliers have been selected: **MHI** and **Toshiba** (Japan) and **HHI** (Korea).
- **Series production** of AU, AP, BU and BP sub-assemblies are underway at all 3 suppliers.

# Large Structure Manufacturing

34





Completed  
BU and BP  
sections



Fitting test of  
AP on AU



~50mm  
↔



Picture of mock up (b) during  
manufacturing

Typical machining accuracy 0.5-1mm


Courtesy QST, MHI and HHI



## 35

# Vertical insertion route

- Lower WP into nose section
- Lower BU outer section onto WP
- Weld AU to BU: *control distortion*
- Insert AP and BP (spring into place)
- Weld AP to AU and BP to BU: *control distortion*
- Fill gap between winding pack and case
- Machine case






## Target tolerance on interface surfaces <2mm

# Development of Insulated Adjustable Keys and Bolts


36

Example IOIS: Using adjustable sleeves, coil misalignment of 12mm can be accepted

Mock-up trials, full size



Adjustable sleeve





# Electrical Issue. High voltage insulation

37

## Challenges

- Unprecedented voltage levels for s/c coils, typical design range 20-30kV driven by coil energy and limits to s/c cable size
- Cryogenic (differential expansion) and vacuum (Paschen breakdown) environments
- Nuclear environment for some of the coils,

## Solutions

- Solid insulation systems, low void content
- Polyimide based electrostatic barriers
- Robust ground screens
- Detailed procedures developed and tested for weak points such a signal wire lead-outs



### TF coil test voltages

Acceptance and Manufacturing Test Voltage Levels

	DC Acceptance Test kV	AC Acceptance Test kV	DC Manufacturing Test kV	AC Manufacturing Test kV	Paschen Manufacturing Test kV
Turn to RP	>2.2	0.4	>2.2	>0.4	2.2
DP to DP	>3.4	0.8	>3.4	>0.8	3.4
WP to ground	>19.0	2.5	>19.0	>2.5	8.0

# Solid Insulation in the Coils

38



Blend of cyanate ester and DGEBA resin gives x2 improvement on radiation resistance



- Developed 2005-2008
- Many challenges in industrialisation
- Exothermic reaction in curing can become uncontrolled
- Some catalysts considered endocrine disruptors or calcinogens
- Etched polyimide film has increased shear strength





# Hand wrapped insulation in feeders and on joints

- Insulation specimens manufactured with pre-preg from different suppliers. Processing conditions optimised
- Pre-preg surface conditions important for bonding and voids
- Pressure important to reduce void fraction to 2-3%



Some material / process combinations result in insulation with significant voids, leading to poor electrical performance




The final selected materials produce largely void-free specimens





# Insulation Manufacture – Feeder Busbars & Joints

40



Feeder Wrapping



Ground screen



Silicon wrap to compress during curing

The joints have a complex outer geometry.  
Insulation will be made during machine assembly  
Insulation is cured in a vacuum bag.





On the magnets, we are gradually getting through the problems of 'First of a Kind' production

We can expect a busy 1-2 years of 'second level' manufacturing problems but we expect these to be containable

Of the 3 main challenges in the last 10 years

- Insulation is solved
- Tolerances have one last manufacturing step to solve and then we have to address *the machine assembly problems*
- Conductor degradation needs to be properly understood but we have routes to manage it if necessary