






First Operation of the Complete KATRIN Superconducting Magnet Chain

4LO2-06, Sept. 21, 2017

Woosik Gil, Institut für Kernphysik (IKP), KIT





Outline



- Part I: Introduction to KATRIN
 - Karlsruhe Tritium Neutrino Experiment (KATRIN)
 - Measurement principle
 - Chain of the complete KATRIN SC magnets
- Part II: First operation results of the SC magnet chain for "First-Light-Plus" measurement campaign
 - Quench Detection
 - Beam alignment
 - B-field stability
- Summary and Outlook

Outline



- Part I: Introduction to KATRIN
 - Karlsruhe Tritium Neutrino Experiment (KATRIN)
 - Measurement principle
 - Chain of the complete KATRIN SC magnets
- Part II: First operation results of the SC magnet chain for "First-Light-Plus" measurement campaign
 - Quench Detection
 - Beam alignment
 - B-field stability
- Summary and Outlook




<u>Karlsruhe Tritium Neutrino experiment (KATRIN)</u>




Neutrino (v)–mass?

→ Influence on universe structure formation?



 \rightarrow Absolute v_e -mass?

\rightarrow Model-independent measurement of m²(\overline{v}_e) based on energy-momentum conservation of tritium β-spectrums



Requirements:

- 1. High source luminosity
- 2. High energy resolution
- 3. Low background rate

- \rightarrow 10 times more sensitivity of 0.2 eV/c² (C.L.90%)
- \rightarrow Possibility of 0.35 eV/c² in 5 σ after 3 years-data-taking


http://www.katrin.kit.edu/

KATRIN Design Report 2004, FZKA 7090




Measurement principle of KATRIN





- Magnetic Adiabatic Collimation with Electrostatic (MAC-E*) filter
 - Adiabatic transport: $\mu = \frac{E_{\perp}}{R} = const.$
 - Electrostatic filter (U) in MS: 18.6 kV
 - Energy resolution: $\Delta E = E_0 \frac{B_A}{B_{max}} = 18.6 keV \frac{0.3 mT}{6 T} = 0.93 \text{ eV}$
 - Max. acceptance angle of β :

$$\theta_{max} = \arcsin(\sqrt{B_s/B_{max}})$$



Transmission of β with $E_{\parallel} > U$, $\theta < \theta_{max}$


* Picard et al., 1992





Chain of the KATRIN SC solenoid magnets





Dr. Woosik Gil


Main components of the KATRIN experiment







16 m long, 310 A 3.6 T, 5.6T, 3 x 1.6 MJ WGTS-> Sept. 2015









←DPS
7 m long,5.6 T

CPS→ 200 A, 172 H

July, 2015 3.4 MJ, 1.6 m³



Outline




- Part I: Introduction to KATRIN
 - Karlsruhe Tritium Neutrino Experiment (KATRIN)
 - Measurement principle
 - Chain of the KATRIN SC magnets
- Part II: First operation results of the SC magnet chain for "First-Light-Plus" measurement campaign
 - Quench Detection
 - Beam alignment
 - B-field stability
- Summary and Outlook



Quench detection by the Magnet Safety System

- Quench detection by considering M_{ii} at 50 % of I_D
 - Quench in DPS-M1 during ramping on Oct. 11, '16
 - Successful quench validation by WGTS-MSS (*)
 - Slow discharge (SD) of WGTS without quench
 - Distinct quench detection by MSS of WGTS → save of large amount of LHe (2 m³) and time!



Successful operation of the MSS

*Gil, MT25




500

dU (mV)

-500

GD3



"First-Light" on Oct.14, 2016




CERN Courier, Dec. 2016

FACILITIES

KATRIN celebrates first beam

On 14 October, the KArlsruhe TRItium Neutrino (KATRIN) experiment, which is presently being assembled at Tritium Laboratory Karlsruhe on the KIT Campus North site, Germany, celebrated "first light". For the first time, electrons were guided through the 70 m-long beamline towards a giant spectrometer, which allows the kinetic energy of the beta electron from tritium beta decays to be determined very precisely. Although actual measurements will not get under way until next year, it marks the





DPS-M1 quenched 3 days before!

Low energetic electron source

B-fields in non-standard configuration!

→ 'First-Light-Plus' measurement campaign!




Continuous magnet operation for about 2 weeks



- First-Light-Plus
 - Beam alignment check mostly at 20 % of I_D
 - Other tests: electrostatic dipoles for ion-elimination, background signals, etc.

Stable operation for this campaign:


- Cryogenic systems
- Compressors
- Vacuum systems
- Power supplies
- Slow control systems




Check of beam alignment




- Full beam illumination on RW
- 1. Changing magnetic fields sectionwise!
- Changing electrostatic voltages on electrodes and RW
- → No issue for tritium with 18 keV becasue of low static energy (recently verified by Krypton measurement in July, 2017).



Nov. 22, 2016



DET: from 25% to 20%




→ Unobstructed electron transmission for the designed magnetic flux of 191 Tcm²


B-field stability of the magnets

RS WGTS

B-field drift of the WGTS in driven mode



B-field drift of the RS magnet in persistent mode




→ The B-field stabilities of all the magnets are within the specification!

Summary and Outlook



Summary

- Successful first light test in Oct. 14, 2016, Successful commissioning measurements with 83mKr at 70 % of I_D in July, 2017.
- Two weeks continuous operation of the complete KATRIN magnets without cooling issue.
- Magnetic field stability of the magnets are within the specifications.
- Unobstructed electron transport in the magnetic flux of 191 Tcm²
- Distinct quench detection by MSS allows us to save a large amount of LHe and cryogenic recovery time!



Outlook

- First tritium data in June, 2018 after tritium loops' completion.
- KATRIN operation for about 5 years, meaning 3 years effective data taking

Thank you for your attention!






KATRIN Collaboration:

130 members, 19 institutions in 5 countries: DE, US, UK, CZ, RUS







WESTFÄLISCHE WILHELMS-UNIVERSITÄT

http://www.katrin.kit.edu/













Supplemental slides



MAIN DATA OF THE KATRIN S.C. MAGNETS



Items	WGTS-R	WGTS-C	WGTS-F	CPS	RS	DPS	PS	PCH	DET
Mode	DM	DM	DM	DM	PM	PM	PM/DM	PM	PM
I_d (A)	309.85	308.84	208.84	200	66.71	71.02	157	86.98	56.154
B_d (T)	3.6	3.6	5.6	5.6	4.7	5.0	4.5	6.0	3.6
L (H)	27.1	33.6	74.5	172	291	290	77.3	428	653
E (MJ)	1.30	1.60	1.62	3.44	0.65	0.73	0.95	1.62	1.03
$J (A/mm^2)$	151	151	100	117	144	155	160	196	185
Modules	3	2	2	7	1	5	2	1	1
Coils	9	6	6	7	3	15	2	3	1