

CONS and HL-LHC day Analysis of needs from BE-BI

Rhodri Jones on behalf of the BE-BI Group

Tuesday 26th September 2017

BE-BI Approved Requests



LHC-CONS & R2E Approved Requests

(Currently no approved HL-CONS requests for BE-BI)

Item	Description	Approved Budget (MCHF)	Spending ⇒ 2020 (MCHF)	Spending 2021-2025 (MCHF)
	R2E Consolidation of Standard LHC BPM system (Radiation Hard Components)	2.85	2.15	0.70
1	LHC-CONS Consolidation of Standard LHC BPM system (Standard Components)	4.20	0.5	3.70
	TOTAL	7.05	2.55	4.40

- Complete consolidation of the LHC BPM system
 - Tunnel & surface electronics
 - Aiming to be ready for LS3
 - Could wait for deployment in LS4
 - Need components manufactured & ready as back-up for post LS3 operation
 - Assumes re-use of existing fibre-optic cabling network
 - Replacement due to ageing or radiation damage not foreseen
- HL-WP13
 - Special electronics for new stripline monitors in LSS1 & LSS5



LHC-CONS & R2E Approved Requests

Item	Description	Approved Budget (MCHF)	Spending ⇒ 2020 (MCHF)	Spending 2021-2025 (MCHF)
2	R2E Development of Rad Hard Electronics for LHC BLM	0.3	0.3	
	LHC-CONS Development of Rad Hard Electronics for LHC BLM	0.2	0.2	
	HL-13 Production & Installation of Rad Hard Electronics for LHC BLM (LSS)	0.7		0.7
	TOTAL	1.2	0.5	0.7

- Development of radiation hard ASIC
 - Eliminates need for long cables
 - More margin between quench threshold & noise level



LHC-CONS Approved Requests

Item	Description	Approved Budget (kCHF)	Spending ⇒ 2020 (kCHF)
3	Consolidation of Fast BCTs (complete) Complete detector & acquisition electronics renovation	135	135
4	Consolidation of Interlock BPM System (LS2) Acquisition electronics renovation	300	300
5	VME fan replacement (LS2) Replacement of Power Supply and Fan-Tray Units	400	400
6	Consolidation of Standard LHC BLM System (LS2-LS3) Surface electronics renovation	1000	1000
7	Consolidation of LHC Wirescanners (LS2) Control electronics renovation	150	150



BE-BI Unapproved Requests by CONS or HL Baseline



Unapproved LHC-CONS / HL Baseline Requests

Item	Description	Budget Request (kCHF)	Allocated from	Priority
8	Unapproved LHC-CONS Consolidation of Head-Tail Instability Monitors	250	2019 to 2020	2

- Essential tool to understand origin of instabilities
 - Most recently showing that fast rise-time in 16L2 instability from tail break-up
- Consolidation Proposal
 - Replacement of Outdated Oscilloscope Based Acquisition System
 - Runs old, unsecure windows version
 - Limited in memory depth
- Proposal
 - Replace existing system with new state-of-the-art electronics during LS2
 - Off the shelf equipment can be bought as soon as money available
 - Some SW (BI & possibly CO) manpower required to adapt to existing framework
- Need for HL
 - Monitor of reference for instability analysis
 - WP13 building more sensitive higher frequency versions but will need benchmark



Unapproved LHC-CONS / HL Baseline Requests

Item	Description	Budget Request (kCHF)	Allocated from	Priority
9	Removed in HL Rebaselining Renovation of Wirescanner Mechanics	680	2021 to 2025	1

- Reference beam profile measurement system
 - Provides cross calibration for all other profile measurement systems
- Consolidation Proposal
 - Replacement of old mechanics
 - Design & some components date from LEP era
- Some consolidation already necessary to address reliability issues
 - New bellows, new ferrite holder.
 - New control electronics already funded by LHC-CONS
- Proposal
 - Complete replacement of wirescanner mechanics
 - Use experience from LIU upgrade of all injector scanners
- Need for HL
 - Only way to ensure reliability of this essential system after LS3



BE-BI New requests in view of HL-LHC installation

(to meet HL-LHC goals)



New LHC-CONS / HL-CONS Requests

Item	Description	Budget Request (MCHF)	Allocated from	Priority
10	LHC / HL-CONS Consolidation of Beam Gas Ionisation Profile Monitors	1.5 to 2.5	2019 to 2025	2
11	HL-CONS Consolidation of Standard BLM Tunnel Electronics	~ 4	2023 to 2028	1



ITEM: 10, Beam Gas Ionisation Profile Monitors

Summary of the Request				
Total Budget request	1.5 MCHF (no magnet) to 2.5 MCHF (SC magnet)	Budget to be allocated in years	2019 - 2025	
Material budget request	1.25 – 2.25 MCHF	Personnel available in addition to personnel budget request	YES	

Personnel budget request (M2P budget)

250 kCHF - Fellow/PJAS + Student

. No burnel by by no programment of inchange at injection

- No bunch by bunch measurement of ion beam sizes at injection
- No measurement of beam size during acceleration

Consequences of delay of request to LS4 or later

Consequences of suppression of request on HL performance

Non-optimised ion operation for initial HL Run



ITEM: 10, Beam Gas Ionisation Profile Monitors

- LHC Beam Gas Ionisation Profile Measurement System
 - For measurement of transverse beam sizes of primarily ion beams
 - Wirescanners limited in use to low intensity beams
 - Synchrotron light monitor inefficient for ions at injection energy & on ramp
- Current System
 - Never became fully operational due to many issues
 - Suffers from significant space charge effects for proton beams above 2TeV
 - Detector & camera performance issues worked on and solved in 2016
 - Had to be removed in EYETS due to RF heating (impedance)
 - Tank needs complete re-design to make it impedance compliant
- Progress in the injectors
 - Duplicate LHC system now being made operational in the SPS
 - Showing some nice results
 - New technology of in-vacuum Pixel Detectors pioneered by LIU for PS
 - Results promising & removes need for regular exchange of in-vacuum MCP
 - Should be able to work with much lower gas pressure
- Need for HL
 - Could be alternative to BGV (SC magnet > 2T for use with p+)
 - Propose review of all beam profile measurement devices for HL
 - To be scheduled early 2019 after analysis of Run 2, SPS and PS results

ITEM: 11, Standard BLM Tunnel Electronics

Rational of the request					
Total Budget request	~ 4.5 MCHF	Budget to be allocated in years (from-to)	2024 – 2028		
Material budget request	~ 4 MCHF	Personnel available [y/n] in addition to personnel budget request	YES		
Personnel budget request (M2P budget for MPAs and fellows)	0.5 MCHF – Fellow/F	PJAS + Students			

Consequences of suppression of request on HL performance

No HL operation due to unavailability of BLM system

Consequences of delay of request to LS4 or later

- Installation anticipated for LS4
- Later deployment risks less reliability (radiation) & unavailability of spares



ITEM: 11, Standard BLM Tunnel Electronics

- LHC BLM System composed of 3 parts
 - Radiation tolerant tunnel electronics
 - Fibre-optic transmission
 - Surface electronics for data treatment & threshold evaluation
- Surface Electronics
 - To be renovated in or shortly after LS2
 - Fully funded by LHC-CONS
- Tunnel Electronics
 - Designed for 20 year LHC lifespan
 - Expected end-of-life after LS4
 - R&D on replacement needs to start before LS3
 - All components to be qualified for use in radiation environment
- Fibre-Optic Communication
 - As for LHC BPM system currently no provisions to replace existing BE-BI fibre-optic distribution in LHC
- Need for HL
 - Vital for HL Operation
 - Cannot function without a fully reliable BLM system



Summary

Priority	Item	Description	Approval Status:
1	11	Standard BLM Tunnel Electronics	NEW
1	10	Consolidation of Beam Gas Ionisation Profile Monitors	NEW
2	8	Consolidation of Head-Tail Instability Monitors	Unapproved LHC-CONS
2	9	Renovation of Wirescanner Mechanics	Unapproved HL-Baseline

- Consolidation of Profile Monitoring Systems
 - Review of all possible techniques foreseen after Run 2
 - Limitations of existing systems (wirescanners & synchrotron light)
 - Best Alternative(s) for HL-LHC (protons & ions)
 - Beam Gas Vertex, Beam Gas Ionisation Monitor, Beam Gas Curtain,....
 - Decision to be made on which to support
 - Some funding already foreseen from HL-WP13
 - Will need to be complemented by CONSOLIDATION

